# CURRENT CONDITIONS REPORT

**GM POWERTRAIN BEDFORD FACILITY**
**105 GM DRIVE**
**BEDFORD, INDIANA**

**EPA ID# IND006036099**

**Volume II - Appendix A through E**

**Prepared For:**
**GM/ENCORE**


**Prepared by:**
**Conestoga-Rovers & Associates**

8615 West Bryn Mawr
Chicago, Illinois 60631

Office: (773) 380-9933
Fax: (773) 380-6421

web: http:\\www.CRAworld.com


**MAY 25, 2001**
**REF. NO. 013968 (1)**

# APPENDIX C.1

# IDNR WATER WELL LOGS

# Record of Water Well

Indiana Department of Natural Resources

*Reference Number*
**220931**

*Driving directions to well*
EAST OOLITIC, 1 MILE EAST OF OOLITIC, LOT #30;

*Date completed*
Thu, Jul 26, 1962

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | WILMA HUBBARD | RRT. #2, BEDFORD,IN. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RRT. 6, BOX 13, BEDFORD, IN. | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 20.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*
*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

*Grouting Information*
*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*
*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*
*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SE 1/4 of the NW 1/4 of Section 3 *Topo map:* OOLITIC
*Field located by:* U *on:* Mon, Jul 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1600 *Ft S of NL:* 2000
*Ground elevation:* 550.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 542430.0 *UTM Northing:* 4305503.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 13.0 | BLUE LS-HARD |
| 13.0 | 14.0 | OPEN HOLE |
| 14.0 | 23.0 | BLUE LS-HARD |
| 23.0 | 51.0 | GRAY LS-SOFT |
| 51.0 | 62.0 | BLUE SH-SOFT |
| 62.0 | 79.0 | BLUE LS-SOFT |
| 79.0 | 100.0 | BLUE SH-SOFT |

*Comments*

4

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220852** | APP 1 MI N OF BEDFORD IN, 1 BLK W OF PEERLESS RD, KNOWN AS WALNUT HEIGHTS. | Fri, Nov 30, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | PULLAS CHILDERS CONST | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN, RR6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.05 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 135.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* 1/4 of the NW 1/4 of the SW 1/4 of Section 2 — *Topo map:* BARTLETTSVILLE
*Field located by:* — *on:*
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* U — *on:* Mon, Jul 01, 1963
*Subdivision name:* WALNUT HEIGHT — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifer elevation:*
*UTM Easting:* — *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 100.0 | BLANK |
| 100.0 | 108.0 | BLUE LS HARD |
| 108.0 | 130.0 | GRAY LS SOFT |
| 130.0 | 200.0 | BLUE SHALE |

***Comments*** LAWRENCE

# Record of Water Well

5

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220857** | BRACKENRIDGE RD, 1 MI N BEDFORD CITY LIMITS. | Thu, Jul 21, 1960 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | JESSIE STIGALL | BEDFORD RR4 | |
| Building Contractor | | | |
| Drilling Contractor | PAUL SCOTT | RR4, BLOOMINGTON IN | |
| Equipment Operator | PAUL SCOTT | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test* — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. — *Static water level:* ft.

*Grouting Information* — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Well Abandonment* — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Administrative*

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 2 — *Topo map:* BARTLETTSVILLE
*Field located by:* HS — *on:* Fri, Nov 04, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 1000 — *Ft E of WL:* 1200 — *Ft S of NL:*
*Ground elevation:* 670.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* 543916.0 — *UTM Northing:* 4304789.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | BLANK |
| 6.0 | 40.0 | RUSTIC BUFF LIME MD |
| 40.0 | 130.0 | BLUE LIME HARD |
| 130.0 | 140.0 | BLUE LIME SOFT |

*Comments* MC

6

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220862** | 2 MI N BEDFORD IN, BRECKINRIDGE RD NEAR DIVE SCHOOL HOUSE. BAHR'S HILAND BLK D, LOT 1. N M ST. | Tue, Jan 26, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HOWARD ELKINS | RR4, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, B0X 13, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 2 *Topo map:* BARTLETTSVILLE
*Field located by:* BRUNS *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 50 *Ft E of WL:* 300 *Ft S of NL:*
*Ground elevation:* 700.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 544039.0 *UTM Northing:* 4304515.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 109.0 | BLANK |
| 109.0 | 150.0 | WH LS HARD |

***Comments***

MC;

# Record of Water Well

7

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220867** | 1 MI N OF IN SR 58 ON MT PLEASANT RD, RR4 BEDFORD IN. | Tue, Sep 10, 1963 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | GUY S. WEVER | RR4, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN, RR6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 250.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.08 gpm for hrs.
*Drawdown:* ft. *Static water level:* 170.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SE 1/4 of the NW 1/4 of Section 1 *Topo map:* BARTLETTSVILLE
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2500 *Ft S of NL:* 2600
*Ground elevation:* 630.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 625.0 *Aquifer elevation:*
*UTM Easting:* 545914.0 *UTM Northing:* 4305331.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | CLRT |
| 4.0 | 17.0 | BROKEN LS |
| 17.0 | 39.0 | BLUE LS HARD |
| 39.0 | 55.0 | GRAY LS HARD |
| 55.0 | 250.0 | BLUE SHALE SOFT |

*Comments* MC 625;

8

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217404** | APP. 3MI E OF BEDFORD, IND. ON US HIGHWAY 58 | Sat, Jan 08, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | NOEL GENE MITCHELL | BEDFORD, IND. R.R. 3 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.

*Drawdown:* ft. *Static water level:* 90.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* NW 1/4 of the NW 1/4 of the NW 1/4 of Section 8 *Topo map:* BARTLETTSVILLE

*Field located by:* JGH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 500 *Ft S of NL:* 300

*Ground elevation:* 650.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 630.0 *Aquifier elevation:*

*UTM Easting:* 548642.0 *UTM Northing:* 4304412.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 17.0 | BOULDERS & MUD HOLES |
| 17.0 | 27.0 | GRAY LS HARD |
| 27.0 | 61.0 | BLUE LS HARD |
| 61.0 | 82.0 | GRAY LS SOFT |
| 82.0 | 85.0 | BLUE SH SOFT |
| 85.0 | 103.0 | BLUE LS SOFT |
| 103.0 | 200.0 | BLUE SH SOFT |

*Comments* MC630:

http://www.state.in.us/serv/dnr_w...orwellPrint...=217404&_from=SUMMARY&_action=...

9

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217409** | 3MI NE OF BEDFORD ON SR 58 IT AND FOR NEW HOUSE; TRAILER THERE NOW | Tue, Nov 27, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LAWRENCE RAY | R.R. #3 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 31.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.6 gpm for hrs.
*Drawdown:* ft. *Static water level:* 45.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 8 *Topo map:* BARTLETTSVILLE
*Field located by:* UHL *on:* Sat, Jun 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1500 *Ft S of NL:* 150
*Ground elevation:* 620.0 *Depth to bedrock:* 4.0 *Bedrock elevation:* 616.0 *Aquifer elevation:*
*UTM Easting:* 548953.0 *UTM Northing:* 4304465.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 32.0 | BLUE LS HARD |
| 32.0 | 32.2 | MUD HOLE |
| 32.5 | 44.0 | BLUE LS HARD |
| 44.0 | 51.0 | GRAY LS SOFT |
| 51.0 | 70.0 | BLUE LS HARD |
| 70.0 | 100.0 | BLUE SH SOFT |

*Comments* MC500

10

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217439** | NE OF BEDFORD BETWEEN THE MT. PLEASANT RD & PLEASANT RUN RD | Thu, Sep 15, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LOUIS FISH | R.R. 3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. R.R. 4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 19.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.33 gpm for 8.0 hrs.
*Drawdown:* ft. — *Static water level:* 30.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 6 — *Topo map:* BARTLETTSVILLE
*Field located by:* H,S — *on:* Fri, Nov 04, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 1800 — *Ft N of SL:* 3100 — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 735.0 — *Depth to bedrock:* 19.0 — *Bedrock elevation:* 716.0 — *Aquifer elevation:*
*UTM Easting:* 547977.0 — *UTM Northing:* 4305296.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 19.0 | CLAY |
| 19.0 | 125.0 | HARD LS |

*Comments* MC715:

# Record of Water Well

11

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217429** | APPR. 3MI E OF BEDFORD, IND. ON US HIGHWAY #58 N/SIDE OF RD | Thu, Aug 26, 1965 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | ROBERT WATSON | BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 12.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the NE 1/4 of the NE 1/4 of Section 7 *Topo map:* BARTLETTSVILLE
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 400 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 700
*Ground elevation:* 630.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 625.0 *Aquifier elevation:*
*UTM Easting:* 548374.0 *UTM Northing:* 4304308.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 7.0 | DIRT |
| 7.0 | 14.0 | LS BOULDERS |
| 14.0 | 31.0 | GRAY LS HARD |
| 31.0 | 50.0 | BR LS SOFT |
| 50.0 | 89.0 | GRAY LS HARD |
| 89.0 | 125.0 | BLUE LS HARD |
| 125.0 | 200.0 | BLUE SH SOFT |

*Comments* MC625:

12

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217424** | 3MI E OF BEDFORD ON SR 58 | Wed, Jul 17, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JERRY NEAL | 1321 5TH STREET, BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 16.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NE 1/4 of the NE 1/4 of Section 7 *Topo map:* BARTLETTSVILLE
*Field located by:* JLH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 600
*Ground elevation:* 650.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 640.0 *Aquifier elevation:*
*UTM Easting:* 548420.0 *UTM Northing:* 4304326.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | DIRT |
| 8.0 | 12.0 | LS BOULDERS HARD |
| 12.0 | 34.0 | WH LS SOFT |
| 34.0 | 78.0 | BLUE LS HARD |
| 78.0 | 83.0 | GRAY LS HARD |
| 83.0 | 107.0 | BLUE LS HARD |
| 107.0 | 200.0 | BLUE SH SOFT |

*Comments* MC640:

13

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217419** | LOCATED NEAR SR58E OF BEDFORD ABOUT 1.5MI E OF CITY LIMITS BED-BARTLITSVILLE RD | Thu, Jul 16, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HARRY E. | R.R. #3 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 155.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 11.83 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.4 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 46.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the NE 1/4 of the NE 1/4 of Section 7 — *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES — *on:* Mon, Aug 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 1100 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 1100
*Ground elevation:* 680.0 — *Depth to bedrock:* 6.0 — *Bedrock elevation:* 674.0 — *Aquifer elevation:*
*UTM Easting:* 548165.0 — *UTM Northing:* 4304180.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 8.0 | HARD SHELLIE LIME WH |
| 8.0 | 115.0 | WH LIME HARD |
| 115.0 | 137.0 | BLUE LIME HARD |
| 137.0 | 155.0 | BLUE SH SOFT |

***Comments*** MC675; LOC ACCEPTED W/O VERIF.:NO;

16

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220872** | 3 MI NE OF BEDFORD IN, ON RR4. | Thu, Dec 10, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DONALD FISH | BEDFORD RR4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IN, RR4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 70.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 14.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the NE 1/4 of the SE 1/4 of Section 1 *Topo map:* BARTLETTSVILLE
*Field located by:* BRUNS *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 600 *Ft N of SL:* 1950 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 700.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 546567.0 *UTM Northing:* 4305114.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 14.0 | 14' CLAY |
| 14.0 | 70.0 | 56' LS |

***Comments*** MC 690;

17

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217905** | W OF BEDFORD 1 MI. 1.25 MI S ON WILLIAMS RD, E SIDE. | Sat, Sep 25, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GORDEN LEE HAMILTON | BEDFORD RR | |
| Building Contractor | | | |
| Drilling Contractor | ROY E ALFORD | MITCHELL RR1 | |
| Equipment Operator | ROY E ALFORD | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 39.5 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for hrs. — *Drawdown:* ft. — *Static water level:* 70.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W

*Section:* NW 1/4 of the SW 1/4 of the NE 1/4 of Section 21 — *Topo map:* BEDFORD WEST

*Field located by:* JCH — *on:* Mon, Aug 01, 1966

*Courthouse location by:* — *on:*

*Location accepted w/o verification by:* — *on:*

*Subdivision name:* — *Lot number:*

*Ft W of EL:* 2500 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 1900

*Ground elevation:* 650.0 — *Depth to bedrock:* 39.0 — *Bedrock elevation:* 611.0 — *Aquifer elevation:*

*UTM Easting:* 541146.0 — *UTM Northing:* 4300669.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 39.0 | SOIL & CLAY FEW BOULDERS |
| 39.0 | 100.0 | GREY LIME |
| 100.0 | 150.0 | WH LIME |

***Comments*** MC 610;

18

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217900** | FROM BEDFORD GOING W ON 16TH ST TURN LEFT ON 450. GO APPROX. .5 MI TURN ELFT AT 2ND CURVE | Mon, Dec 09, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GENE BEX | | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 170.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 48.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 5.0 gpm for 2.0 hrs.
*Drawdown:* ft. — *Static water level:* 95.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 21 — *Topo map:* BEDFORD WEST
*Field located by:* JVH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 2500 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 2100
*Ground elevation:* 660.0 — *Depth to bedrock:* 25.0 — *Bedrock elevation:* 635.0 — *Aquifier elevation:*
*UTM Easting:* 541182.0 — *UTM Northing:* 4300566.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | RED CLAY |
| 20.0 | 25.0 | BROWN CLAY |
| 25.0 | 27.0 | SHELL |
| 27.0 | 29.0 | HARD LIME |
| 29.0 | 30.0 | BLANK |
| 30.0 | 40.0 | LIME |
| 40.0 | 41.0 | BROKEN |
| 41.0 | 60.0 | HARD LIME |
| 60.0 | 125.0 | MED LIME WHITE |
| 125.0 | 130.0 | HARD LIME |
| 130.0 | 170.0 | LS |

***Comments*** MC635

# Record of Water Well

19

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217895** | FROM BEDFORD GOING ABOUT 2 MI TURN L ON 450, GO ABOUT .5 MI TO BES LOTS. WILL BE 4TH HOUSE ON R. | Wed, May 15, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GLEN CRAIG | BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 52.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test* — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 2.0 gpm for 2.0 hrs.
*Drawdown:* ft. — *Static water level:* 125.0 ft.

*Grouting Information* — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Well Abandonment* — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Administrative*

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 21 — *Topo map:* BEDFORD WEST
*Field located by:* PW — *on:* Tue, Aug 17, 1971
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 1800 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 2150
*Ground elevation:* 670.0 — *Depth to bedrock:* 22.0 — *Bedrock elevation:* 648.0 — *Aquifer elevation:*
*UTM Easting:* 541371.0 — *UTM Northing:* 4300572.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 22.0 | BR CLAY |
| 22.0 | 30.0 | SHELL |
| 30.0 | 47.0 | HARD LIME |
| 47.0 | 52.0 | SOFT |
| 52.0 | 85.0 | HARD LIME |
| 85.0 | 165.0 | MD LIME |
| 165.0 | 175.0 | HARD LIME |

*Comments* MC 650; VERIFIED BY OWNER;

# Record of Water Well

20

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217885** | FROM BEDFORD GOING WEST ON 16TH TURN LEFT ON 450 GO APPROX. .25 MI 1ST RD LEFT (BEX EDITION) | Fri, Jun 19, 1970 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WARREN WILMAN | R1 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 135.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 42.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 15.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 95.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the NE 1/4 of Section 21 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Tue, Aug 17, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1650
*Ground elevation:* 630.0 *Depth to bedrock:* 16.0 *Bedrock elevation:* 614.0 *Aquifer elevation:*
*UTM Easting:* 541274.0 *UTM Northing:* 4300718.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 16.0 | CLAY |
| 16.0 | 38.0 | BROKEN LIME |
| 38.0 | 75.0 | LIME |
| 75.0 | 81.0 | HARD LIME |
| 81.0 | 135.0 | MED LIME |

*Comments* MC615; VERIFIED BY OWNER

# Record of Water Well

21

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217880** | FROM BEDFORD GOING W TURN LEFT ON 450 GO APPRX. .5 MI STONE HOUSE ON LEFT; THOMAS CHESTNUT PLACE | Sun, Dec 15, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | THOMAS CHESTNUT | R1 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 179.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 60.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.5 gpm for 2.0 hrs.
*Drawdown:* ft. — *Static water level:* 139.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 21 — *Topo map:* BEDFORD WEST
*Field located by:* PW — *on:* Tue, Aug 17, 1971
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 2450 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 2500
*Ground elevation:* 665.0 — *Depth to bedrock:* 50.0 — *Bedrock elevation:* 615.0 — *Aquifer elevation:*
*UTM Easting:* 541182.0 — *UTM Northing:* 4300462.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 50.0 | CLAY |
| 50.0 | 60.0 | SOFT LIME |
| 60.0 | 140.0 | LIME |
| 140.0 | 155.0 | MED LIME |
| 155.0 | 179.0 | HARD LIME |

***Comments*** MC615; VERIFIED BY OWNER

# Record of Water Well

22

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217910** | FROM BEDFORD GOING W TURN L ON SR450 GO ABOUT .5 MI TURN L AT BIXE'S HOMESITES. 1ST HOUSE ON L. | Fri, Nov 17, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROY BAKER | R1, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 145.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 45.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 8.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the NE 1/4 of Section 21 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Mon, Aug 16, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1850
*Ground elevation:* 660.0 *Depth to bedrock:* 30.0 *Bedrock elevation:* 630.0 *Aquifer elevation:*
*UTM Easting:* 541298.0 *UTM Northing:* 4300663.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | CLAY |
| 30.0 | 34.0 | BR |
| 34.0 | 38.0 | LIME |
| 38.0 | 45.0 | BROKEN |
| 45.0 | 145.0 | LIME |

***Comments*** MC 630. VERIFIED BY OWNER;

# Record of Water Well

23

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217875** | FROM BEDFORD GOING W TURN L ON 450 TO 1ST HOUSE ON L. DONALD T. RES. | Mon, Nov 06, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WAYNE TIREY | R#1, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 32.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 100.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 21 *Topo map:* BEDFORD WEST
*Field located by:* U *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2000 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1200
*Ground elevation:* 660.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 541310.0 *UTM Northing:* 4300864.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 26.0 | CLAY |
| 26.0 | 28.0 | LIME |
| 28.0 | 31.0 | CLAY |
| 31.0 | 50.0 | LS |
| 51.0 | 65.0 | WH LIME |
| 65.0 | 66.0 | BROKEN |
| 66.0 | 150.0 | WH LIME |

***Comments***

24

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220877** | 3 MI NE OF BEDFORD IN, ON MT PLEASANT RD. | Tue, Dec 22, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ELMER FISH | BEDFORD IN RR4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IN, RR4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 86.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 11.0 | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the SE 1/4 of Section 1 *Topo map:* BARTLETTSVILLE
*Field located by:* BRUNS *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2500 *Ft N of SL:* 2400 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 625.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 545970.0 *UTM Northing:* 4305216.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 11.0 | CLAY |
| 11.0 | 86.0 | LS |

*Comments* MI 615;

# Record of Water Well

28

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220841** | ON SR 58, 1 MI E OF BEDFORD, R3. | Mon, Oct 05, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MRS. JOSEPH A. MEYERS | BEDFORD RR3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IN RR4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 144.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 40.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.06 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 60.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SE 1/4 of Section 12 *Topo map:* BARTLETTSVILLE
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1700 *Ft N of SL:* 800 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 720.0 *Depth to bedrock:* 40.0 *Bedrock elevation:* 680.0 *Aquifer elevation:*
*UTM Easting:* 546244.0 *UTM Northing:* 4303186.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 40.0 | ROCK & CLAY |
| 40.0 | 144.0 | LS |

*Comments* MC 680;

29

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220959** | SR 50E OF BEDFORD IN, .25 MI. | Mon, Dec 28, 1959 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | TRI-ANGLE CONSTR CO INC. | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* INDUSTRY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 250.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.92 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SE 1/4 of the SE 1/4 of Section 13 *Topo map:* BEDFORD EAST
*Field located by:* BAINES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1150 *Ft N of SL:* 100 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 560.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 546396.0 *UTM Northing:* 4301330.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 2.0 | CLAY DIRT |
| 2.0 | 35.0 | WH LIME SOFT |
| 35.0 | 55.0 | BLUE LIME HARD |
| 55.0 | 70.0 | WH LIME HARD |
| 70.0 | 115.0 | BLUE LIME HARD |
| 115.0 | 142.0 | GRAY LIME HARD |
| 142.0 | 250.0 | BLUE SHALE |

*Comments* MC 560:

# Record of Water Well

30

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220847** | E. OF OALITE, IN. LOT #68 WALNUT HEIGHTS ADDITION; | Mon, Sep 23, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROSCOE ELKINS | RRT. #8, BLOOMINGTON, IN. | |
| Building Contractor | | | |
| Drilling Contractor | GEORGE SNOPP | RRT. #4, BLOOMINGTON, IN. | |
| Equipment Operator | GEORGE SNOPP | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 55.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 14.0 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 0.2 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 23.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1W
***Section:*** SW 1/4 of the NW 1/4 of the SW 1/4 of Section 2 ***Topo map:*** BARTLETTSVILLE
***Field located by:*** JCH ***on:*** Mon, Aug 01, 1966
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** 1700 ***Ft E of WL:*** 650 ***Ft S of NL:***
***Ground elevation:*** 655.0 ***Depth to bedrock:*** 15.0 ***Bedrock elevation:*** 640.0 ***Aquifier elevation:***
***UTM Easting:*** 543648.0 ***UTM Northing:*** 4305014.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 14.0 | DIRT |
| 14.0 | 55.0 | WHITE HARD LS |

***Comments*** MC 640; WELL PUMPED DRY DURING TEST;

# Record of Water Well

31

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223305** | 4 MI N OF BEDFORD ON MT PLEASANT RD | Mon, Oct 26, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES GRAVES | RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD P. STULTZ | BEDFORD IND. RR 4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 115.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 8.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.3 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 40.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 36 — *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES — *on:* Mon, Aug 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* NO — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 1700 — *Ft N of SL:* 2700 — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 730.0 — *Depth to bedrock:* — *Bedrock elevation:* 615.0 — *Aquifer elevation:*
*UTM Easting:* 546188.0 — *UTM Northing:* 4306949.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.5 | CLAY |
| 8.5 | 73.5 | SOFT LS |
| 73.5 | 115.5 | HARD LS |

***Comments*** MC725

# Record of Water Well

32

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223310** | PEERLESS RD 5 MIN. N OF BEDFORD RR 4 | Fri, Oct 23, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HAROLD SMITH | BEDFORD RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD RR 4 IND. | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 225.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 16.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* gpm for hrs.
*Drawdown:* ft. — *Static water level:* 75.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 35 — *Topo map:* BARTLETTSVILLE
*Field located by:* JRD — *on:* Tue, Aug 08, 1978
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 2000 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 1000
*Ground elevation:* 600.0 — *Depth to bedrock:* 16.0 — *Bedrock elevation:* 584.0 — *Aquifer elevation:*
*UTM Easting:* 544524.0 — *UTM Northing:* 4307384.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 16.0 | CLAY |
| 16.0 | 90.0 | LS |
| 90.0 | 225.0 | SOAPSTONE |

***Comments*** MC584: WIFE OF WELL-DRILLER VERIFIED/IN THE JUNK-YARD BY BUILDING

33

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217307** | 5 MI N OF BEDFORD ON PEERLESS RD | Fri, Oct 16, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WM. MCKEE ANDERSON | BEDFORD IND. RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4 BOX 72 BEDFORD INDIANA | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 162.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 11.0 | *Material:* | *Diameter:* 6.5 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the SE 1/4 of the SW 1/4 of Section 26 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Thu, Sep 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* NO *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 50 *Ft E of WL:* 1900 *Ft S of NL:*
*Ground elevation:* 680.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 544086.0 *UTM Northing:* 4307713.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 11.0 | CLAY |
| 11.0 | 130.0 | HARD LS |
| 130.0 | 166.0 | SOAPSTONE |

***Comments*** MC670

# Record of Water Well

34

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217312** | 5 MI N OF BEDFORD ON MT PLEASANT RD | Fri, Nov 02, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHN STULTZ | BEDFORD RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4 BOX 72 BEDFORD INDIANA | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.01 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 90.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the SE 1/4 of the SE 1/4 of Section 26 *Topo map:* BARTLETTSVILLE
*Field located by:* WHL *on:* Sat, Jun 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1300 *Ft E of WL:* 1200 *Ft S of NL:*
*Ground elevation:* 680.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 544732.0 *UTM Northing:* 4308097.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | CLAY |
| 18.0 | 150.0 | HARD LS |

*Comments* MC665

35

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217347** | ON PEERLESS RD ASK OF JUDAH STORE | Sat, Jul 25, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HORACE MEADOWS | R #4 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | R #4 BEDFORD IND. | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 115.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 33.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for 4.0 hrs.
*Drawdown:* ft. *Static water level:* 60.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the NE 1/4 of Section 27 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2700 *Ft S of NL:* 200
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 542707.0 *UTM Northing:* 4309231.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 33.0 | CLAY |
| 33.0 | 115.0 | LS |

*Comments* MC61Page 9563

# Record of Water Well

36

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217352** | PEERLESS | Mon, Jun 08, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOE HIGNITE | BEDFORD RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. RR 4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 240.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.0 | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for 8.0 hrs. *BailTest rate:* 0.05 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 80.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the NW 1/4 of the SE 1/4 of Section 27 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1400 *Ft E of WL:* 3600 *Ft S of NL:*
*Ground elevation:* 535.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 543008.0 *UTM Northing:* 4308134.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | CONFLICTING DATA |
| 0.0 | 23.0 | CLAY |
| 23.0 | 45.0 | LS |
| 45.0 | 20.0 | SOAPSTONE |

*Comments*

37

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217357** | PEERLESS IND. APP. 3 MI N OF BEDFORD IND. | Wed, Aug 12, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES CLEMENTS | BEDFORD IND. RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. RR 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 75.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the SE 1/4 of Section 27 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2000 *Ft E of WL:* 3250 *Ft S of NL:*
*Ground elevation:* 520.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 542892.0 *UTM Northing:* 4308323.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | HOLE NO. 2 |
| 0.0 | 19.0 | DIRT |
| 19.0 | 22.0 | GRAY LS HARD |
| 22.0 | 75.0 | BLUE SH SOFT |

***Comments*** MC505; BOTH HOLES WERE DRY

# Record of Water Well

38

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **5996** | 1 MI SE OF BEDFORD CITY LIMITS ON I STREET | Fri, Mar 27, 1992 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LEWIS DITTON | R R 15 BOX 10 BEDFORD IN 47421 | 2194834875 |
| Building Contractor | | | |
| Drilling Contractor | REYNOLDS INC | P O BOX 186 HWY 37 S ORLEANS IN 47452 | 8128653232 |
| Equipment Operator | PAUL SHELTON | License: 751 | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* ROTARY | *Pump type:* SUBMERSIBLE |
| | *Depth:* 345.0 | *Pump setting depth:* 340.0 | *Water quality:* CLEAR |
| Casing | *Length:* 21.0 | *Material:* S | *Diameter:* 6.6 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* AIR *Test rate:* 2.0 gpm for 1.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* 345.0 ft. *Static water level:* 100.0 ft.

***Grouting Information*** *Material:* CEMENT *Depth:* from 0.0 to 20.0
*Installation Method:* TREMIE *Number of bags used:* 1.0

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* 1/4 of the 1/4 of the NW 1/4 of Section 25 *Topo map:* BEDFORD EAST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 15.0 | CLAY |
| 15.0 | 75.0 | LIMESTONE |
| 75.0 | 155.0 | WATER FORMATION (LIME) |
| 155.0 | 345.0 | LIMESTON |

***Comments***

39

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217845** | SE FROM BEDFORD CITY LIMITS 2 MI ON I ST, TURN LEFT AT 1ST CROSSRDS., .75 MI ON LEFT; WELL IS BURIED 50' NW OF NW CORNER OF HOUSE (5' N OF DRIVEWAY) | Fri, Feb 21, 1986 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CALVIN (LUKE) LAWSON | 2517 I ST., BEDFORD, IN 47421 | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS, INC. | PO BOX 230, 816 W. MAIN PAOLI, IN 47454 | |
| Equipment Operator | PAUL SHELTON | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 223.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.0 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 6.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 75.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the SE 1/4 of Section 25 *Topo map:* BEDFORD EAST
*Field located by:* OH *on:* Tue, May 23, 1989
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 600 *Ft N of SL:* 2500 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 690.0 *Depth to bedrock:* 17.0 *Bedrock elevation:* 673.0 *Aquifier elevation:*
*UTM Easting:* 546570.0 *UTM Northing:* 4298895.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 17.0 | CLAY |
| 17.0 | 140.0 | LS |
| 140.0 | 200.0 | WATER FORMATION |
| 200.0 | 210.0 | LS |
| 210.0 | 223.0 | DARK SHALE |

***Comments***

MC673; VERIFIED BY NEIGHBOR

40

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217850** | CORNER STORE ON WASHINGTON AVE IN TOWN OF BEDFORD IN. | Thu, Sep 05, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LENAD CORNER | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13, BEDFORD IN | |
| Equipment Operator | CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 170.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 37.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.81 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 69.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the SW 1/4 of Section 23 *Topo map:* BEDFORD EAST
*Field located by:* PW *on:* Mon, Aug 16, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2050 *Ft E of WL:* 50 *Ft S of NL:*
*Ground elevation:* 680.0 *Depth to bedrock:* 34.0 *Bedrock elevation:* 646.0 *Aquifier elevation:*
*UTM Easting:* 543580.0 *UTM Northing:* 4300298.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 34.0 | DIRT |
| 34.0 | 55.0 | BLUE LS HARD |
| 55.0 | 70.0 | BRAY LS HARD |
| 70.0 | 75.0 | BR LS SOFT |
| 75.0 | 95.0 | WH LS HARD |
| 95.0 | 130.0 | WH LS SOFT |
| 130.0 | 145.0 | BLUE LS HARD |
| 145.0 | 170.0 | WH LS HARD |

***Comments*** MC 645. VERIFIED BY MANAGER:

# Record of Water Well

41

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217860** | FROM BEDFORD TURN LEFT ON 450. APROX. .5 MI TURN LEFT BEX ADDITION | Sat, Jul 27, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LAUELLA | R1 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** | ***Drilling method:*** | ***Pump type:*** |
| | ***Depth:*** 160.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 42.0 | ***Material:*** | ***Diameter:*** 6.25 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 5.0 gpm for 3.0 hrs.
***Drawdown:*** ft. ***Static water level:*** 110.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1W
***Section:*** NE 1/4 of the SE 1/4 of the NE 1/4 of Section 21 ***Topo map:*** BEDFORD WEST
***Field located by:*** PW ***on:*** Tue, Aug 17, 1971
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** 1750 ***Ft N of SL:*** ***Ft E of WL:*** ***Ft S of NL:*** 1600
***Ground elevation:*** 670.0 ***Depth to bedrock:*** 37.0 ***Bedrock elevation:*** 633.0 ***Aquifer elevation:***
***UTM Easting:*** 541457.0 ***UTM Northing:*** 4300748.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 37.0 | CLAY |
| 37.0 | 45.0 | SOFT LIME |
| 45.0 | 46.0 | LIME |
| 46.0 | 52.0 | MED LIME |
| 52.0 | 62.0 | LIME |
| 62.0 | 66.0 | BROWN SHELL |
| 66.0 | 75.0 | LIME |
| 75.0 | 80.0 | KNOB STONE |
| 80.0 | 150.0 | LIME |
| 150.0 | 160.0 | BLUE |

***Comments*** NP 635; VERIFIED BY OWNER

42

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217865** | 1.5 MI SW OF BEDFORD ON SR 158, WILLIAMS RD. | Thu, Sep 29, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RAS W. COX | BEDFORD IN, RR1 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR#6, BOX 13, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 198.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 61.6 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 148.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 21 — *Topo map:* BEDFORD WEST
*Field located by:* HS — *on:* Thu, Oct 02, 1969
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 1400 — *Ft E of WL:* 1500 — *Ft S of NL:*
*Ground elevation:* 605.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifer elevation:*
*UTM Easting:* 540810.0 — *UTM Northing:* 4300047.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | DIRT |
| 30.0 | 58.0 | BLUE LS & MUD HOLES |
| 58.0 | 80.0 | BLUE LS HARD |
| 80.0 | 144.0 | BR LS SOFT |
| 144.0 | 160.0 | BLUE LS HARD |
| 160.0 | 173.0 | GREY LS SOFT |
| 173.0 | 198.0 | BLUE LS HARD |

*Comments* CHEM TEST: FE, 0.3 PPM, HARDNESS 440 PPM, PH 7.5, CHLORIDE 10 PPM;

# Record of Water Well

43

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217870** | APPROX 500' N FROM WILLIAMS RD & 200' E OF W PROPERTY LINE. | Mon, Jul 28, 1958 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | LOREN E. HENDERSON | 233 N M RD, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR#6, BOX 13, BEDFORD IN | |
| Equipment Operator | BUAYRUS ERIE | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 151.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 35.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 96.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the SW 1/4 of Section 21 *Topo map:* BEDFORD WEST
*Field located by:* BAINES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 900 *Ft E of WL:* 400 *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 540475.0 *UTM Northing:* 4299889.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | DIRT & FLINT ROCK |
| 30.0 | 80.0 | WH HARD LIME |
| 80.0 | 90.0 | GRAY OR BUFF LIME |
| 90.0 | 151.0 | WH HARD LIME |

*Comments* MC:

# Record of Water Well

44

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217915** | FROM BEDFORD GOING WEST ON 16TH TURN ON E450 GO APPROX 1 MI TO BLOCK BASEMENT ON RD SIDE OF ROAD | Fri, Jan 10, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DWIGHT PROW | R1 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 42.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 115.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 21 *Topo map:* BEDFORD WEST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 35.0 | CLAY |
| 35.0 | 41.0 | WHITE LIME |
| 41.0 | 44.0 | SHELL |
| 44.0 | 120.0 | LIME |
| 120.0 | 123.0 | BLANK |
| 123.0 | 125.0 | SOFT SHELL |
| 125.0 | 175.0 | HARD LIME |

*Comments*

45

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217949** | RIVER BLUFF ADDT ABOUT 2 MI SW OF BEDFORD IN ON RIVER BLUFF RD. | Sat, Aug 01, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT D. BRUCE | RR1, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13, BEDFORD IN | |
| Equipment Operator | BUAYRUS ERIE | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 105.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the SW 1/4 of Section 27 *Topo map:* BEDFORD WEST
*Field located by:* HS *on:* Fri, Nov 04, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 150 *Ft E of WL:* 700 *Ft S of NL:*
*Ground elevation:* 580.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 542206.0 *UTM Northing:* 4298072.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 145.0 | BLANK |
| 145.0 | 175.0 | BLUE SHALE |

***Comments*** MC; SULPHER WATER;

46

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217954** | S OUT OF BEDFORD ON WASHINGTON AVE TO RIVER BLUFFS RD. W APP .25 MI, S SIDE OF RIVER BLUFF RD. | Wed, Apr 06, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LARRY EVANS BLDR | | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13, BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 190.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SE 1/4 of the SW 1/4 of Section 27 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Tue, Aug 17, 1971
*Courthouse location by:* JCH *on:* Mon, Aug 01, 1966
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 900 *Ft E of WL:* 2400 *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* 14.0 *Bedrock elevation:* 616.0 *Aquifier elevation:*
*UTM Easting:* 542712.0 *UTM Northing:* 4298304.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 14.0 | BOULDERS & HOLES |
| 14.0 | 32.0 | BLUE LS HARD |
| 32.0 | 40.0 | BLUE LS SOFT |
| 40.0 | 56.0 | GRAY LS SOFT |
| 56.0 | 62.0 | WH LS SOFT |
| 62.0 | 98.0 | GRAY LS SOFT |
| 98.0 | 115.0 | WH LS HARD |
| 115.0 | 137.0 | BLUE LS HARD |
| 137.0 | 154.0 | GRAY LS HARD |
| 154.0 | 165.0 | BLUE LS HARD |
| 165.0 | 171.0 | WH LS HARD |
| 171.0 | 184.0 | BLUE SHALE SOFT |

| | | |
|---|---|---|
| 184.0 | 190.0 | WH LS HARD |

*Comments* MC 615; VERIFIED BY BUILDER;

47

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217959** | 3 MI SE OF BEDFORD, 300' N OF POOR FARM RD, 6' E OF BARN | Wed, Oct 30, 1963 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | JOE WELLS | R5 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BEDFORD, IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 91.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 3.0 gpm for hrs. | *Drawdown:* ft. | *Static water level:* 61.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to | *Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to | *Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE — *Township:* 5N *Range:* 1W

*Section:* SW 1/4 of the SE 1/4 of the SE 1/4 of Section 25 — *Topo map:* BEDFORD EAST

*Field located by:* JVH — *on:* Mon, Aug 01, 1966

*Courthouse location by:* — *on:*

*Location accepted w/o verification by:* — *on:*

*Subdivision name:* — *Lot number:*

*Ft W of EL:* 1000 — *Ft N of SL:* 150 — *Ft E of WL:* — *Ft S of NL:*

*Ground elevation:* 680.0 — *Depth to bedrock:* 15.0 — *Bedrock elevation:* 665.0 — *Aquifer elevation:*

*UTM Easting:* 546459.0 — *UTM Northing:* 4298178.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 17.0 | BRKN STONE & BOULDERS LIME |
| 17.0 | 41.0 | BLUE LS HARD |
| 41.0 | 77.0 | GREY LS SOFT |
| 77.0 | 91.0 | BROWN LS SOFT |

*Comments* MC665

48

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **235518** | SR37 TO BEDFORD, IN TURN E ON 5TH STREET TO L ST. TURN S ON L ST. GO 0.5MI TO BIGFOOT STATION ON W/SIDE OF STREET | Wed, Jan 08, 1992 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHNSON OIL | PO BOX 347 COLUMBUS, IN 47202 | (812)379-9227 |
| Building Contractor | | | |
| Drilling Contractor | AMERICAN ENV | 8765 GUION RD SUITE G 46268 | (317)871-4090 |
| Equipment Operator | RON MATHES | License: 294 | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** TEST | ***Drilling method:*** OTHER | ***Pump type:*** |
| | ***Depth:*** 15.5 | ***Pump setting depth:*** | ***Water quality:*** CLOUDY |
| Casing | ***Length:*** 50.0 | ***Material:*** PVC | ***Diameter:*** 4.0 |
| Screen | ***Length:*** 10.0 | ***Material:*** PVC | ***Diameter:*** 4.0 ***Slot size:*** .010 |

***Well Capacity Test***

***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** gpm for hrs.

***Drawdown:*** ft. ***Static water level:*** ft.

***Grouting Information***

***Material:*** BENTONITE ***Depth:*** from 0.0 to 1.0

***Installation Method:*** ***Number of bags used:***

***Well Abandonment***

***Sealing material:*** ***Depth:*** from to

***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1W

***Section:*** 1/4 of the 1/4 of the 1/4 of Section 23 ***Topo map:*** BEDFORD EAST

***Field located by:*** ***on:***

***Courthouse location by:*** ***on:***

***Location accepted w/o verification by:*** ***on:***

***Subdivision name:*** ***Lot number:***

***Ft W of EL:*** ***Ft N of SL:*** ***Ft E of WL:*** ***Ft S of NL:***

***Ground elevation:*** ***Depth to bedrock:*** ***Bedrock elevation:*** ***Aquifier elevation:***

***UTM Easting:*** ***UTM Northing:***

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | CONCRETE |
| 1.0 | 6.0 | CRUSHED STONE, WET SAND |
| 6.0 | 15.5 | RED MOIST CLAY |

***Comments***

49

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **273065** | FROM WILLIAMS GOING E ON 450 .5 MI W OF CREEK BRIDGE. LANE ON RD SIDE OF RD; BACK ACRES BROCK & SONS | Fri, Apr 10, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MERTON BROCK | R1 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 125.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 14.0 | ***Material:*** | ***Diameter:*** 6.25 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 3.0 gpm for 3.0 hrs.
***Drawdown:*** ft. ***Static water level:*** 85.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1W
***Section:*** NW 1/4 of the SW 1/4 of the NW 1/4 of Section 27 ***Topo map:*** BEDFORD WEST
***Field located by:*** JVH ***on:*** Mon, Aug 01, 1966
***Courthouse location by:*** JVH ***on:*** Mon, Aug 01, 1966
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** ***Ft E of WL:*** 250 ***Ft S of NL:*** 1800
***Ground elevation:*** 650.0 ***Depth to bedrock:*** 10.0 ***Bedrock elevation:*** 640.0 ***Aquifier elevation:***
***UTM Easting:*** 542024.0 ***UTM Northing:*** 4299103.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | CLAY |
| 12.0 | 28.0 | LIME |
| 28.0 | 30.0 | BROWN LIME |
| 30.0 | 33.0 | HARD LIME |
| 33.0 | 45.0 | WHITE LIME |
| 45.0 | 50.0 | SOFT LIME |
| 50.0 | 75.0 | LIME |
| 75.0 | 92.0 | SHELL |
| 92.0 | 106.0 | LIME |
| 106.0 | 125.0 | BLUE SHELL |

***Comments*** MC640

# Record of Water Well

50

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **336969** | 1507 18TH ST, BEDFORD, IN | Thu, Jul 29, 1999 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DANIEL L. HALL | 1318 16TH ST., BEDFORD, IN 47421 | (812)279-8101 |
| Building Contractor | | | |
| Drilling Contractor | PHILLIPS WELL DRLNG & PUMP SVC | RR12 BOX 444, BEDFORD, IN 47421 | (812)279-4843 |
| Equipment Operator | LLOYD PHILLIPS | License: 208 | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* SUBMERSIBLE |
| | *Depth:* 200.0 | *Pump setting depth:* 185.0 | *Water quality:* CLEAR GOOD |
| Casing | *Length:* 36.0 | *Material:* PVC | *Diameter:* 6.0 |
| Screen | *Length:* 40.0 | *Material:* PVC | *Diameter:* 4.0 *Slot size:* 1.25 |

***Well Capacity Test***

*Type of test:* BAILING *Test rate:* 11.0 gpm for 1.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 185.0 ft.

***Grouting Information***

*Material:* BENONITE *Depth:* from 0.0 to 36.0
*Installation Method:* PUMP *Number of bags used:* 3.5

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* 1/4 of the SE 1/4 of the NE 1/4 of Section 23 *Topo map:* BEDFORD EAST

| | | | |
|---|---|---|---|
| *Field located by:* | | *on:* | |
| *Courthouse location by:* | | *on:* | |
| *Location accepted w/o verification by:* | | *on:* | |
| *Subdivision name:* | | *Lot number:* | |
| *Ft W of EL:* | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* | *Depth to bedrock:* | *Bedrock elevation:* | *Aquifier elevation:* |
| *UTM Easting:* | | *UTM Northing:* | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 2.0 | TOPSOIL |
| 2.0 | 6.0 | CLAY |
| 6.0 | 12.0 | SHALE |
| 12.0 | 139.0 | LS |
| 139.0 | 200.0 | WHITE LS |

***Comments*** SEE MAP

# Record of Water Well

51

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220949** | NW BEDFORD IN, .5 MI ON LANE KNOWN AS BILL BARK QUARY. N OF GRAVEY LANE. THE 3RD HOUSE ON L SIDE OF BILL BARK LANE. | Mon, Mar 27, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WINFRED WEVER | 503 ST, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN, R6 | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 123.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 29.25 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.05 gpm for hrs. — *Drawdown:* ft. — *Static water level:* 60.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W

*Section:* SE 1/4 of the SE 1/4 of the NE 1/4 of Section 16 — *Topo map:* BEDFORD WEST

*Field located by:* JCH — *on:* Mon, Aug 01, 1966

*Courthouse location by:* — *on:*

*Location accepted w/o verification by:* — *on:*

*Subdivision name:* — *Lot number:*

*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:*

*Ground elevation:* 610.0 — *Depth to bedrock:* 25.0 — *Bedrock elevation:* 585.0 — *Aquifier elevation:*

*UTM Easting:* 541896.0 — *UTM Northing:* 4302187.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | DIRT |
| 28.0 | 35.0 | BLUE LS HARD |
| 35.0 | 55.0 | BLUE LS SOFT |
| 55.0 | 61.0 | BR LS SOFT |
| 61.0 | 123.0 | WH LS SOFT |

***Comments*** MC 585.

53

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220926** | E OOLITIC, RR4. | Mon, May 01, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | FELIX CHENAULT JR | E OOLITIC, RR4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IN, RR4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 88.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 14.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SE 1/4 of the NW 1/4 of Section 3 *Topo map:* OOLITIC
*Field located by:* U *on:* Thu, Aug 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1700 *Ft S of NL:* 1900
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 542461.0 *UTM Northing:* 4305521.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 14.0 | CLAY |
| 14.0 | 50.0 | LS |
| 50.0 | 84.0 | SHALE |

*Comments*

54

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220936** | E OOLITIC, LOT 65. | Mon, Jun 15, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DENNY MAY | BEDFORD, RR4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IN, RR4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 85.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** | ***Material:*** | ***Diameter:*** |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** — ***Type of test:*** PUMPING; ***Test rate:*** 1.0 gpm for 8.0 hrs.; ***BailTest rate:*** gpm for hrs.; ***Drawdown:*** ft.; ***Static water level:*** 30.0 ft.

***Grouting Information*** — ***Material:***; ***Depth:*** from to; ***Installation Method:***; ***Number of bags used:***

***Well Abandonment*** — ***Sealing material:***; ***Depth:*** from to; ***Installation Method:***; ***Number of bags used:***

***Administrative***

| | | | |
|---|---|---|---|
| ***County:*** LAWRENCE | | ***Township:*** 5N ***Range:*** 1W | |
| ***Section:*** 1/4 of the 1/4 of the 1/4 of Section 3 | | | ***Topo map:*** OOLITIC |
| ***Field located by:*** | | ***on:*** | |
| ***Courthouse location by:*** | | ***on:*** | |
| ***Location accepted w/o verification by:*** | | ***on:*** | |
| ***Subdivision name:*** | | ***Lot number:*** | |
| ***Ft W of EL:*** | ***Ft N of SL:*** | ***Ft E of WL:*** | ***Ft S of NL:*** |
| ***Ground elevation:*** | ***Depth to bedrock:*** | ***Bedrock elevation:*** | ***Aquifier elevation:*** |
| ***UTM Easting:*** | | ***UTM Northing:*** | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 13.0 | CLAY |
| 13.0 | 45.0 | SANDY LS |
| 45.0 | 85.0 | SOAPSTONE |

*Comments*

# Record of Water Well

55

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220941** | E OOLTIC IN, LOT 31. | Thu, Jul 25, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LARRY RANDOLPH | BEDFORD IN, RR2 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN, RR6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 127.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 14.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 40.0 ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* 1/4 of the 1/4 of the 1/4 of Section 3 *Topo map:* OOLITIC

*Field located by:* *on:*

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

| *Ft W of EL:* | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* |
|---|---|---|---|
| *Ground elevation:* | *Depth to bedrock:* | *Bedrock elevation:* | *Aquifier elevation:* |
| *UTM Easting:* | | *UTM Northing:* | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | DIRT |
| 10.0 | 31.0 | GRAY LS SOFT |
| 31.0 | 46.0 | BLUE LS HARD |
| 46.0 | 127.0 | BLUE SHALE SOFT |

***Comments***

56

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220956** | TOWN OF EAST OOLITIC, LOT #22 | Wed, Sep 27, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | VOLLIE STAGGS | EAST OOLITIC, IN. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RRT. 6, BOX 13, BEDFORD, IN. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 101.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 6.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 71.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the NW 1/4 of Section 3 *Topo map:* OOLITIC
*Field located by:* U *on:* Mon, Jul 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 50 *Ft S of NL:* 1900
*Ground elevation:* 540.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 541955.0 *UTM Northing:* 4305516.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 25.0 | DIRT |
| 25.0 | 30.0 | BLUE LS-HARD |
| 30.0 | 36.0 | BLUE SH-SOFT |
| 36.0 | 74.0 | BLUE LS-HARD |
| 74.0 | 101.0 | BLUE SH-SOFT |

***Comments***

# Record of Water Well

52

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220921** | E OOLITIC RD. | Sat, May 07, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | IRA CHENAULT | E OOLITIC RD | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IN, RR4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 60.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 12.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.3 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NW 1/4 of Section 3 *Topo map:* OOLITIC
*Field located by:* BRINES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2600 *Ft E of WL:* 400 *Ft S of NL:*
*Ground elevation:* 520.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 542070.0 *UTM Northing:* 4305314.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | CLAY |
| 12.0 | 60.0 | LS |

***Comments***

MC 510;

57

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221531** | 5MI SE OF BEDFORD ON POOR FARM RD | Sat, Apr 06, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RUSSELL CROUCHER | CEMENT PLANT RD | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. R.R. 4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 80.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

| | | | |
|---|---|---|---|
| *Well Capacity Test* | *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 80.0 gpm for 8.0 hrs. |
| | *Drawdown:* ft. | *Static water level:* 40.0 ft. | |

| | | |
|---|---|---|
| *Grouting Information* | *Material:* | *Depth:* from to |
| | *Installation Method:* | *Number of bags used:* |

| | | |
|---|---|---|
| *Well Abandonment* | *Sealing material:* | *Depth:* from to |
| | *Installation Method:* | *Number of bags used:* |

| | | | | |
|---|---|---|---|---|
| *Administrative* | *County:* LAWRENCE | | *Township:* 5N *Range:* 1E | |
| | *Section:* SE 1/4 of the SW 1/4 of the SE 1/4 of Section 30 | | | *Topo map:* BEDFORD EAST |
| | *Field located by:* HUH | | *on:* Mon. Aug 01, 1966 | |
| | *Courthouse location by:* | | *on:* | |
| | *Location accepted w/o verification by:* | | *on:* | |
| | *Subdivision name:* | | *Lot number:* | |
| | *Ft W of EL:* 2800 | *Ft N of SL:* 500 | *Ft E of WL:* | *Ft S of NL:* |
| | *Ground elevation:* 700.0 | *Depth to bedrock:* 20.0 | *Bedrock elevation:* 680.0 | *Aquifer elevation:* |
| | *UTM Easting:* 547791.0 | | *UTM Northing:* 4298253.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | CLAY |
| 18.0 | 80.0 | HARD LS |

*Comments* MC680:

58

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221536** | APPR. 2.5MI SE OF BEDFORD IND ON POOR FARM RD | Tue, May 17, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WILLIAM C. TARR | BEDFORD IND. R.R. 5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 107.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 33.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 8.0 gpm for hrs.
*Drawdown:* ft. | *Static water level:* 30.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE | *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 30 | *Topo map:* BEDFORD EAST
*Field located by:* PW | *on:*
*Courthouse location by:* | *on:*
*Location accepted w/o verification by:* | *on:*
*Subdivision name:* | *Lot number:*
*Ft W of EL:* | *Ft N of SL:* 100 | *Ft E of WL:* 1050 | *Ft S of NL:*
*Ground elevation:* 700.0 | *Depth to bedrock:* 27.0 | *Bedrock elevation:* 673.0 | *Aquifer elevation:*
*UTM Easting:* 547073.0 | *UTM Northing:* 4298167.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 27.0 | DIRT |
| 27.0 | 65.0 | BR LS SOFT |
| 65.0 | 92.0 | GRAY LS SOFT |
| 92.0 | 107.0 | BLUE LS HARD |

*Comments*: MC675: VERIFIED BY OWNER, MC

59

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217994** | APP. 3.5MI E OF BEDFORD IND. ON S LEATHERWOOD RD. S/SIDE OF RD | Thu, Jul 11, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CLAUDE E. CADE | R.R. #6, BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 154.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 40.0 ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* NE 1/4 of the NW 1/4 of the SE 1/4 of Section 20 *Topo map:* BEDFORD EAST

*Field located by:* JCH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 1600 *Ft N of SL:* 2400 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 720.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 700.0 *Aquifer elevation:*

*UTM Easting:* 549688.0 *UTM Northing:* 4300462.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | DIRT |
| 8.0 | 22.0 | BOULDERS |
| 22.0 | 56.0 | BLUE LS HARD |
| 56.0 | 67.0 | GRAY LS HARD |
| 67.0 | 74.0 | WH LS SOFT |
| 74.0 | 97.0 | GRAY LS SOFT |
| 97.0 | 136.0 | WH LS SOFT |
| 136.0 | 154.0 | BLUE LS HARD |

***Comments*** MC700;

# Record of Water Well

60

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217999** | APPR. 2MI S, E OF BEDFORD, IND. ON S LEATHERWOOD RD | Mon, Jun 29, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT & MARIE FOX | BEDFORD, IND. R.R.6 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 38.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 7.83 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 7.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 8.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NW 1/4 of the SW 1/4 of Section 20 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2500 *Ft E of WL:* 700 *Ft S of NL:*
*Ground elevation:* 640.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 635.0 *Aquifer elevation:*
*UTM Easting:* 548770.0 *UTM Northing:* 4300465.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 2.5 | DIRT |
| 2.5 | 18.0 | BLUE LS HARD |
| 18.0 | 25.0 | GRAY LS HARD |
| 25.0 | 29.0 | BR LS SOFT |
| 29.0 | 38.0 | GRAY LS HARD |

***Comments*** MC635.

# Record of Water Well

61

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218004** | 3-1/2 MILES SOUTHEAST OF BEDFORD ON SOUTH LEATHERWOOD ROAD | Fri, Aug 28, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LOVELL & MARY PIERCE | RR 6, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BOX 13, BEDFORD IN | |
| Equipment Operator | EUGENE UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 141.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 26.92 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.6 gpm for 1.0 hrs.
*Drawdown:* 85.0 ft. *Static water level:* 56.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 20 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2000 *Ft N of SL:* 2700 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 750.0 *Depth to bedrock:* 24.0 *Bedrock elevation:* 726.0 *Aquifier elevation:*
*UTM Easting:* 549570.0 *UTM Northing:* 4300530.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

***Comments*** MC725: OWNER NOT HOME

62

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218009** | LOT 5A E OF BEDFORD, IND. BROOK KNOLL ADD. | Thu, Sep 30, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHN W. REUTER | BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R.6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 17.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 0.75 gpm for hrs. | *Drawdown:* ft. | *Static water level:* 40.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to | *Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to | *Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE — *Township:* 5N *Range:* 1E

*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 19 — *Topo map:* BEDFORD EAST

*Field located by:* JUH — *on:* Mon, Aug 01, 1966

*Courthouse location by:* — *on:*

*Location accepted w/o verification by:* — *on:*

*Subdivision name:* — *Lot number:*

*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* 1600 — *Ft S of NL:* 2600

*Ground elevation:* 580.0 — *Depth to bedrock:* 5.0 — *Bedrock elevation:* 575.0 — *Aquifer elevation:*

*UTM Easting:* 547245.0 — *UTM Northing:* 4300514.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 10.0 | GRAY LS SOFT |
| 10.0 | 42.0 | GRAY LS HARD |
| 42.0 | 70.0 | BLUE LS HARD |
| 70.0 | 89.0 | GRAY LS HARD |
| 89.0 | 150.0 | BLUE SH SOFT |

*Comments*: MC575:

# Record of Water Well

63

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218014** | APP. 1.5 E OF BEDFORD, IND. ON TUNNELTON RD | Sat, Aug 29, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | AUDRIE BEAVERS | BEDFORD, IND. R.R.5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 34.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 10.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 20.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 12.0 ft.

*Grouting Information*: *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*: *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 19 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2700 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2200
*Ground elevation:* 530.0 *Depth to bedrock:* 7.0 *Bedrock elevation:* 523.0 *Aquifier elevation:*
*UTM Easting:* 547745.0 *UTM Northing:* 4300632.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DIRT |
| 3.0 | 7.0 | BROKEN LS |
| 7.0 | 22.0 | GRAY LS HARD |
| 22.0 | 34.0 | BLUE LS HARD |

*Comments* MC575;

64

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218019** | TUNNELTON RD ABOUT 2MI E FROM CITY OF BEDFORD | Thu, Jun 04, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT HERTHEL | BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 224.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.42 gpm for hrs.
*Drawdown:* ft. *Static water level:* 84.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NW 1/4 of the SE 1/4 of Section 19 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2300 *Ft N of SL:* 2300 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 570.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 550.0 *Aquifier elevation:*
*UTM Easting:* 547885.0 *UTM Northing:* 4300403.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 7.0 | DIRT |
| 7.0 | 20.0 | BOULDERS & MUD HOLES |
| 20.0 | 54.0 | BLUE LS HARD |
| 54.0 | 57.0 | BLUE SH SOFT |
| 57.0 | 75.0 | GRAY LS HARD |
| 75.0 | 92.0 | BLUE LS HARD |
| 92.0 | 101.0 | GRAY LS HARD |
| 101.0 | 229.0 | BLUE SH SOFT |

***Comments*** MC550:

65

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218024** | APP. 1MI SE OF BEDFORD IND. ON TUNNELTON RD. LOT 35 & 35A IN BROOK KNOLL ADDATION | Fri, May 28, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HERBERT ROSS | BEDFORD, IND. R.R. 5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 177.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.15 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 75.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the NW 1/4 of Section 19 — *Topo map:* BEDFORD EAST
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 600 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 2100
*Ground elevation:* 575.0 — *Depth to bedrock:* 15.0- — *Bedrock elevation:* 560.0 — *Aquifier elevation:*
*UTM Easting:* 547012.0 — *UTM Northing:* 4300844.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 1.0 | DIRT |
| 1.0 | 15.0 | BROKEN LS |
| 15.0 | 23.0 | BLUE LS HARD |
| 23.0 | 44.0 | GRAY LS HARD |
| 44.0 | 57.0 | WH LS HARD |
| 57.0 | 86.0 | BLUE LS HARD |
| 86.0 | 104.0 | BLUE LS SOFT |
| 104.0 | 110.0 | GRAY LS HARD |
| 110.0 | 177.0 | BLUE SH SOFT |

***Comments*** MC560.

66

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217384** | SR 58 3MI E OF BEDFORD IND. | Thu, Jul 10, 1958 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RAYMOND A STIPP | BEDFORD IND. R.R. 5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | BUAYRUS ERSI | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* | *Pump type:* |
| | *Depth:* 115.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 80.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NW 1/4 of the NE 1/4 of Section 8 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 9.0 | DIRT |
| 9.0 | 20.0 | SHELLIE WH LIME |
| 20.0 | 94.0 | HARD WH LIME |
| 94.0 | 115.0 | BLUE SH |

***Comments*** LOC. ACCEPTED W/O VERIF., YES; OWNER NOT HOME.

67

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217389** | APPR. 3MI E OF BEDFORD, IND. ON US HIGHWAY 58 | Tue, Feb 26, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | OSCAR LOVEALL | 1707 P ST. BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 25.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.

*Drawdown:* ft. *Static water level:* 110.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* NE 1/4 of the NW 1/4 of the NW 1/4 of Section 8 *Topo map:* BARTLETTSVILLE

*Field located by:* N *on:* Thu, Aug 01, 1963

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 900 *Ft S of NL:* 50

*Ground elevation:* 670.0 *Depth to bedrock:* 24.0 *Bedrock elevation:* 646.0 *Aquifier elevation:*

*UTM Easting:* 548796.0 *UTM Northing:* 4304490.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 13.0 | BOULDERS |
| 13.0 | 14.0 | MUD HOLE |
| 14.0 | 23.0 | BLUE LS HARD |
| 23.0 | 24.0 | MUD LOLE |
| 24.0 | 35.0 | BLUE LS HARD |
| 35.0 | 52.0 | WH LS SOFT |
| 52.0 | 96.0 | BLUE LS HARD |
| 96.0 | 98.0 | BLUE SH SOFT |
| 98.0 | 112.0 | BLUE LS HARD |
| 112.0 | 115.0 | BLUE SH SOFT |
| 115.0 | 121.0 | BLUE LS HARD |
| 121.0 | 150.0 | BLUE SH SOFT |

*Comments* MC645;

68

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217394** | APPR. 2MI E OF BEDFORD ON US 50 N/SIDE OF HIGHWAY | Thu, May 05, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HAROLD HEWITT | BEDFORD, IND. R.R.6 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 20.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NE 1/4 of the SE 1/4 of Section 8 *Topo map:* BARTLETTSVILLE
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 100 *Ft N of SL:* 2100 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 660.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 655.0 *Aquifier elevation:*
*UTM Easting:* 550084.0 *UTM Northing:* 4303557.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 8.0 | LS BOULDERS |
| 8.0 | 45.0 | BR LS HARD |
| 45.0 | 51.0 | GRAY LS HARD |
| 51.0 | 89.0 | BLUE LS HARD |
| 89.0 | 105.0 | GRAY LS HARD |
| 105.0 | 108.0 | BLUE LS SOFT |
| 108.0 | 115.0 | BLUE LS HARD |
| 115.0 | 150.0 | BLUE SH SOFT |

*Comments* MC655:

69

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217399** | APPR. 3MI E OF BEDFORD, IND. ON US 58 | Wed, Oct 14, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RAYMOND STIPP | BEDFORD, IND. R.R. 3 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 45.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NW 1/4 of the NE 1/4 of Section 8 *Topo map:* BARTLETTSVILLE
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1300 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 300
*Ground elevation:* 640.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 635.0 *Aquifer elevation:*
*UTM Easting:* 549679.0 *UTM Northing:* 4304419.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | DIRT |
| 8.0 | 12.0 | LS BOULDERS |
| 12.0 | 53.0 | BLUE LS HARD |
| 53.0 | 79.0 | GRAY LS HARD |
| 79.0 | 150.0 | BLUE SH SOFT |

*Comments* MC635;

70

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217414** | APPR 2.5MI E OF BEDFORD ON US HY 58 S/SIDE OF RD | Thu, Apr 21, 1966 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | WARREN D. RAINEY | R.R. #3 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 7 *Topo map:* BARTLETTSVILLE
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1900 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2000
*Ground elevation:* 670.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 660.0 *Aquifier elevation:*
*UTM Easting:* 547922.0 *UTM Northing:* 4303905.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 7.0 | DIRT |
| 7.0 | 15.0 | BLUE LS HARD |
| 15.0 | 30.0 | WH LS SOFT |
| 30.0 | 51.0 | BLUE LS HARD |
| 51.0 | 66.0 | BLUE SH SOFT |
| 66.0 | 89.0 | BLUE LS HARD |
| 89.0 | 102.0 | WH LS SOFT |
| 102.0 | 125.0 | BLUE LS HARD |
| 125.0 | 150.0 | BLUE SH SOFT |

*Comments* MC660:

71

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217444** | E OF BEDFORD, IND. ON US 58 TO PLEASANT RUN RD, TURN N, APPR. 1MI . WELL ON E/SIDE OF RD | Thu, Mar 30, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DAN MATTHEWS | BEDFORD, IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 16.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 8.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 20.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the NW 1/4 of the SW 1/4 of Section 5 *Topo map:* BARTLETTSVILLE
*Field located by:* JRD *on:* Tue, Aug 08, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1900 *Ft E of WL:* 100 *Ft S of NL:*
*Ground elevation:* 690.0 *Depth to bedrock:* 9.0 *Bedrock elevation:* 681.0 *Aquifier elevation:*
*UTM Easting:* 548537.0 *UTM Northing:* 4305110.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 9.0 | DIRT |
| 9.0 | 45.0 | GRAY LS HARD |
| 45.0 | 62.0 | WH LS HARD |
| 62.0 | 70.0 | BLUE LS SOFT |
| 70.0 | 83.0 | GRAY LS HARD |
| 83.0 | 100.0 | BLUE LS HARD |

***Comments***

MC681. OWNER VERIFIED/20' SW OF HOUSE; MC;

72

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217449** | APPR. 3MI E OF BEDFORD, IND. ON US HIGHWAY 58 | Tue, Apr 20, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JEFFERSON RAGSDALE | BEDFORD, IND. R.R. 3 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 60.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the SE 1/4 of the SW 1/4 of Section 5 *Topo map:* BARTLETTSVILLE
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1100 *Ft E of WL:* 1800 *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 625.0 *Aquifier elevation:*
*UTM Easting:* 549031.0 *UTM Northing:* 4304821.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DIRT |
| 3.0 | 38.0 | BLUE LS HARD |
| 38.0 | 53.0 | GRAY LS SOFT |
| 53.0 | 200.0 | BLUE SH SOFT |

*Comments* MC625:

73

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217454** | APPR. 150' E OF BEDFORD & BARTLETTSVILLE RD IN TAVEN | Wed, May 25, 1960 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | DELBERT BAKER | 1027 O ST. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 98.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 40.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.8 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 48.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 5 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 450 *Ft E of WL:* 50 *Ft S of NL:*
*Ground elevation:* 700.0 *Depth to bedrock:* 6.0 *Bedrock elevation:* 694.0 *Aquifier elevation:*
*UTM Easting:* 548522.0 *UTM Northing:* 4304677.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 35.0 | LS BOULDERS |
| 35.0 | 70.0 | LS WH SOFT |
| 70.0 | 80.0 | LS BLUE HARD |
| 80.0 | 98.0 | LS WH HARD |

*Comments* MC695; LOC. ACCEPTED W/O VERIF., NO;

74

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217459** | ON SR 58, 3MI E OF BEDFORD | Mon, Apr 20, 1964 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | WAYNE HAMMOND | BEDFORD R.R. 3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. R.R. 4 | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 9.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for 8.0 hrs. *BailTest rate:* 0.25 gpm for hrs.

*Drawdown:* ft. *Static water level:* 70.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* SE 1/4 of the SW 1/4 of the SE 1/4 of Section 5 *Topo map:* BARTLETTSVILLE

*Field located by:* JUH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 1800 *Ft N of SL:* 100 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 670.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 660.0 *Aquifer elevation:*

*UTM Easting:* 549533.0 *UTM Northing:* 4304538.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 9.0 | CLAY |
| 9.0 | 95.0 | LS |
| 95.0 | 200.0 | SOAPSTONE |

*Comments* MC660;

75

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217464** | ON BEDFORD & BARTLETTSVILLE RD ABOUT 3MI E OF BEDFORD IND. .5MI N OF SR 58 | Mon, Jul 20, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | PAT MURPHEY | R.R. 5 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 80.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.92 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.16 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 21.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NW 1/4 of the SW 1/4 of Section 5 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1950 *Ft E of WL:* 300 *Ft S of NL:*
*Ground elevation:* 680.0 *Depth to bedrock:* 26.0 *Bedrock elevation:* 654.0 *Aquifer elevation:*
*UTM Easting:* 548576.0 *UTM Northing:* 4305120.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 26.0 | DIRT |
| 26.0 | 60.0 | WH LIME HARD |
| 60.0 | 80.0 | BLUE LIME HARD |

*Comments* MC655; LOC. ACCEPTED W/O VERIF., NO;

76

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217469** | A PART OF THE SW QUARTER OF SECTION 5, TOWNSHIP 5N RANGE 1E ON BARTLETTSVILLE RD | Thu, Oct 24, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES D. DECKARD | 816 P. ST. BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 24.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.33 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 60.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 5 — *Topo map:* BARTLETTSVILLE
*Field located by:* JUH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 600 — *Ft E of WL:* 100 — *Ft S of NL:*
*Ground elevation:* 710.0 — *Depth to bedrock:* 5.0 — *Bedrock elevation:* 705.0 — *Aquifer elevation:*
*UTM Easting:* 548533.0 — *UTM Northing:* 4304733.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 17.0 | BROKEN LS |
| 17.0 | 30.0 | GRAY LS SOFT |
| 30.0 | 55.0 | WH LS SOFT |
| 55.0 | 97.0 | BLUE LS HARD |
| 97.0 | 125.0 | GRAY LS HARD |
| 125.0 | 134.0 | BLUE LS HARD |
| 134.0 | 140.0 | BLUE SH SOFT |
| 140.0 | 158.0 | BLUE LS HARD |
| 158.0 | 200 | BLUE SH SOFT |

***Comments*** MC705.

77

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217474** | 3MI N E OF BEDFORD IND ON BEDFORD & BARTHERSVILLE RD | Thu, Jul 16, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RICHARD ALLEN | 67E. 17TH ST. BEDFORD, IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | BUAYRNS ERE | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 69.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 14.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 48.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 5 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 400 *Ft E of WL:* 50 *Ft S of NL:*
*Ground elevation:* 690.0 *Depth to bedrock:* 4.0 *Bedrock elevation:* 686.0 *Aquifer elevation:*
*UTM Easting:* 548538.0 *UTM Northing:* 4304645.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 10.0 | SHELLIE LIME |
| 10.0 | 69.0 | WH LIME ,NOT TO HARD |

***Comments***

MC685. LOC. ACETED W/O VERIF., NO;

# Record of Water Well

78

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217676** | 4 MILES NE OF BEDFORD IN - 1 MI E OF MT. PLEASANT CHRISTIAN CHURCH NW CORNER OF SEC. 31, TWP. 6 | Tue, Dec 01, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | VIRN STULTZ | RR 4, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BEDFORD IN | |
| Equipment Operator | E. & C. UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.3 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 90.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1E
*Section:* NW 1/4 of the SE 1/4 of the SW 1/4 of Section 31 — *Topo map:* BARTLETTSVILLE
*Field located by:* JVH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 700 — *Ft E of WL:* 2200 — *Ft S of NL:*
*Ground elevation:* 630.0 — *Depth to bedrock:* 5.0 — *Bedrock elevation:* 625.0 — *Aquifer elevation:*
*UTM Easting:* 547401.0 — *UTM Northing:* 4306326.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 23.0 | BLUE LIMESTONE BOULDERS MUDHOL |
| 23.0 | 56.0 | BLUE LIMESTONE HARD |
| 56.0 | 81.0 | GRAY LIMESTONE HARD |
| 81.0 | 200.0 | BLUE SHALE SOFT |

*Comments* MC625

79

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217681** | SIX MILES NE OF BEDFORD | Mon, Oct 05, 1959 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | PAUL FISH | RR 4 BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4, BEDFORD IN | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 7.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* SW 1/4 of the NW 1/4 of the SW 1/4 of Section 31 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1600 *Ft E of WL:* 300 *Ft S of NL:*
*Ground elevation:* 680.0 *Depth to bedrock:* 7.0 *Bedrock elevation:* 673.0 *Aquifier elevation:*
*UTM Easting:* 546658.0 *UTM Northing:* 4306524.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 7.0 | CLAY |
| 7.0 | 11.0 | SANDSTONE |
| 11.0 | 31.0 | SOAPSTONE |
| 31.0 | 90.0 | HARD LIMESTONE |
| 90.0 | 125.0 | SOAPSTONE |

*Comments* MC675

# Record of Water Well

80

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217686** | ABOUT 6 MILES NE OF BEDFORD AND ABOUT 1-1/2 MI NW OF PLEASANT RUN CHURCH WHICH IS ON BEDFORD & BARTLETTSVILLE ROAD | Tue, Aug 11, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | EARL BARTLET | RR 4, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BEDFORD IN | |
| Equipment Operator | B. ERIE | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 280.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 11.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.13 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 145.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* SE 1/4 of the NW 1/4 of the NW 1/4 of Section 30 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1500 *Ft S of NL:* 1100
*Ground elevation:* 750.0 *Depth to bedrock:* 9.0 *Bedrock elevation:* 741.0 *Aquifier elevation:*
*UTM Easting:* 547183.0 *UTM Northing:* 4308956.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 9.0 | DIRT |
| 9.0 | 80.0 | LIME SOFT |
| 30.0 | 35.0 | BLUE SHALE |
| 35.0 | 80.0 | WHITE LIME |
| 80.0 | 85.0 | BLUE SHALE |
| 85.0 | 132.0 | BLUE SHALE HARD |
| 132.0 | 280.0 | BLUE SHALE |

***Comments*** MC745

# Record of Water Well

81

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217691** | DRILLED AT BIG BARN FARM CORNERING AT BARTLETTSVILLE AND PLEASANT RUN ROADS, 7 MILES NE OF BEDFORD | Mon, Jul 22, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CLAUDE HARRELL | RR 3, BOX 154, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BEDFORD IN | |
| Equipment Operator | E. & C. UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 142.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.

*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E

*Section:* NW 1/4 of the SE 1/4 of the SE 1/4 of Section 30 *Topo map:* BARTLETTSVILLE

*Field located by:* *on:*

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 1000 *Ft N of SL:* 1050 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 680.0 *Depth to bedrock:* 13.0 *Bedrock elevation:* 667.0 *Aquifier elevation:*

*UTM Easting:* 548073.0 *UTM Northing:* 4308029.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 13.0 | DIRT |
| 13.0 | 31.0 | BLUE LIMESTONE HARD |
| 31.0 | 46.0 | GRAY LIMESTONE SOFT |
| 46.0 | 61.0 | BLUE LIMESTONE HARD |
| 61.0 | 73.0 | GRAY LIMESTONE HARD |
| 73.0 | 131.0 | BLUE LIMESTONE HARD |
| 131.0 | 142.0 | BLUE SHALE SOFT |

***Comments***

MC 630 DRY HOLE

# Record of Water Well

82

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217696** | NORTH EAST OF BEDFORD IND ON MOUNT PLEASANT ROAD | Fri, Sep 23, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LAWRENCE HARRELL | | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. RR6 BOX 13 | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 250.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 16.25 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 125.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SE 1/4 of Section 30 *Topo map:* BARTLETTSVILLE
*Field located by:* S&H *on:* Fri, Nov 04, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 400 *Ft E of WL:* 2700 *Ft S of NL:*
*Ground elevation:* 720.0 *Depth to bedrock:* 6.0 *Bedrock elevation:* 714.0 *Aquifier elevation:*
*UTM Easting:* 547565.0 *UTM Northing:* 4307844.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 36.0 | WHITE LS HARD |
| 36.0 | 48.0 | BLUE LS SOFT |
| 48.0 | 54.0 | WHITE LS HARD |
| 54.0 | 102.0 | BLUE LS HARD |
| 102.0 | 108.0 | WHITE LS SOFT |
| 108.0 | 121.0 | BLUE LS HARD |
| 121.0 | 250.0 | BLUE SHALE SOFT |

***Comments*** MC715:CHEMICAL ANALYSIS

# Record of Water Well

83

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219663** | | Sat, Feb 13, 1954 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | STEPHEN BUCK | AT CEMETERY TARRY PARK | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR #2 MITCHELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 16.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.35 gpm for 0.5 hrs.
*Drawdown:* ft. *Static water level:* ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* 1/4 of the 1/4 of the 1/4 of Section 3 *Topo map:* BEDFORD WEST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 16.0 | OVRBRDN CLAY BLDRS BRKN LS |
| 16.0 | 100.0 | LS |

*Comments* APPROX LOC: WELL HAS RESERVE CAP 80 GAL.

84

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219668** | APPROX. 3MI S BEDFORD ON OLD RD 37 ACROSS FROM CRESTHAVEN CEMETRY | Mon, May 11, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | APPLACRES, INC. | R. #1 BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R,. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 258.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 35.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.75 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 3 *Topo map:* BEDFORD WEST
*Field located by:* DW *on:* Tue, Aug 17, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1550 *Ft S of NL:* 1800
*Ground elevation:* 610.0 *Depth to bedrock:* 29.0 *Bedrock elevation:* 581.0 *Aquifier elevation:*
*UTM Easting:* 542436.0 *UTM Northing:* 4295420.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 7.0 | DIRT |
| 7.0 | 29.0 | BOULDERS & MUD HOLE |
| 24.0 | 38.0 | WH LS HARD |
| 38.0 | 60.0 | BR LS SOFT |
| 60.0 | 94.0 | WH LS HARD |
| 94.0 | 103.0 | GRAY LS HARD |
| 103.0 | 108.0 | BL E LS HARD |
| 108.0 | 114.0 | BL E LS SOFT |
| 114.0 | 131.0 | BL E LS HARD |
| 131.0 | 136.0 | GRAY LS SOFT |
| 136.0 | 158.0 | BL E LS HARD |
| 158.0 | 187.0 | GRAY LS HARD |
| 187.0 | 200.0 | W LS SOFT |

| | | | |
|---|---|---|---|
| | 200.0 | 258.0 | BLUE SH SOFT |

*Comments* MC580; VERIFIED BY MANAGER, MC;

# Record of Water Well

85

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219673** | 100YDS W OF KELLY CASTLY SPRING. 300YRS SW OF E. FORK WH RIVER. .5MI DOWN STREAM FROM MONON BRIDGE | Wed, Mar 22, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT M. & LOIS B. MOWERY | 105 SHAWNEE DRIVE BEDFORD, IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 218.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 93.0 ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W

*Section:* SW 1/4 of the NE 1/4 of the NW 1/4 of Section 3 *Topo map:* BEDFORD WEST

*Field located by:* PW *on:* Tue, Aug 17, 1971

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1950 *Ft S of NL:* 1150

*Ground elevation:* 620.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 605.0 *Aquifier elevation:*

*UTM Easting:* 542539.0 *UTM Northing:* 4296121.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 1.0 | DIRT |
| 1.0 | 15.0 | BOULDERS & BROKEN LS |
| 15.0 | 48.0 | GRAY LS SOFT |
| 48.0 | 57.0 | BLUE LS HARD |
| 57.0 | 84.0 | GRAY LS SOFT |
| 84.0 | 106.0 | BLUE LS HARD |
| 106.0 | 112.0 | GRAY LS SOFT |
| 112.0 | 151.0 | BLUE LS HARD |
| 151.0 | 185.0 | WH LS SOFT |
| 185.0 | 195.0 | BLUE SH SOFT |
| 195.0 | 218.0 | WH LS SOFT |

***Comments*** MC605: VERIFIED BY OWNER, MC;

# Record of Water Well

86

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219678** | JUNCTION 50 & 37 WEST ON RD. 50 TO FIRST RD NORTH 1000 FT ON RIGHT | Fri, Oct 04, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WILLIAM LEWIS | 11 MURRAY, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | WILLARD ENGLISH & SON | RR 1, CLAYTON IN | |
| Equipment Operator | LEON ENGLISH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 280.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 44.0 | *Material:* | *Diameter:* 5.5 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.67 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NW 1/4 of Section 3 *Topo map:* BEDFORD WEST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 400 *Ft S of NL:* 1000
*Ground elevation:* 610.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 605.0 *Aquifier elevation:*
*UTM Easting:* 542088.0 *UTM Northing:* 4296145.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

***Comments*** MC605

87

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219683** | 3MI S OF BEDFORD, IND. ON SAND PIT RD | Thu, May 02, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHN TINCHER | BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** STOCK | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 148.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 22.5 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 0.25 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 40.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 4N ***Range:*** 1W
***Section:*** NW 1/4 of the NW 1/4 of the NW 1/4 of Section 2 ***Topo map:*** BEDFORD EAST
***Field located by:*** PW ***on:*** Mon, Aug 16, 1971
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** ***Ft E of WL:*** 450 ***Ft S of NL:*** 100
***Ground elevation:*** 590.0 ***Depth to bedrock:*** 12.0 ***Bedrock elevation:*** 578.0 ***Aquifier elevation:***
***UTM Easting:*** 543661.0 ***UTM Northing:*** 4296439.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | DIRT |
| 12.0 | 33.0 | BR LS SOFT |
| 33.0 | 60.0 | WH LS SOFT |
| 60.0 | 92.0 | BLUE LS HARD |
| 92.0 | 127.0 | WH LS HARD |
| 127.0 | 148.0 | BLUE LS HARD |

***Comments*** MC580; VERIFIED BY OWNER. MC;

# Record of Water Well

88

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219688** | 4 MILES S BEDFORD OVERLOOKING WHITE RIVER | Mon, Nov 02, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BEDFORD CHRISTIAN CAMP | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | GEORGE SNAPP | RR 4, BLOOMINGTON IN | |
| Equipment Operator | GEORGE SNAPP | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 39.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 4.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 2 *Topo map:* BEDFORD EAST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1200
*Ground elevation:* 550.0 *Depth to bedrock:* 35.0 *Bedrock elevation:* 515.0 *Aquifier elevation:*
*UTM Easting:* 544420.0 *UTM Northing:* 4296129.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

*Comments* MC515: SMALL SULPHUR CONTENT

# Record of Water Well

89

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219734** | FROM FAYETTEVILLE GO SOUTH APPROX. 3 MILES TO COXTON, GO SOUTH 1/2 MILE, CROSS CATTLE GUARD, GO TO LAST FARM HOUSE | Sun, Mar 20, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | FRANK SCHERSCHEL | RFD 1, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R #1, BEDFORD | |
| Equipment Operator | L. O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** STOCK | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 200.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** | ***Material:*** | ***Diameter:*** |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 1.5 gpm for 1.0 hrs.
***Drawdown:*** ft. ***Static water level:*** 20.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 4N ***Range:*** 1W
***Section:*** NW 1/4 of the NW 1/4 of the NW 1/4 of Section 5 ***Topo map:*** BEDFORD WEST
***Field located by:*** BARNES ***on:*** Fri, Jul 01, 1960
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** ***Ft E of WL:*** 400 ***Ft S of NL:*** 100
***Ground elevation:*** 520.0 ***Depth to bedrock:*** ***Bedrock elevation:*** ***Aquifer elevation:***
***UTM Easting:*** 538869.0 ***UTM Northing:*** 4296348.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

***Comments*** MC

90

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219739** | NEAR BEDFORD | Sat, Jul 03, 1954 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | JOHN WAGNER | WOODS TERRY RD | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR #3 MITCHELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.33 gpm for hrs.
*Drawdown:* ft. *Static water level:* 67.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* 1/4 of the NE 1/4 of the NW 1/4 of Section 4 *Topo map:* BEDFORD WEST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 540985.0 *UTM Northing:* 4296357.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | WATER @120' |
| 0.0 | 25.0 | OVRBRN CLY ROCKS BRKN LS |
| 25.0 | 28.0 | SOLID ROCK |
| 28.0 | 150.0 | LS |

*Comments* WELL HAS 110 GAL RESERVE CAP. WATER @ 120'.

# Record of Water Well

91

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219744** | BETWEEN MITCHELL & BEDFORD ON SR 37 AT STOP LIGHT WELL #3 | Thu, Oct 03, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MARATHON OIL SERVICE STATION | | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS, INC. | WEST BADEN, IND. R.R. #1 | |
| Equipment Operator | DON CALLAHAN, HOWE WALKER | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* INDUSTRY | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 303.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 58.0 | *Material:* | *Diameter:* 6.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 60.67 ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W

*Section:* SE 1/4 of the SE 1/4 of the NE 1/4 of Section 4 *Topo map:* BEDFORD WEST

*Field located by:* PW *on:* Sun, Jan 17, 1971

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 100 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2050

*Ground elevation:* 610.0 *Depth to bedrock:* 3.0 *Bedrock elevation:* 607.0 *Aquifer elevation:*

*UTM Easting:* 541952.0 *UTM Northing:* 4295829.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | CLAY |
| 3.0 | 11.0 | LS |
| 11.0 | 14.0 | BROKEN STONE & MUD |
| 14.0 | 20.0 | LS |
| 20.0 | 30.0 | SS |
| 30.0 | 58.0 | LIME |
| 58.0 | 303.0 | LS |

***Comments*** MC605. VERIFIED BY MANAGER. MC: LAW 503;

92

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219749** | .25MI N OF JCT SR 37&50 S OF BEDFORD ON WOODS FERRY RD .25MI FROM SR 50 | Wed, Jan 17, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES WOOD | BEDFORD, R.R. 1 | |
| Building Contractor | | | |
| Drilling Contractor | RAY E. ALFORD | MITCHELL R.R. 2 | |
| Equipment Operator | RAY E. ALFORD | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 49.0 | *Material:* | *Diameter:* 6.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 70.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* NW 1/4 of the SE 1/4 of the NE 1/4 of Section 4 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Tue, Aug 17, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1500
*Ground elevation:* 615.0 *Depth to bedrock:* 49.0 *Bedrock elevation:* 566.0 *Aquifier elevation:*
*UTM Easting:* 541589.0 *UTM Northing:* 4295980.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 49.0 | SOIL & CLAY |
| 49.0 | 67.0 | GRAY LIME |
| 67.0 | 72.0 | BR LIME |
| 72.0 | 108.0 | WH LIME |
| 108.0 | 175.0 | GRAY LIME |

***Comments*** MC565;

93

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219754** | SW OF BEDFORD IND ON SR 50 ABOUT 2MI AFTER TURNING W OF 37&50 | Tue, Sep 01, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | EARVIN AND THELMA W MEADOWS | RR 1 BOX 234 BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND. | |
| Equipment Operator | ERIC BUCYRUS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 210.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 63.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 90.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the SE 1/4 of Section 4 *Topo map:* BEDFORD WEST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2250 *Ft N of SL:* 1600 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 595.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 541272.0 *UTM Northing:* 4295345.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | DIRT |
| 20.0 | 60.0 | SOFTLIME&SHALEYE[illegible]LLOFMUDHOLE |
| 60.0 | 155.0 | HARD WH LIME |
| 155.0 | 165.0 | SOFT BLUE LIME |
| 165.0 | 190.0 | HARD BLUE LIME |
| 190.0 | 195.0 | SOFT BLUE LIME |
| 195.0 | 210.0 | HARD BLUE |

***Comments*** [illegible] LOC. ACCEPTED W/O VERIF. NO;

94

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219759** | GOING NORTH ON HIGHWAY 37 & 50 AT JUNCTION, SOUTH OF WHITE RIVER TURN LEFT 1ST ROAD APPROX. 1/4 MI | Wed, Sep 21, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BILL BUCK | | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R #1, BEDFORD | |
| Equipment Operator | L. O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 54.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 3.0 hrs.
*Drawdown:* ft. *Static water level:* 75.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the NE 1/4 of Section 4 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Mon, Aug 17, 1970
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 850 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 100
*Ground elevation:* 600.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 585.0 *Aquifier elevation:*
*UTM Easting:* 541728.0 *UTM Northing:* 4296419.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

*Comments* MC585; VERIFIED BY BUILDER, MC

95

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **320179** | .5 MI S OF JCT 50 & 37 ON HWY37, LT ON WESLYN CHURCH, GO .5 MI E ACROSS RR TRACKS, 3RD HOUSE ON RT | Fri, Nov 06, 1992 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BEN GRIMES | 904 BROOK ST., MITCHELL, IN 47446 | |
| Building Contractor | | | |
| Drilling Contractor | S&S DRILLING INC. | R1 MONTGOMERY, IN 47558 | |
| Equipment Operator | DEXTER SWARTZENTRUBER | License: 302 | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** ROTARY | ***Pump type:*** |
| | ***Depth:*** 180.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 55.0 | ***Material:*** PVC | ***Diameter:*** 6.0 |
| Screen | ***Length:*** 140.0 | ***Material:*** PVC | ***Diameter:*** 4.5 ***Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** 7.0 gpm for hrs. ***BailTest rate:*** gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** ft.

***Grouting Information*** ***Material:*** BNSL ***Depth:*** from 55.0 to 0.0
***Installation Method:*** PUMP ***Number of bags used:*** 2.0

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 4N ***Range:*** 1W
***Section:*** 1/4 of the 1/4 of the 1/4 of Section 3 ***Topo map:*** BEDFORD EAST
***Field located by:*** ***on:***
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** ***Ft E of WL:*** ***Ft S of NL:***
***Ground elevation:*** ***Depth to bedrock:*** ***Bedrock elevation:*** ***Aquifier elevation:***
***UTM Easting:*** ***UTM Northing:***

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 15.0 | CLAY |
| 15.0 | 16.0 | LS |
| 16.0 | 23.0 | GREEN SH |
| 23.0 | 34.0 | LS |
| 34.0 | 38.0 | SOFT GRAY SH |
| 38.0 | 44.0 | LS |
| 44.0 | 47.0 | FRACTURED LIME/MUDDY CLAY |
| 57.0 | 91.0 | TAN LIME |
| 91.0 | 93.0 | FRACTURED LIME |
| 93.0 | 110.0 | BRN LIME |
| 110.0 | 115.0 | DOLOMITE LIME |
| 115.0 | 180.0 | TAN LIME |

***Comments***

96

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220473** | APP T MI SE OF BEDFORD IN ON WHITE RIVER KNOWN AS DUNCAN BEND | Sat, Jan 21, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GENERAL J HALE | BEDFORD RR 5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN RR6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** OTHER | ***Drilling method:*** | ***Pump type:*** |
| | ***Depth:*** 150.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 33.5 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 0.1 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 75.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 4N ***Range:*** 1E
***Section:*** NW 1/4 of the SW 1/4 of the NE 1/4 of Section 6 ***Topo map:*** BEDFORD EAST
***Field located by:*** PJ ***on:*** Mon, Aug 16, 1971
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***

| | | | |
|---|---|---|---|
| ***Ft W of EL:*** 2200 | ***Ft N of SL:*** | ***Ft E of WL:*** | ***Ft S of NL:*** 1550 |
| ***Ground elevation:*** 540.0 | ***Depth to bedrock:*** 8.0 | ***Bedrock elevation:*** 532.0 | ***Aquifer elevation:*** |
| ***UTM Easting:*** 548019.0 | | ***UTM Northing:*** 4296047.0 | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | DIRT |
| 8.0 | 12.0 | GRAY LS HARD |
| 12.0 | 28.0 | BROKEN LS SOFT |
| 28.0 | 33.0 | BLUE LS HARD |
| 33.0 | 150.0 | BLUE SH SOFT |

***Comments*** MC 530: VERIFIED BY NEIGHBOR

97

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220478** | WELL IS 5-1/2 MILES SE OF BEDFORD AND 1/4 MI W OF TUNNELTON ROAD, 33 FT. NW OF BARN | Thu, Oct 12, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WM. DUNCAN | R 5, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 112.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 51.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.02 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 32.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 4N *Range:* 1E
*Section:* NE 1/4 of the SE 1/4 of the NE 1/4 of Section 6 *Topo map:* BEDFORD EAST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 100 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1800
*Ground elevation:* 520.0 *Depth to bedrock:* 50.0 *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 548642.0 *UTM Northing:* 4293972.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

*Comments* MC470

98

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217373** | FROM FAYETTEVILLE ON 58 E, 1ST RD TO R. TURN R ON NEXT RD, 1ST FARM HOUSE. | Sat, Jul 01, 1950 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HALE HALL | R#2, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 179.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 24.5 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 117.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 24 *Topo map:* BEDFORD WEST
*Field located by:* BAINES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2400 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 800
*Ground elevation:* 600.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | RED CLAY |
| 22.0 | 65.0 | WH LIME |
| 65.0 | 85.0 | WH HARD LIME |
| 85.0 | 105.0 | GRAY SOFT LIME |
| 105.0 | 110.0 | WH LIME |
| 110.0 | 125.0 | GRAY SOFT LIME |
| 125.0 | 179.0 | WH AGR LIME |

***Comments*** MC:

99

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217523** | 3 MI E OF FAYETTEVILLE ON BUTTERFLY LANE, E SIDE. | Wed, Jun 05, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MARVEL MAY | RR#2, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | PAUL STULTZ | 1420 W 14TH ST, BLOOMINGTON IN | |
| Equipment Operator | OREN LAKE | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 149.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 72.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 60.0 gpm for hrs.
*Drawdown:* ft. | *Static water level:* 80.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE | *Township:* 5N *Range:* 2W
*Section:* SE 1/4 of the SW 1/4 of the SE 1/4 of Section 13 | *Topo map:* BEDFORD WEST
*Field located by:* U | *on:* Tue, Oct 01, 1963
*Courthouse location by:* | *on:*
*Location accepted w/o verification by:* | *on:*
*Subdivision name:* | *Lot number:*
*Ft W of EL:* 1400 | *Ft N of SL:* 330 | *Ft E of WL:* | *Ft S of NL:*
*Ground elevation:* 635.0 | *Depth to bedrock:* | *Bedrock elevation:* | *Aquifier elevation:*
*UTM Easting:* 536624.0 | *UTM Northing:* 4301260.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 72.0 | DIRT & BROKEN STONE |
| 72.0 | 149.0 | MD GREY STONE |

*Comments*

100

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217528** | 3 MI E OF FAYETTEVILLE IN, ON THE BUTLER FLY LANE. 1ST R, W SIDE ON STILTS. | Sat, May 25, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | KELSO FROST | RR#2, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | PAUL STULTZ | 1420 W 14TH ST, BLOOMINGTON IN | |
| Equipment Operator | OREN LAKE | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 156.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 40.0 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 240.0 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 91.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 2W
***Section:*** SE 1/4 of the SW 1/4 of the SE 1/4 of Section 13 ***Topo map:*** BEDFORD WEST
***Field located by:*** U ***on:*** Tue, Oct 01, 1963
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** 1500 ***Ft N of SL:*** 100 ***Ft E of WL:*** ***Ft S of NL:***
***Ground elevation:*** 635.0 ***Depth to bedrock:*** ***Bedrock elevation:*** ***Aquifier elevation:***
***UTM Easting:*** 536599.0 ***UTM Northing:*** 4301199.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 40.0 | BROKEN STONE RED CLAY |
| 40.0 | 156.0 | GREY STONE |

***Comments*** 40" RED CLAY & BROKEN STONE 116 GREY STONE MD STONE FOR HARDNESS;

101

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217533** | FROM FAYETTEVILLE CHURCH OF CHRIST 1ST HOUSE SOUTH ON EAST SIDE OF RD; 2 NEW HOUSE, SO RD | Sat, May 18, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROSE ROBERTSON | RR WILLIAMS, IN | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 105.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 83.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 2.0 hrs.
*Drawdown:* 5.0 ft. *Static water level:* 75.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* SE 1/4 of the SW 1/4 of the SW 1/4 of Section 13 *Topo map:* BEDFORD WEST
*Field located by:* *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 330 *Ft E of WL:* 1000 *Ft S of NL:*
*Ground elevation:* 635.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 535703.0 *UTM Northing:* 4301249.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | RED CLAY |
| 10.0 | 20.0 | BROKEN LS |
| 20.0 | 40.0 | LS |
| 40.0 | 50.0 | HARD LS |
| 50.0 | 55.0 | SOFT STONE |
| 55.0 | 69.0 | LS |
| 69.0 | 75.0 | SOFT SHELL |
| 75.0 | 93.0 | SOFT LIME |
| 93.0 | 95.0 | BLANK |
| 95.0 | 103.0 | LS |
| 103.0 | 105.0 | SHELL |

***Comments*** NEIGHBOR [illegible]

102

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217538** | ABOUT .25MI W OF FAYETTEVILLE IN. | Wed, May 15, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHN WAY | RR2, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 118.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 68.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 78.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* NW 1/4 of the SE 1/4 of the SW 1/4 of Section 13 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Thu, Aug 01, 1968
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 800 *Ft E of WL:* 1600 *Ft S of NL:*
*Ground elevation:* 600.0 *Depth to bedrock:* 65.0 *Bedrock elevation:* 535.0 *Aquifier elevation:*
*UTM Easting:* 535886.0 *UTM Northing:* 4301402.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 65.0 | BOULDERS MUD HOLES & STONE |
| 65.0 | 79.0 | GRAY LS SOFT |
| 79.0 | 97.0 | BLUE LS SOFT |
| 97.0 | 101.0 | BROKEN STONE SOFT |
| 101.0 | 115.0 | GRAY LS SOFT |
| 115.0 | 118.0 | BROKEN STONE SOFT |

***Comments*** MC 535Page 9525

# Record of Water Well

103

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217543** | FROM FAYETTEVILLE GOING EAST .5 MI BEHIND CHURCH OF CHRIST CHURCH | Fri, Jun 03, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ALVAN ROLLINS | R2 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 13.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 20.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 90.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* NW 1/4 of the SE 1/4 of the SW 1/4 of Section 13 *Topo map:* BEDFORD WEST
*Field located by:* MJ *on:* Wed, Aug 18, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 900 *Ft E of WL:* 1400 *Ft S of NL:*
*Ground elevation:* 610.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 600.0 *Aquifier elevation:*
*UTM Easting:* 535820.0 *UTM Northing:* 4301463.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | CLAY |
| 10.0 | 35.0 | HARD LIME |
| 35.0 | 92.0 | LIME |
| 92.0 | 125.0 | SOFT LIME |

*Comments* MC600; VERIFIED BY OWNER

104

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217548** | FROM FAYETTEVILLE, GO EAST TO 1ST RD TO RIGHT. 2ND HOUSE ON RIGHT | Wed, Aug 10, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MRS. OPAL EMPSON | R1 WILLIAMS, IN | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 90.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 26.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* SE 1/4 of the NW 1/4 of the SE 1/4 of Section 13 *Topo map:* BEDFORD WEST
*Field located by:* S&H *on:* Wed, Nov 02, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1900 *Ft N of SL:* 1600 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 615.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 536466.0 *UTM Northing:* 4301669.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 24.0 | CLAY |
| 24.0 | 28.0 | LIME |
| 28.0 | 32.0 | SHELL |
| 32.0 | 35.0 | LIME |
| 35.0 | 49.0 | LIME |
| 49.0 | 50.0 | SEAM |
| 50.0 | 51.0 | LIME |
| 51.0 | 52.0 | SEAM |
| 52.0 | 55.0 | LIME |
| 55.0 | 60.0 | SHELL |
| 60.0 | 65.0 | LIME |
| 65.0 | 70.0 | SHELL |
| 70.0 | 90.0 | LIME |

*Comments* MC: FE 0.1 PPM, HARDNESS 353 PPM, PH 8.0, CHLORIDE 8 PPM

105

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217553** | ABOUT 5 MI W ON SR158 AT 537 W & 50N & 15 RODS W. FAYETTEVILLE AREA. | Thu, Apr 25, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MR. JAMES M. CANADA | RR1, WILLIAMS IN | |
| Building Contractor | | | |
| Drilling Contractor | MUMMA DRLG INC. | WASHINGTON & LYONS IN | |
| Equipment Operator | DEAN K. MUMMA | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 130.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 35.0 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for 1.5 hrs.
*Drawdown:* ft. *Static water level:* 60.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 13 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Wed, Aug 18, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*

| | | | |
|---|---|---|---|
| *Ft W of EL:* 2300 | *Ft N of SL:* 2700 | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* 620.0 | *Depth to bedrock:* 34.0 | *Bedrock elevation:* 586.0 | *Aquifer elevation:* |
| *UTM Easting:* 536345.0 | | *UTM Northing:* 4302010.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 34.0 | CLAY & BOULDERS |
| 34.0 | 105.0 | LIME & BREAKS & SHALE |
| 105.0 | 130.0 | SANDY LIME WATER |

*Comments* MC 585; VERIFIED BY OWNER; PH 7.8, IRON 0.5, HARDNESS 23 GRAINS; SEE MAP;

106

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217558** | TAKE 16TH ST RD W OF BEDFORD, 1.5MI W EUREKA TO T RD .5 MI N OF T RD. | Thu, Apr 17, 1969 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES H. EAGAN | SPRINGVILLE IN | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN ST, PAOLI IN | |
| Equipment Operator | WENDELL NEWLIN&DON CALLAHAN | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 65.0 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 4.0 gpm for hrs. — *Drawdown:* ft. — *Static water level:* 60.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 2W

*Section:* SW 1/4 of the SE 1/4 of the NW 1/4 of Section 12 — *Topo map:* OOLITIC

*Field located by:* PW — *on:* Wed, Aug 18, 1971

*Courthouse location by:* — *on:*

*Location accepted w/o verification by:* — *on:*

*Subdivision name:* — *Lot number:*

*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* 1700 — *Ft S of NL:* 2500

*Ground elevation:* 700.0 — *Depth to bedrock:* 7.0 — *Bedrock elevation:* 693.0 — *Aquifier elevation:*

*UTM Easting:* 535911.0 — *UTM Northing:* 4303673.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 7.0 | CLAY |
| 7.0 | 15.0 | LS |
| 15.0 | 25.0 | SOFT STONE |
| 25.0 | 45.0 | BROKEN STONE & MUD |
| 45.0 | 55.0 | LIME |
| 55.0 | 115.0 | BUFF COLORED LIME |
| 115.0 | 120.0 | HARD LIME |
| 120.0 | 140.0 | WATER BEARING SHALE & PORUS LI |

***Comments*** MC 695; VERIFIED BY OWNER

107

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217563** | W OUT OF BEDFORD, 16TH ST TOWARD FAYETTEVILLE TURN R GO N 2.5 MI, TURN R 1ST HOUSE ON R. | Mon, Dec 03, 1973 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DOUG KELLY | RR2, BEDFORD IN | |
| Building Contractor | FORREST LAKE | RR2, BEDFOR IN | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN ST, PAOLI IN | |
| Equipment Operator | GORDON BURTON | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 130.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 114.0 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* PUMPING *Test rate:* 15.0 gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* 40.0 ft. *Static water level:* 70.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* NW 1/4 of the NE 1/4 of the NW 1/4 of Section 12 *Topo map:* OOLITIC
*Field located by:* JRD *on:* Tue, Aug 08, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1750 *Ft S of NL:* 100
*Ground elevation:* 685.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 675.0 *Aquifer elevation:*
*UTM Easting:* 535961.0 *UTM Northing:* 4304386.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | CLAY |
| 10.0 | 25.0 | LS & BROKEN ROCK |
| 25.0 | 30.0 | SHELL |
| 30.0 | 35.0 | LIME |
| 35.0 | 45.0 | CAVE |
| 45.0 | 75.0 | LS |
| 75.0 | 80.0 | BROKEN ROCK & MUD |
| 80.0 | 100.0 | LS |
| 100.0 | 103.0 | BROKEN ROCK |
| 103.0 | 107.0 | CAVE |
| 107.0 | 125.0 | LS |
| 125.0 | 127.0 | SHELL |
| 127.0 | 130.0 | LIME |

*Comments* MC 675; OWNER VERIFIED/15' NW OF HOUSE:

108

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217568** | GO W TO CROOSRDS AT FAYETTEVILLE-TURN R(N) THEN GOTO NEXT CROSSRDS, TURN L(W). HOUSE TRAILER IN THE FIELD. | Fri, Mar 08, 1974 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RICHARD PIERCE | RR#2, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN ST, PAOLI IN | |
| Equipment Operator | GORDON BURTON | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 143.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 61.0 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test* — *Type of test:* PUMPING; *Test rate:* 11.0 gpm for hrs.; *BailTest rate:* gpm for hrs.
*Drawdown:* 73.0 ft.; *Static water level:* 70.0 ft.

*Grouting Information* — *Material:*; *Depth:* from to
*Installation Method:*; *Number of bags used:*

*Well Abandonment* — *Sealing material:*; *Depth:* from to
*Installation Method:*; *Number of bags used:*

*Administrative*

*County:* LAWRENCE; *Township:* 5N *Range:* 2W
*Section:* NW 1/4 of the NW 1/4 of the NW 1/4 of Section 12; *Topo map:* OOLITIC
*Field located by:* JRD; *on:* Tue, Aug 08, 1978
*Courthouse location by:*; *on:*
*Location accepted w/o verification by:*; *on:*
*Subdivision name:*; *Lot number:*
*Ft W of EL:*; *Ft N of SL:*; *Ft E of WL:* 400; *Ft S of NL:* 300
*Ground elevation:* 690.0; *Depth to bedrock:* 10.0; *Bedrock elevation:* 680.0; *Aquifier elevation:*
*UTM Easting:* 535534.0; *UTM Northing:* 4304338.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | CLAY |
| 10.0 | 15.0 | LS |
| 15.0 | 20.0 | SHELL |
| 20.0 | 25.0 | LIME |
| 25.0 | 47.0 | BROKEN ROCK & MUD |
| 47.0 | 50.0 | LIME |
| 50.0 | 55.0 | MUD |
| 55.0 | 100.0 | LIME |
| 100.0 | 105.0 | SHELL |
| 105.0 | 143.0 | LIME |

*Comment* MC 680; OWNER VERIFIED/50' W OF TRAILER

109

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217573** | FROM FAYETTEVILLE GOING EAST, TURN 1ST RD NORTH 4TH HOUSE ON LEFT | Tue, Sep 17, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES CHASTAIN | R2 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 40.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 140.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 2W
*Section:* NE 1/4 of the SW 1/4 of the NW 1/4 of Section 12 *Topo map:* OOLITIC
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1000 *Ft S of NL:* 1800
*Ground elevation:* 730.0 *Depth to bedrock:* *Bedrock elevation:* 690.0 *Aquifier elevation:*
*UTM Easting:* 535746.0 *UTM Northing:* 4303862.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 40.0 | CLAY |
| 40.0 | 58.0 | LIME |
| 58.0 | 89.0 | HARD LIME |
| 89.0 | 90.0 | SOFT SEAM |
| 90.0 | 119.0 | LIME |
| 119.0 | 121.0 | BROKEN |
| 121.0 | 175.0 | LIME |

*Comments* MC69Page 9577

110

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217578** | GO TO BEDFORD- GO OUT TOWARD FAYETTEVILLE | Mon, Jun 11, 1973 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WILLIAM WALKER | RR2 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | | | |
| Equipment Operator | GORDON BURTON | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** OTHER | ***Pump type:*** |
| | ***Depth:*** 123.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 95.0 | ***Material:*** | ***Diameter:*** 6.62 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 10.0 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 80.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 2W
***Section:*** NW 1/4 of the NW 1/4 of the NE 1/4 of Section 12 ***Topo map:*** OOLITIC
***Field located by:*** JRD ***on:*** Wed, Aug 09, 1978
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** 2600 ***Ft N of SL:*** ***Ft E of WL:*** ***Ft S of NL:*** 50
***Ground elevation:*** 660.0 ***Depth to bedrock:*** 20.0 ***Bedrock elevation:*** 640.0 ***Aquifer elevation:***
***UTM Easting:*** 536217.0 ***UTM Northing:*** 4304398.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 26.0 | SS |
| 26.0 | 31.0 | MUD |
| 31.0 | 43.0 | LS |
| 43.0 | 48.0 | MUD |
| 48.0 | 68.0 | LS |
| 68.0 | 71.0 | SHALE |
| 71.0 | 74.0 | LS |
| 74.0 | 78.0 | MUD |
| 78.0 | 90.0 | BROKEN ROCK & MUD |
| 90.0 | 105.0 | LS |
| 105.0 | 109.0 | SHALE |
| 109.0 | 123.0 | LS |

*Comments* MC640: OWNER VERIFIED/50' S OF RD; WELL PUMPED DRY DURING TEST

111

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **317714** | 9 MI ON 158W RIGHT OLD CRAGE MILL RD, FIRST HOUSE ON LT, R12 BOX 442, WILLIAMS, IN | Sat, Apr 15, 1995 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | KIM & JAY PHILLIPS | RR1 BOX 442, WILLIAMS,IN 47470 | (812)279-6415 |
| Building Contractor | | | |
| Drilling Contractor | PHILLIPS WELL DRILLING | RR12 BOX 624, BEDFORD,IN 47421 | (812)279-4843 |
| Equipment Operator | JUNIOR PHILLIPS | License: 208 | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* CLEAR, ODOR |
| Casing | *Length:* 30.0 | *Material:* PVC | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* AIR; *Test rate:* 6.0 gpm for 120.0 hrs.; *BailTest rate:* gpm for hrs.; *Drawdown:* ft.; *Static water level:* ft.

***Grouting Information*** — *Material:* BENT; *Depth:* from 0.0 to 30.0; *Installation Method:* PUMP; *Number of bags used:* 2.0

***Well Abandonment*** — *Sealing material:*; *Depth:* from to; *Installation Method:*; *Number of bags used:*

***Administrative***

| | | | |
|---|---|---|---|
| *County:* LAWRENCE | | *Township:* 5N *Range:* 2W | |
| *Section:* 1/4 of the 1/4 of the SE 1/4 of Section 13 | | | *Topo map:* BEDFORD WEST |
| *Field located by:* | | *on:* | |
| *Courthouse location by:* | | *on:* | |
| *Location accepted w/o verification by:* | | *on:* | |
| *Subdivision name:* | | *Lot number:* | |
| *Ft W of EL:* | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* | *Depth to bedrock:* | *Bedrock elevation:* | *Aquifier elevation:* |
| *UTM Easting:* | | *UTM Northing:* | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 2.0 | TOPSOIL |
| 2.0 | 8.0 | CLAY |
| 8.0 | 140.0 | BEDROCK |

***Comments***

117

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217377** | ABOUT 2.5 MI OFF SR54 ON MILLRIDGE RD, W OF BEDFORD. | Fri, Jan 18, 1974 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DICK JONES | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN, PAOLI IN | |
| Equipment Operator | RALPH BURTON&GORDON BURTON | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 123.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* PUMPING; *Test rate:* -15.0 gpm for hrs.; *BailTest rate:* gpm for hrs.; *Drawdown:* ft.; *Static water level:* 70.0 ft.

***Grouting Information*** — *Material:*; *Depth:* from to; *Installation Method:*; *Number of bags used:*

***Well Abandonment*** — *Sealing material:*; *Depth:* from to; *Installation Method:*; *Number of bags used:*

***Administrative***

*County:* LAWRENCE; *Township:* 5N *Range:* 2W

*Section:* SW 1/4 of the SW 1/4 of the SE 1/4 of Section 1; *Topo map:* OOLITIC

*Field located by:* JRD; *on:* Tue, Aug 08, 1978

*Courthouse location by:*; *on:*

*Location accepted w/o verification by:*; *on:*

*Subdivision name:*; *Lot number:*

*Ft W of EL:* 900; *Ft N of SL:* 100; *Ft E of WL:*; *Ft S of NL:*

*Ground elevation:* 670.0; *Depth to bedrock:* 30.0; *Bedrock elevation:* 640.0; *Aquifer elevation:*

*UTM Easting:* 536326.0; *UTM Northing:* 4304446.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | CLAY & MUD |
| 30.0 | 35.0 | LIME |
| 35.0 | 40.0 | BROKEN ROCK & MUD |
| 40.0 | 45.0 | LIME |
| 45.0 | 50.0 | SHELL |
| 50.0 | 55.0 | LIME |
| 55.0 | 65.0 | BROKEN ROCK & MUD |
| 65.0 | 70.0 | LIME |
| 70.0 | 75.0 | SHELL |
| 75.0 | 80.0 | LIME |
| 80.0 | 90.0 | SOFT FORM.BROKENROCK&MUD |
| 90.0 | 105.0 | LS |
| 105.0 | 107.0 | SHELL |

| | | |
|---|---|---|
| 107.0 | 123.0 | LIME |

*Comments* MC 640; OWNER VERIFIED/SW CORNER OF HOUSE;

113

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217365** | FROM BEDFORD GO S ON OLD RD 37 TURN ON SANDPIT RD GO E 1/2 MI WELL IS LOCATED JUST BEFORE YOU GET TO RR TRACKS ON THE R DRILLED WELL FOR JIM GILBERT | Tue, Jan 01, 1980 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | TINA SCHALER | BEDFORD IN 47421 | |
| Building Contractor | | | |
| Drilling Contractor | PHILLIPS WELL DRILLING | R#12 BOX 323A BEDFFORD IN 47421 | |
| Equipment Operator | PHILLIPS WELL DRILLING | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* SUBMERSIBLE |
| | *Depth:* 97.0 | *Pump setting depth:* 90.0 | *Water quality:* ODOR |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* gpm for hrs.
*Drawdown:* ft. — *Static water level:* 35.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the NW 1/4 of the SE 1/4 of Section 34 — *Topo map:* BEDFORD WEST
*Field located by:* — *on:*
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* LW 3/20/86 — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 1750 — *Ft E of WL:* 3300 — *Ft S of NL:*
*Ground elevation:* 535.0 — *Depth to bedrock:* 25.0 — *Bedrock elevation:* 510.0 — *Aquifier elevation:*
*UTM Easting:* 542926.0 — *UTM Northing:* 4297103.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 25.0 | RED CLAY |
| 25.0 | 97.0 | BEDROCK |

*Comments* SEE COUTNY FILE FOR LOCATION INFOPage 9564

114

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217370** | S ON OLD 37 S TO TURN ON LEATHERWOOD RD GO 1/4 MI S OF THE US 50 & SR 37 JUNCTION ON JIM GILBERTS OLD PLACE. | Wed, Jan 01, 1986 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | TINA SCHALER | BEDFORD IN 47421 | |
| Building Contractor | | | |
| Drilling Contractor | PHILLIPS WELL DRILLING | R #12 BOX 323A BEDFORD IN 47421 | |
| Equipment Operator | PHILLIPS WELL DRILLING | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 170.0 | *Pump setting depth:* | *Water quality:* MUDDY & MUD |
| Casing | *Length:* 170.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 130.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SE 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* LW 3/20/86 *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2050 *Ft E of WL:* 3900 *Ft S of NL:*
*Ground elevation:* 542.0 *Depth to bedrock:* 105.0 *Bedrock elevation:* 437.0 *Aquifer elevation:*
*UTM Easting:* 543151.0 *UTM Northing:* 4297133.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | SAND |
| 30.0 | 105.0 | BLUE CLAY |
| 105.0 | 170.0 | BEDROCK |

*Comments* LOCATION INFO IN COUNTY FILE

115

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217375** | GOTO 4 LANE SR ON 37 ACROSS NEW BRIDGE & TURN R. TRAILER COURT ON R. | Thu, Nov 02, 1972 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LEROY RAGSDALE | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN, PAOLI IN 47454 | |
| Equipment Operator | GORDON BURTON | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 63.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 36.0 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 30.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 15.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the SE 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* JRD *on:* Fri, Aug 11, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*

| | | | |
|---|---|---|---|
| *Ft W of EL:* 500 | *Ft N of SL:* 2300 | *Ft E of WL:* 4700 | *Ft S of NL:* |
| *Ground elevation:* 525.0 | *Depth to bedrock:* 30.0 | *Bedrock elevation:* 495.0 | *Aquifer elevation:* |
| *UTM Easting:* 543389.0 | | *UTM Northing:* 4297194.0 | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | CLAY |
| 4.0 | 30.0 | SAND |
| 30.0 | 41.0 | LS |
| 41.0 | 48.0 | SHALE |
| 48.0 | 63.0 | LS |

***Comments*** MC 495 OWNER VERIFIED 100'S OF RD 150' SE OF BENCH MARK;

116

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217434** | 2MI NE OF BEDFORD IND. 1MI N ON MT PLESANT RD & 1MI E WELL IN BACK OF TRAILER | Sat, Jul 27, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ELMER ARNALD | BEDFORD R.R. | |
| Building Contractor | | | |
| Drilling Contractor | RAY E. ALFORD | MITCHELL IND. R.R. 2 | |
| Equipment Operator | RAY E. ALFORD | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 121.5 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.05 gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 6 *Topo map:* BARTLETTSVILLE
*Field located by:* N *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2000 *Ft S of NL:* 2600
*Ground elevation:* 735.0 *Depth to bedrock:* 6.0 *Bedrock elevation:* 729.0 *Aquifer elevation:*
*UTM Easting:* 547358.0 *UTM Northing:* 4305321.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | CLAY |
| 6.0 | 105.0 | GRAY & WH LS |
| 105.0 | 121.5 | NAB STONE SH ,WATER VERY LITE |

***Comments*** MC730; Page 0560

117

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217385** | 300' W OF EAST FORK OF WHITE RIVER 200' S OF OLD SR37 BRIDGE ABUTMENT APPROX. 3 MI S OF BEDFORD, IN ON LOT 14 OF RIVER HEIGHTS ADD. TO LAWRENCE COUNTY | Wed, Apr 27, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JERRY D. BECHNER | 1622 18TH ST., BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BOX 13, BEDFORD, IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 67.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 10.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 27.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1300 *Ft E of WL:* 1200 *Ft S of NL:*
*Ground elevation:* 490.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 542341.0 *UTM Northing:* 4296865.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 14.0 | SANDY DIRT |
| 14.0 | 20.0 | SHELL LS |
| 20.0 | 50.0 | WHITE LIME HARD |
| 50.0 | 55.0 | SS BROWN |
| 55.0 | 67.0 | BLUE LS HARD |

***Comments*** MC

118

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217390** | WELL #1 S LAWRENCE WATER UTLS NEAR WHITE RIVER BRIDGE ON SR37, S IF BEDFORD IN. | Fri, Jan 30, 1970 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | S LAWRENCE UTLS. INC. | HURON IN | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN ST, PAOLI IN 47454 | |
| Equipment Operator | DON CALLAHAN | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 63.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 46.0 | *Material:* | *Diameter:* 12.0 |
| Screen | *Length:* 15.0 | *Material:* | *Diameter:* 12.0 *Slot size:* 25-30 |

***Well Capacity Test***

*Type of test:* PUMPING *Test rate:* 20.0 gpm for 0.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 8.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* 1/4 of the 1/4 of the 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 542214.0 *UTM Northing:* 4297273.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 26.0 | BR SAND |
| 26.0 | 30.0 | MD SAND |
| 30.0 | 34.0 | S&G |
| 34.0 | 38.0 | GOOD S&G |
| 38.0 | 47.0 | FN S&G |
| 47.0 | 56.0 | FN S & SM MD G |
| 56.0 | 58.0 | GRAV & BROKEN STONE |
| 58.0 | 60.0 | BROKEN LS |
| 60.0 | 63.0 | SHALE GRAY |

*Comments* WELL PUMPED DRY DURING TEST; LAYNE NORTHERN 25'-45' 60 SCREEN, 45'-62' 100SCREEN;

119

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217395** | NEAR WHITE RIVER BRIDGE ON SR37, S OF BEDFORD IN. | Tue, Mar 24, 1970 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | S LAWRENCE WATER UTLS. INC. | HURON IN. | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN ST, PAOLI IN 47454 | |
| Equipment Operator | DON CALLAHAN | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 68.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 54.0 | *Material:* | *Diameter:* 12.0 |
| Screen | *Length:* 15.0 | *Material:* | *Diameter:* 12.0 *Slot size:* 25-30 |

***Well Capacity Test***

*Type of test:* PUMPING *Test rate:* 40.0 gpm for 24.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* 40.0 ft. *Static water level:* 8.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NW 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* STEEN *on:* Mon, Jun 01, 1970
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2700 *Ft E of WL:* 200 *Ft S of NL:*
*Ground elevation:* 490.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:* 420.0
*UTM Easting:* 542031.0 *UTM Northing:* 4297798.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 25.0 | FN SAND BR IN COLOR |
| 25.0 | 28.0 | SAND & CLAY MIXED |
| 28.0 | 32.0 | GRAV |
| 32.0 | 35.0 | SAND |
| 35.0 | 38.0 | CLAY & SAND MIXED |
| 38.0 | 45.0 | SAND |
| 45.0 | 68.0 | GOOD S&G |

*Comments* CHEM TEST; WELL #1;

120

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217844** | NEAR WHITE RIVER BRIDGE ON SR37 S OF BEDFORD IN. | Tue, May 05, 1970 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | S LAWRENCE WATER UTLS. INC. | HURON IN | |
| Building Contractor | | | |
| Drilling Contractor | JOHN REYNOLDS & SONS INC. | 816 W MAIN ST, PAOLI IN | |
| Equipment Operator | DON CALLAHAN | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 72.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 57.0 | *Material:* | *Diameter:* 12.0 |
| Screen | *Length:* 15.0 | *Material:* | *Diameter:* 12.0 *Slot size:* 25-30 |

*Well Capacity Test*

*Type of test:* PUMPING *Test rate:* 140.0 gpm for 24.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* 40.0 ft. *Static water level:* 8.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NW 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* STEEN *on:* Mon, Jun 01, 1970
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2850 *Ft E of WL:* 350 *Ft S of NL:*
*Ground elevation:* 490.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:* 420.0
*UTM Easting:* 542075.0 *UTM Northing:* 4297306.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 25.0 | FN SAND & BR IN COLOR |
| 25.0 | 28.0 | SAND & CLAY MIXED |
| 28.0 | 32.0 | GRAV |
| 32.0 | 35.0 | SAND |
| 35.0 | 38.0 | CLAY & SAND MIXED |
| 38.0 | 45.0 | SAND |
| 45.0 | 72.0 | GOOD S&G |

*Comments* CHEM TEST; WELL #2:

121

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217849** | SR 37 S OF BEDFORD ON R AFTER CROSSING WHITE RIVER. NEXT TO RIVER IN VICINITY OF 1980 REYNOLDS TEST WELLS, TMB 8/17/83. | Mon, Jun 27, 1983 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | S LAWRENCE WATER UTLS. INC. | R2, MITCHELL IN 47446 | |
| Building Contractor | | | |
| Drilling Contractor | REYNOLDS SUPPLY INC. | PO BOX 230, 816 W MAIN ST, PAOLI IN 47454 | |
| Equipment Operator | RALPH BURTON | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* OTHER | *Drilling method:* REVERSE ROTARY | *Pump type:* |
| | *Depth:* 88.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 68.0 | *Material:* | *Diameter:* 20.0 |
| Screen | *Length:* 20.0 | *Material:* | *Diameter:* 18.0 *Slot size:* 60 |

***Well Capacity Test***

*Type of test:* PUMPING *Test rate:* 250.0 gpm for 24.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* 7.25 ft. *Static water level:* 16.1 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the NW 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* BRUNS *on:* Wed, Aug 17, 1983
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 550 *Ft S of NL:* 1700
*Ground elevation:* 490.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:* 405.0
*UTM Easting:* 542139.0 *UTM Northing:* 4297530.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 35.0 | CLAY & SAND MIXED |
| 35.0 | 40.0 | FN SAND |
| 40.0 | 45.0 | CRS GRAV & SAND |
| 45.0 | 50.0 | CRS GRAV & SAND |
| 50.0 | 55.0 | CRS GRAV & SAND |
| 55.0 | 60.0 | CRS GRAV & SAND |
| 60.0 | 65.0 | CRS GRAV & SAND |
| 65.0 | 70.0 | CRS S&G |
| 70.0 | 75.0 | MD S&G |
| 75.0 | 80.0 | MD S&G |
| 80.0 | 85.0 | FN SAND |
| 85.0 | 87.0 | FN SAND & CLAY BOTTOM |

***Comments***

MC 405; WELL #4 NPage 0596

122

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217854** | SR37 S OF BEDFORD ON R AFTER CROSSING WHITE RIVER. NEXT TO RIVER IN AREA OF 1980 REYNOLDS TEST HOLES. TMB 8/17/83. | Fri, Jul 01, 1983 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | S LAWRENCE WATER UTLS. INC. | R2, MITCHELL IN 47446 | |
| Building Contractor | | | |
| Drilling Contractor | REYNOLDS SUPPLY INC. | PO BOX 230, 816 W MAIN ST, PAOLI IN 47454 | |
| Equipment Operator | RALPH BURTON | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* REVERSE ROTARY | *Pump type:* |
| | *Depth:* 87.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 67.0 | *Material:* | *Diameter:* 20.0 |
| Screen | *Length:* 20.0 | *Material:* | *Diameter:* 18.0 *Slot size:* 60 |

***Well Capacity Test***

*Type of test:* PUMPING *Test rate:* 250.0 gpm for 24.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* 7.7 ft. *Static water level:* 23.4 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* BRUNS *on:* Wed, Aug 17, 1983
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 700 *Ft S of NL:* 2150
*Ground elevation:* 490.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:* 405.0
*UTM Easting:* 542188.0 *UTM Northing:* 4297371.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 35.0 | CLAY & SAND MIXED |
| 35.0 | 40.0 | FN SAND |
| 40.0 | 45.0 | CRS GRAV & SAND |
| 45.0 | 50.0 | CRS GRAV & SAND |
| 50.0 | 55.0 | CRS GRAV & SAND |
| 55.0 | 60.0 | CRS GRAV & SAND |
| 60.0 | 65.0 | CRS GRAV & SAND |
| 65.0 | 70.0 | CRS S&G |
| 70.0 | 75.0 | MD S&G |
| 75.0 | 80.0 | MD S&G |
| 80.0 | 85.0 | FN SAND |
| 85.0 | 88.0 | FN SAND & CLAY BOTTOM |

***Comments***

MC 405. [illegible] LOCATION DECRIBED BY JOHN SCHMIDT FROM REYNOLDS OFFICE.

123

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217859** | | Tue, Oct 21, 1980 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | SOUTH LAWRENCE UTILITIES | | |
| Building Contractor | | | |
| Drilling Contractor | | | |
| Equipment Operator | GENE WILLIAMS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* | *Pump type:* |
| | *Depth:* 82.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 15.35 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 34 *Topo map:* BEDFORD WEST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* BRUNS *on:* Tue, Jun 02, 1981
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 675 *Ft S of NL:* 2075
*Ground elevation:* 490.0 *Depth to bedrock:* 82.0 *Bedrock elevation:* 408.0 *Aquifer elevation:*
*UTM Easting:* 542193.0 *UTM Northing:* 4297431.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DK BRN . SILTY SANDY CLAY |
| 3.0 | 13.0 | M. BRN. SILTY CLAY |
| 13.0 | 18.0 | M. BRN. SILTY. SANDY CLAY |
| 18.0 | 23.0 | SAND |
| 23.0 | 28.0 | M. SAND |
| 28.0 | 38.0 | M. SAND |
| 38.0 | 53.0 | M. SAND W/ PEA GRAVEL |
| 53.0 | 63.0 | M. SAND |
| 63.0 | 78.0 | M. TO C SAND W/ GRAVEL |
| 78.0 | 82.0 | M TO C SAND W/ PEA GRAVEL |

*Comments* SAND ANALYSIS ATTACHED: CHEM. TEST: OW 4.

124

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217864** | | Tue, Oct 21, 1980 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | SOUTH LAWRENCE UTILITIES | | |
| Building Contractor | | | |
| Drilling Contractor | REYNOLDS SUPPLY | | |
| Equipment Operator | GENE WILLIAMS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* | *Pump type:* |
| | *Depth:* 82.5 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* gpm for hrs. | *Drawdown:* ft. | *Static water level:* 15.58 ft.

*Grouting Information*: *Material:* | *Depth:* from to | *Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to | *Installation Method:* | *Number of bags used:*

*Administrative*

| | | | |
|---|---|---|---|
| *County:* LAWRENCE | | *Township:* 5N *Range:* 1W | |
| *Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 34 | | | *Topo map:* BEDFORD WEST |
| *Field located by:* | | *on:* | |
| *Courthouse location by:* | | *on:* | |
| *Location accepted w/o verification by:* BRUNS | | *on:* Tue, Jun 02, 1981 | |
| *Subdivision name:* REYNOLDS | | *Lot number:* | |
| *Ft W of EL:* | *Ft N of SL:* | *Ft E of WL:* 700 | *Ft S of NL:* 2125 |
| *Ground elevation:* 490.0 | *Depth to bedrock:* 83.0 | *Bedrock elevation:* 407.0 | *Aquifer elevation:* |
| *UTM Easting:* 542198.0 | | *UTM Northing:* 4297380.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DK BRN, SILTY FN SANDY TOP SOI |
| 3.0 | 13.0 | M. BRN SILTY CLAY |
| 13.0 | 18.0 | M. BRN, SANDY, SILTY, CLAY |
| 18.0 | 23.0 | NO RETURN, PROBABLY SAND |
| 23.0 | 28.0 | BLANK |
| 28.0 | 82.5 | MED. SAND |

*Comments*: CHEM. TEST; OW-3; SAND ANALYSIS ATTACHED;

125

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217869** | 50'N OF OW-1 (80) | |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | SOUTH LAWRENCE UTILITIES | | |
| Building Contractor | | | |
| Drilling Contractor | | | |
| Equipment Operator | GENE WILLIAMS | License: 102080 | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* | *Pump type:* |
| | *Depth:* 84.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.

*Drawdown:* ft. *Static water level:* 15.24 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 34 *Topo map:* BEDFORD WEST

*Field located by:* *on:*

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* BRUNS *on:* Tue, Jun 02, 1981

*Subdivision name:* REYNOLDS *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 700 *Ft S of NL:* 2175

*Ground elevation:* 490.0 *Depth to bedrock:* 84.0 *Bedrock elevation:* 406.0 *Aquifier elevation:*

*UTM Easting:* 542198.0 *UTM Northing:* 4297333.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.5 | BRN SANDY TOPSOIL |
| 0.5 | 8.0 | M. BRN SAND/ SILT CLAY |
| 8.0 | 18.0 | M. BRN. SILTY CLAY |
| 18.0 | 23.0 | SAND |
| 23.0 | 84.0 | M.C SAND |

*Comments* CHEM TEST; OW-2; ATTACHED SAND ANALYSIS GRAPHS;

# Record of Water Well

126

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217909** | W OF WHITE RIVER BRIDGE, NEAR SR37 & 50 2 MI S OF BEDFORD, IN AT CATTLE FARM W OF TOOL SHED ON HILL | Fri, Oct 19, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BEN A. HITCHCOCK | 1625 N ST., BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BEDFORD, IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 170.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 22.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 15.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 94.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SE 1/4 of Section 33 *Topo map:* BEDFORD WEST
*Field located by:* *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1500 *Ft N of SL:* 2100 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 590.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 541505.0 *UTM Northing:* 4297121.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 23.0 | BLUE LS & BOULDERS |
| 23.0 | 30.0 | BLUE LS HARD |
| 30.0 | 70.0 | BROWN LS SOFT |
| 70.0 | 92.0 | BLUE LS SOFT |
| 92.0 | 104.0 | BLUE SHALE SOFT |
| 104.0 | 118.0 | GRAY LS HARD |
| 118.0 | 165.0 | BLUE LS HARD |
| 165.0 | 170.0 | BLUE SHALE SOFT |

***Comments***

# Record of Water Well

127

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217914** | FROM JCT 37 & 50 SOUTH OF BEDFORD GO NORTH 1ST RD ON LEFT AS OF NOW IS LAST HOUSE ON RIGHT | Wed, Mar 22, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES DWYER | | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 135.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 17.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 2.0 gpm for 2.0 hrs.
*Drawdown:* ft. | *Static water level:* 85.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE | *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SE 1/4 of the SE 1/4 of Section 33 | *Topo map:* BEDFORD WEST
*Field located by:* PW | *on:* Tue, Aug 17, 1971
*Courthouse location by:* | *on:*
*Location accepted w/o verification by:* | *on:*
*Subdivision name:* | *Lot number:*
*Ft W of EL:* 1100 | *Ft N of SL:* 100 | *Ft E of WL:* | *Ft S of NL:*
*Ground elevation:* 610.0 | *Depth to bedrock:* 16.0 | *Bedrock elevation:* 594.0 | *Aquifer elevation:*
*UTM Easting:* 541627.0 | *UTM Northing:* 4296463.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 15.0 | CLAY |
| 15.0 | 16.0 | BLANK |
| 16.0 | 35.0 | LIME |
| 35.0 | 44.0 | SHELL |
| 44.0 | 45.0 | BLANK |
| 45.0 | 135.0 | MED LIME |

*Comments*: MC595: VERIFIED BY OWNERPage 9600

128

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217919** | 1ST HOUE ON LEFT AFTER CROSS RR AT COXTON | Fri, Jul 14, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HARRY VOORHIES | R1 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 80.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 20.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 10.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 31 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Tue, Aug 17, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2050 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 850
*Ground elevation:* 520.0 *Depth to bedrock:* 18.0 *Bedrock elevation:* 502.0 *Aquifer elevation:*
*UTM Easting:* 538122.0 *UTM Northing:* 4297743.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | CLAY |
| 18.0 | 62.0 | LIME |
| 62.0 | 70.0 | HARD LIME |
| 70.0 | 80.0 | MED LS |

***Comments*** MC500; VERIFIED BY OWNER

129

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217924** | FROM FAYETTEVILLE GO S TO 450 CROSS 450 GO TO RR 2ND HOUSE ON LEFT | Tue, May 02, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MARY SHELP | R1 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 109.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 66.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 26.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the NW 1/4 of the NE 1/4 of Section 31 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Tue, Aug 17, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1800 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1000
*Ground elevation:* 520.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 500.0 *Aquifer elevation:*
*UTM Easting:* 538201.0 *UTM Northing:* 4297687.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 30.0 | SOFT GRAY |
| 30.0 | 35.0 | SOFT BROWN |
| 35.0 | 55.0 | SOFT GRAY |
| 55.0 | 65.0 | SOFT BROWN |
| 65.0 | 75.0 | MED LS |
| 75.0 | 109.0 | HARD LIME |

***Comments*** MC500, VERIFIED BY OWNER

130

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217929** | FROM FAYETTEVILLE GO S TO 450 CROSS 450 GOING S TO CATTLE YARD TURN RIGHT 1ST HOUSE ON RIGHT | Thu, Mar 30, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DAVID INMAN | R1 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 95.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 25.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 10.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 58.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 31 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Tue, Aug 17, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2500
*Ground elevation:* 550.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 530.0 *Aquifer elevation:*
*UTM Easting:* 538073.0 *UTM Northing:* 4297207.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 25.0 | GRAY LIME |
| 25.0 | 40.0 | DARK LIME |
| 40.0 | 90.0 | WHITE LIME |
| 90.0 | 91.0 | WATER SEAM |
| 91.0 | 95.0 | WHITE LIME |

***Comments***

MC530; VERIFIED BY OWNEPage 9601

131

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217934** | GOING W FROM BEDFORD ON 450 APROX. 5 MI TO FAYETTEVILLE & COXTON CROSSRD. TURN LEFT GO TO RR. WILL BE 2ND HOUSE ON RD | Thu, Apr 01, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES RAINEY | R1 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 120.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 51.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 1.5 gpm for 4.0 hrs.
*Drawdown:* ft. | *Static water level:* 25.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE | *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 31 | *Topo map:* BEDFORD WEST
*Field located by:* JVH | *on:* Mon, Aug 01, 1966
*Courthouse location by:* | *on:*
*Location accepted w/o verification by:* | *on:*
*Subdivision name:* | *Lot number:*
*Ft W of EL:* 1900 | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* 1100
*Ground elevation:* 520.0 | *Depth to bedrock:* 50.0 | *Bedrock elevation:* 470.0 | *Aquifer elevation:*
*UTM Easting:* 538147.0 | *UTM Northing:* 4297646.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 35.0 | BLUE CLAY |
| 35.0 | 48.0 | YEL CLAY |
| 48.0 | 75.0 | WHITE LIME SOFT |
| 75.0 | 120.0 | VERY HARD LIME |

*Comments*: MC470

# Record of Water Well

132

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217939** | FROM FAYETTESVILLE GO S TO SR450 TURN R, 1ST HOUSE TRAILER ON L. | Sat, May 04, 1968 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | HENRY ACTON | R#1, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 70.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 47.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 10.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 30 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Wed, Aug 18, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 200 *Ft E of WL:* 50 *Ft S of NL:*
*Ground elevation:* 570.0 *Depth to bedrock:* 45.0 *Bedrock elevation:* 525.0 *Aquifier elevation:*
*UTM Easting:* 537068.0 *UTM Northing:* 4298042.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 45.0 | CLAY |
| 45.0 | 50.0 | SHELL |
| 50.0 | 60.0 | LIME |
| 60.0 | 63.0 | SHELL |
| 63.0 | 65.0 | LIME |
| 65.0 | 70.0 | SHELL |

*Comments* MC 525; MAILBOX VERIFICATION;

133

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217944** | FROM BEDFORD GOING W ON 450 LAST FARM BEFORE CROSSING SALT CK BRIDGE | Sat, May 02, 1970 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | FRANK JACKSON | | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD, IN | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 22.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 3.0 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 95.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 29 — *Topo map:* BEDFORD WEST
*Field located by:* PW — *on:* Tue, Aug 17, 1971
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 2200 — *Ft E of WL:* 1950 — *Ft S of NL:*
*Ground elevation:* 580.0 — *Depth to bedrock:* 18.0 — *Bedrock elevation:* 562.0 — *Aquifer elevation:*
*UTM Easting:* 539335.0 — *UTM Northing:* 4298676.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | CLAY |
| 18.0 | 20.0 | SHELL |
| 20.0 | 45.0 | LIME |
| 45.0 | 101.0 | MED LIME |
| 101.0 | 103.0 | SS |
| 103.0 | 140.0 | LIME |

***Comments*** MC560; VERIFIED BY NEIGHBOPage 966

134

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220882** | 3 S OF BEDFORD IN, ON VINEGAR HILL RD. | Tue, Mar 06, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | KENNETH DAY | RR#5, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 26.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the NW 1/4 of the SE 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1800 *Ft N of SL:* 1700 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 660.0 *Depth to bedrock:* 25.0 *Bedrock elevation:* 635.0 *Aquifier elevation:*
*UTM Easting:* 546173.0 *UTM Northing:* 4297032.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 23.0 | DIRT |
| 23.0 | 50.0 | WH LS SOFT |
| 50.0 | 73.0 | GRAY LS SOFT |
| 73.0 | 100.0 | BLUE LS HARD |

***Comments*** MC 635

# Record of Water Well

135

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220887** | 2.75 MI S OF BEDFORD ON I ST. | Tue, Mar 09, 1965 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | WALTER WOODWARD | R1, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 105.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 20.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 80.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the NW 1/4 of the SE 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*

| | | | |
|---|---|---|---|
| *Ft W of EL:* 1800 | *Ft N of SL:* 1500 | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* 650.0 | *Depth to bedrock:* 15.0 | *Bedrock elevation:* 635.0 | *Aquifer elevation:* |
| *UTM Easting:* 546173.0 | | *UTM Northing:* 4296965.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 17.0 | DIRT |
| 17.0 | 33.0 | BLUE LS HARD |
| 33.0 | 40.0 | GRAY LS HARD |
| 40.0 | 74.0 | WH LS SOFT |
| 74.0 | 88.0 | GRAY LS HARD |
| 88.0 | 94.0 | BR LS HARD |
| 94.0 | 105.0 | BLUE LS HARD |

*Comments* MC 635;

# Record of Water Well

136

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220892** | 3 MI S, S ON AIRPORT RD, 1 MI W ON BLK TIP RD. BEDFORD IN. | Fri, Mar 18, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | I.L. EDWARDS | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | KING WELL DRLG | DILLSBORO IN, RR1 | |
| Equipment Operator | JACK KING | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 35.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 6.75 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 98.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the NE 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 900 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 300
*Ground elevation:* 685.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 546459.0 *UTM Northing:* 4298013.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | NO INFORMATION |

*Comments*

137

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220897** | S OF BLOOMINGTON ON SR37 TO BEDFORD. E TO PALEISTINE RD TO SUNNY ACRES DR, E ON SE CORNER. | Sat, Feb 20, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DONALD PIPER | 611 T ST, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | WILLARD ENGLISH & SONS | CLAYTON IN, RR1 | |
| Equipment Operator | LEON ENGLISH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 112.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 22.0 | *Material:* | *Diameter:* 6.5 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2000 *Ft S of NL:* 300
*Ground elevation:* 650.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 630.0 *Aquifier elevation:*
*UTM Easting:* 545758.0 *UTM Northing:* 4298025.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | CLAY YEL |
| 22.0 | 91.0 | LS BLUE |
| 91.0 | 102.0 | LS BR |
| 102.0 | 112.0 | LS BLUE |

*Comments* MC 630;

138

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220902** | APPRX 3MI S OF BEDFORD IN, ON THE PALESTINE RD.ABOUT 400' S ON PALESTINE RD FROM THE VINIGAR HILL, PALESTINE CROSS RDS. | Tue, Jul 23, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LOUIE E. JOHNSON | 1410 HILLCRES RD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 111.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 71.0 ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* NW 1/4 of the NW 1/4 of the SE 1/4 of Section 36 *Topo map:* BEDFORD EAST

*Field located by:* JCH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 2000 *Ft N of SL:* 2500 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 675.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 665.0 *Aquifier elevation:*

*UTM Easting:* 546112.0 *UTM Northing:* 4297276.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | DIRT |
| 12.0 | 34.0 | GRAY LS HARD |
| 34.0 | 68.0 | BLUE LS HARD |
| 68.0 | 101.0 | GRAY LS SOFT |
| 101.0 | 111.0 | BLUE LS HARD |

*Comments* MC 665;

139

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220907** | 2 MI S OF BEDFORD TO POOR FARM RD, NOW CR200S. E 300', S 70'. | Sat, Jul 20, 1968 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | BOB BURKHART | RR#5, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD IN | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 106.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 25.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 13.0 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 46.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 36 — *Topo map:* BEDFORD EAST
*Field located by:* PW — *on:* Mon, Aug 16, 1971
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* 2100 — *Ft S of NL:* 100
*Ground elevation:* 650.0 — *Depth to bedrock:* 22.0 — *Bedrock elevation:* 628.0 — *Aquifer elevation:*
*UTM Easting:* 545794.0 — *UTM Northing:* 4298074.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | DIRT |
| 22.0 | 32.0 | GRAY LS HARD |
| 32.0 | 70.0 | BLUE LS HARD |
| 70.0 | 85.0 | WH LS SOFT |
| 85.0 | 106.0 | BLUE LS SOFT |

***Comments*** MC 630; MAILBOX VERIFICATION;

140

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220912** | 3 MI S OF BEDFORD IN, ON VINIGAR HILL RD. 250S?UCH. | Wed, Jul 24, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LLOYD CRAIG | RR5, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD IN | |
| Equipment Operator | CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 133.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 26.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.6 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 53.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* PW *on:* Mon, Aug 16, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2350 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1500
*Ground elevation:* 680.0 *Depth to bedrock:* 23.0 *Bedrock elevation:* 657.0 *Aquifier elevation:*
*UTM Easting:* 546020.0 *UTM Northing:* 4297324.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 23.0 | DIRT |
| 23.0 | 70.0 | WH LS SOFT |
| 70.0 | 76.0 | BLUE LS HARD |
| 76.0 | 105.0 | GRAY LS SOFT |
| 105.0 | 133.0 | WH LS HARD |

***Comments***

MC 655; VERIFIED BY NEIGHBOR;

141

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220917** | RR5 | Sat, Apr 02, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | | | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR4, BEDFORD IN | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 120.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 24.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the NE 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Sun, Jul 01, 1962
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2250 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 200
*Ground elevation:* 670.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 546044.0 *UTM Northing:* 4298044.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 24.0 | CLAY |
| 24.0 | 120.0 | LS |

***Comments***

# Record of Water Well

142

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220922** | IN BEDFORD, S ON I ST PAST POOR FARM RD TO THE 1ST RD, THEN EAST TO THE 1ST RD AND NORTH ON THE EAST SIDE OF RD | Thu, Aug 12, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHN SCOGGINS | 1905 14TH ST., BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | WILLARD ENGLISH & SON | RR1 CLAYTON, IN | |
| Equipment Operator | LEON ENGLISH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 130.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.5 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 20.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 30.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* NE 1/4 of the NE 1/4 of the NE 1/4 of Section 36 *Topo map:* BEDFORD EAST

*Field located by:* JVH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 100

*Ground elevation:* 690.0 *Depth to bedrock:* 25.0 *Bedrock elevation:* 665.0 *Aquifier elevation:*

*UTM Easting:* 546690.0 *UTM Northing:* 4298087.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 27.0 | CLAY YEL |
| 27.0 | 130.0 | LS |

*Comments* MC665

143

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220927** | 2 BLKS E OF PALESTINE RD & 2 BLKS N OF VINEGAR HILL RD. | Tue, Aug 01, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT C. NILSON | 1708 7TH ST, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | | |
| Equipment Operator | CHARLES | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 118.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 10.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 48.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* PW *on:* Mon, Aug 16, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1300 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2000
*Ground elevation:* 690.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 670.0 *Aquifer elevation:*
*UTM Easting:* 546343.0 *UTM Northing:* 4297501.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | DIRT |
| 20.0 | 30.0 | BLUE LIME HARD |
| 30.0 | 80.0 | WH LIME HARD |
| 80.0 | 118.0 | WH LIME SOFT |

*Comments* MC 670; VERIFIED BY MAILBOX;

14H

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220932** | SUNNY ACRES DR, SO OF BEDFORD. | Thu, Jun 25, 1964 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | JACK BYREN | 1630 25ST, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR4, BEDFORD IN | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 105.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.0 | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* PUMPING *Test rate:* 10.0 gpm for 8.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 36 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2200 *Ft S of NL:* 700
*Ground elevation:* 665.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 545813.0 *UTM Northing:* 4297909.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | CLAY |
| 28.0 | 105.0 | LS |

*Comments* MC 665Page 9789

145

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220937** | POOR FARM RD. | Fri, May 20, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | VADA H. HAWKINS | RR5, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR4, BEDFORD IN | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 110.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.3 gpm for 8.0 hrs.
*Drawdown:* ft. — *Static water level:* 40.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 36 — *Topo map:* BEDFORD EAST
*Field located by:* BARNES — *on:* Fri, Jul 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 3000 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 700
*Ground elevation:* 670.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* 545813.0 — *UTM Northing:* 4297909.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | CLAY |
| 6.0 | 10.0 | SOFT LS |

***Comments***

146

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220942** | 3 MI S OF BEDFORD, IN ON PALESTINE RD | Thu, Sep 19, 1963 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | G. BROWN | R1 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BOX 13, BEDFORD, IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 113.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 47.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 58.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* NE 1/4 of the SW 1/4 of the SE 1/4 of Section 36 *Topo map:* BEDFORD EAST

*Field located by:* JVH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 1600 *Ft N of SL:* 1200 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 660.0 *Depth to bedrock:* 45.0 *Bedrock elevation:* 615.0 *Aquifier elevation:*

*UTM Easting:* 546246.0 *UTM Northing:* 4296879.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | DIRT |
| 12.0 | 44.0 | BOULDERS & MUD HOLES |
| 44.0 | 69.0 | BLUE LS HARD |
| 69.0 | 90.0 | GRAY LS HARD |
| 90.0 | 113.0 | WHITE LS HARD |

*Comments* MC615

147

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220947** | ON SANDPIT RD JUST E OF MONAN RR AP. 3 MI SW OF BEDFORD, IN S ACROSS | Mon, Jul 27, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | J.W. HAWKINS | RR1 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BOX 13, BEDFORD, IN | |
| Equipment Operator | B. ERIE | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* OTHER | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 78.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 40.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NW 1/4 of Section 35 — *Topo map:* BEDFORD EAST
*Field located by:* BARNES — *on:* Fri, Jul 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 520.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* 543661.0 — *UTM Northing:* 4297372.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 21.0 | SAND RED |
| 21.0 | 40.0 | BLUE MUCK |
| 40.0 | 64.0 | BROWN MCUK |
| 64.0 | 68.0 | BROWN LIME |
| 68.0 | 78.0 | SAND & SHALE |

***Comments*** MC460

148

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220952** | 3 MI S OF BEDFORD ON SAND PIT RD. | Tue, Aug 22, 1961 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | GLEN HOPKIN | RR1, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 176.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 35 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 100 *Ft E of WL:* 400 *Ft S of NL:*
*Ground elevation:* 600.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 580.0 *Aquifer elevation:*
*UTM Easting:* 543655.0 *UTM Northing:* 4296531.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | DIRT |
| 22.0 | 27.0 | LS BOLDER |
| 27.0 | 75.0 | BR LS |
| 75.0 | 80.0 | BLUE LS |
| 80.0 | 83.0 | BLUE SHALE SHALE SOFT |
| 83.0 | 167.0 | BR LS |
| 167.0 | 176.0 | BLUE SHALE |

*Comments* MC 580;

# Record of Water Well

149

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **317715** | 2 MI W OF BEDFORD, ON 450, RT SD OF RD | Thu, May 28, 1998 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | KIM JACKSON | RR BOX 1695, BEDFORD, IN 47421 | |
| Building Contractor | | | |
| Drilling Contractor | S&S DRILLING INC. | R1 BOX 507, MONTGOMERY, IN 47558 | |
| Equipment Operator | DEXTER SWARTZENTRUBER | License: 302 | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 103.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* PVC | *Diameter:* 6.0 |
| Screen | *Length:* 80.0 | *Material:* PVC | *Diameter:* 4.5 *Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* 10.0 gpm for hrs. *BailTest rate:* gpm for hrs.

*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* BNSL *Depth:* from 30.0 to 0.0

*Installation Method:* PUMP *Number of bags used:* 2.0

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* 1/4 of the 1/4 of the NE 1/4 of Section 30 *Topo map:* BEDFORD WEST

*Field located by:* *on:*

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*

*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | CLAY |
| 3.0 | 25.0 | BRKN LIME |
| 25.0 | 62.0 | LIME |
| 62.0 | 64.0 | CLAY |
| 64.0 | 103.0 | SANDY LIME |

***Comments***

# Record of Water Well

150

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217925** | FROM BEDFORD GO W ON 16TH ST TO 450. GO APROX 2 MI. OLDER FARM HOUSE ON L SIDE. LAST HOUSE BEFORE RANCH IN SALT CREEK BRIDGE. | Sat, Dec 15, 1979 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BRIDWELL ESTATE | R#11, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | CARROLL SHIELDS | R#4, MITCHELL IN | |
| Equipment Operator | CARROLL SHIELDS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 31.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 2.0 gpm for 2.0 hrs.
*Drawdown:* ft. — *Static water level:* 110.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SE 1/4 of the SE 1/4 of Section 20 — *Topo map:* BEDFORD WEST
*Field located by:* PES — *on:* Thu, Jul 31, 1980
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 700 — *Ft N of SL:* 300 — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 628.0 — *Depth to bedrock:* 31.0 — *Bedrock elevation:* 597.0 — *Aquifer elevation:*
*UTM Easting:* 540134.0 — *UTM Northing:* 4299700.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 31.0 | CLAY |
| 31.0 | 150.0 | SOFT LIME |

***Comments*** MC 597; VERIFIED BY NEIGHBOR & MAILBOX;

151

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217945** | FROM FAYETTESVILLE GO S ABOUT 2MI, TURN L AT 2ND RD GO ABOUT 1 MI. TURN L 1ST HOUSE ON L. | Mon, Dec 11, 1967 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | DANNIE GOENS | RR, WILLIAMS | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIS O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 22.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 2.0 hrs.

*Drawdown:* ft. *Static water level:* 55.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 19 *Topo map:* BEDFORD WEST

*Field located by:* PW *on:* Wed, Aug 18, 1971

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* 850 *Ft E of WL:* 1400 *Ft S of NL:*

*Ground elevation:* 600.0 *Depth to bedrock:* 21.0 *Bedrock elevation:* 579.0 *Aquifer elevation:*

*UTM Easting:* 537519.0 *UTM Northing:* 4299865.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 19.0 | CLAY |
| 19.0 | 21.0 | BLANK |
| 21.0 | 22.0 | LIME |
| 22.0 | 26.0 | SHELL |
| 26.0 | 45.0 | SOFT LIME |
| 45.0 | 55.0 | BROKEN |
| 55.0 | 60.0 | MD LIME |
| 60.0 | 75.0 | HARD LIME |
| 75.0 | 135.0 | BR LIME |
| 135.0 | 150.0 | GRAY LIME |

*Comments* MC 580; VERIFIED BY OWNER;

# Record of Water Well

152

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217930** | FROM BEDFORD GOING WEST ON 450 CROSS SALT CREEK 1ST RD TO RIGHT 7TH HOUSE ON RIGHT | Mon, May 15, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOE NORDHOFF | 2704 W 16TH ST., BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 180.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 100.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 19 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Wed, Aug 18, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1000 *Ft E of WL:* 1600 *Ft S of NL:*
*Ground elevation:* 600.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 580.0 *Aquifer elevation:*
*UTM Easting:* 537525.0 *UTM Northing:* 4299907.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 28.0 | LIME |
| 28.0 | 40.0 | SOFT LIME |
| 40.0 | 48.0 | LIME |
| 48.0 | 49.0 | SHELL |
| 49.0 | 60.0 | LIME |
| 60.0 | 62.0 | HARD LIME |
| 62.0 | 63.0 | SOFT LIME |
| 63.0 | 64.0 | BLANK |
| 64.0 | 68.0 | LIME |
| 68.0 | 71.0 | SHELL |
| 71.0 | 180.0 | LIME |

*Comments* MS-580, VERIFIED BY OWNER

153

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217935** | FROM BEDFORD GOING W TURN LEFT ON 450 CROSS SALT CREEK TURN 1ST RD RIGHT GO .5 MI TURN RIGHT 4TH HOUSE ON LEFT | Mon, Oct 07, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DONNIE NORDHOFF | | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 199.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 38.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 8.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 99.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 19 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Wed, Aug 18, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1300 *Ft E of WL:* 1250 *Ft S of NL:*
*Ground elevation:* 610.0 *Depth to bedrock:* 35.0 *Bedrock elevation:* 575.0 *Aquifer elevation:*
*UTM Easting:* 537446.0 *UTM Northing:* 4299993.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 35.0 | CLAY |
| 35.0 | 40.0 | LIME |
| 40.0 | 150.0 | HARD LIME |
| 150.0 | 199.0 | MED LIME |

*Comments* MC575: VERIFIED BY OWNER

# Record of Water Well

154

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217940** | FROM BEDFORD GO WEST APPROX 1 MI TURN LEFT ON 450 CROSS SALT CREEK TURN RIGHT 1ST RD APPROX 1 MI TURN RIGHT. LAST NEW HOUSE ON LEFT | Wed, Jun 19, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DONNIE NORDHOFF | BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 170.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 35.0 | ***Material:*** | ***Diameter:*** 6.25 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 1.0 gpm for 2.0 hrs.
***Drawdown:*** ft. ***Static water level:*** 70.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1W
***Section:*** SE 1/4 of the NW 1/4 of the SW 1/4 of Section 19 ***Topo map:*** BEDFORD WEST
***Field located by:*** PW ***on:*** Wed, Aug 18, 1971
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** 1450 ***Ft E of WL:*** 1150 ***Ft S of NL:***
***Ground elevation:*** 600.0 ***Depth to bedrock:*** 32.0 ***Bedrock elevation:*** 568.0 ***Aquifier elevation:***
***UTM Easting:*** 537409.0 ***UTM Northing:*** 4300035.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 32.0 | CLAY |
| 32.0 | 45.0 | BLUE LIME |
| 45.0 | 66.0 | LIME |
| 66.0 | 67.0 | SHELL |
| 67.0 | 75.0 | MED LIME |
| 75.0 | 95.0 | HARD LIME |
| 95.0 | 114.0 | MED LIME |
| 114.0 | 122.0 | SOFT LIME |
| 122.0 | 135.0 | MED LIME |
| 135.0 | 152.0 | BROWN LIME |
| 152.0 | 155.0 | HARD LIME |
| 155.0 | 170.0 | MED LIME |

***Comments*** MC570; VERIFIED BY OWNER

155

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217950** | FROM BEDFORD GOING WEST ON 450 GO APPROX 5 MI CROSS SALT CREEK 1ST RD ON RIGHT. 9TH HOUSE ON RIGHT ON THIS ROAD | Fri, Mar 10, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | J. NORDHOFF | | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD, IN | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 160.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 46.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 77.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 19 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Wed, Aug 18, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1300 *Ft E of WL:* 1550 *Ft S of NL:*
*Ground elevation:* 600.0 *Depth to bedrock:* 45.0 *Bedrock elevation:* 555.0 *Aquifier elevation:*
*UTM Easting:* 537525.0 *UTM Northing:* 4299986.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 40.0 | CLAY |
| 40.0 | 50.0 | SOFT LIME |
| 50.0 | 55.0 | HARD LIME |
| 55.0 | 60.0 | MED LIME |
| 60.0 | 66.0 | HARD LIME |
| 66.0 | 67.0 | BLUE SHELL |
| 67.0 | 70.0 | HARD LIME |
| 70.0 | 77.0 | SHELL & LIME |
| 77.0 | 160.0 | LIME |

***Comments*** MC555; VERIFIED BY OWNER

# Record of Water Well

156

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217955** | FROM BEDFORD TURN LEFT ON 450 TURN RIGHT 1ST RD TO RIGHT AFTER CROSSING SALT CREEK GO .5 MI TURN RIGHT 3RD NEW HOUSE ON LEFT (W/STONE FRONT) | Wed, Nov 20, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | TOM NORDHOFF | BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 204.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 73.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 114.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 19 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Tue, Aug 18, 1970
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1200 *Ft E of WL:* 1300 *Ft S of NL:*
*Ground elevation:* 610.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 590.0 *Aquifer elevation:*
*UTM Easting:* 537464.0 *UTM Northing:* 4429968.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 39.0 | BROKEN |
| 39.0 | 62.0 | LIME |
| 62.0 | 63.0 | SEAM |
| 63.0 | 69.0 | LIME |
| 69.0 | 70.0 | SEAM |
| 70.0 | 75.0 | BROKEN |
| 75.0 | 85.0 | HARD LIME |
| 85.0 | 145.0 | MED LIME |
| 145.0 | 160.0 | BROWN LIME |
| 160.0 | 205.0 | WHITE LIME |

***Comments*** MC590 [illegible] REPORTED BY OWNER

# Record of Water Well

157

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217960** | FROM FAYETTEVILLE GOING S ABOUT 2MI. WELL BE 2 RDS, TURN OFF ABOUT SAME TIME, TURN 2ND Y. TURN 1ST RD L 2ND HOUSE. | Sat, Mar 30, 1968 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DONNIE NORDHOFF | BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIE SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 185.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 24.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 135.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 19 *Topo map:* BEDFORD WEST
*Field located by:* PW *on:* Wed, Aug 18, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1000 *Ft E of WL:* 1350 *Ft S of NL:*
*Ground elevation:* 600.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 585.0 *Aquifer elevation:*
*UTM Easting:* 537470.0 *UTM Northing:* 4299913.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 15.0 | CLAY |
| 15.0 | 20.0 | SHELL |
| 20.0 | 35.0 | SOFT LIME |
| 35.0 | 65.0 | MD LIME |
| 65.0 | 78.0 | HARD LIME |
| 78.0 | 165.0 | MD LIME |
| 165.0 | 185.0 | MD SOFT LIME GRAY |

*Comments* MC 585; VERIFIED BY OWNER;

158

# Record of Water Well

Indiana Department of Natural Resources

| | | | |
|---|---|---|---|
| ***Reference Number*** **220859** | ***Driving directions to well*** EUREKA IN. | | ***Date completed*** Tue, Oct 20, 1964 |
| ***Owner-Contractor*** | ***Name*** | ***Address*** | ***Telephone*** |
| Well Owner | JAMES E. TERRY | 1507 2ND ST | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOS 13, BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 91.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 39.5 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 48.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1W
***Section:*** NE 1/4 of the NE 1/4 of the NW 1/4 of Section 18 ***Topo map:*** BEDFORD WEST
***Field located by:*** JCH ***on:*** Mon, Aug 01, 1966
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** 4900 ***Ft E of WL:*** 2450 ***Ft S of NL:***
***Ground elevation:*** 650.0 ***Depth to bedrock:*** 35.0 ***Bedrock elevation:*** 615.0 ***Aquifer elevation:***
***UTM Easting:*** 537823.0 ***UTM Northing:*** 4302687.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 29.0 | DIRT |
| 29.0 | 34.0 | BOULDERS & MUD HOLES |
| 34.0 | 67.0 | BLUE LS SOFT |
| 67.0 | 73.0 | GRAY LS HARD |
| 73.0 | 91.0 | BLUE LS HARD |

***Comments*** MC 615:

159

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220864** | WEST EDGE OF EUREKA, IN | Wed, Sep 26, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES KILLIAN | RR2 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BEDFORD, IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 93.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 51.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 21.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SE 1/4 of the NW 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 3300 *Ft E of WL:* 1600 *Ft S of NL:*
*Ground elevation:* 625.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 537543.0 *UTM Northing:* 4302151.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 31.0 | DIRT |
| 31.0 | 47.0 | MUD HOLES & BOULDERS |
| 47.0 | 58.0 | BLUE LS HARD |
| 58.0 | 83.0 | GRAY LS HARD |
| 83.0 | 93.0 | BLUE LS HARD |

*Comments*

# Record of Water Well

160

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220869** | ON SR 158 W OF EUREKA ABOUT .5 MI. | Fri, Oct 30, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | KERMIT WILLIAMS | RR2, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOS 13, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 41.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.92 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 80.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SE 1/4 of the NW 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* BAINS *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2600 *Ft E of WL:* 1550 *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 537555.0 *UTM Northing:* 4302004.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 35.0 | DIRT & FLINT ROCK |
| 35.0 | 40.0 | SOFT BLUE SHALE |
| 40.0 | 75.0 | WH LIME |
| 75.0 | 80.0 | EXTRA SOFT SHALE |
| 80.0 | 100.0 | HARD BLUE SHALE |
| 100.0 | 125.0 | BUFF LIME STONE |

*Comments* MC;

# Record of Water Well

161

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220874** | NW CORNER OF SAID QUARTER SECTION. S OF LEESVILLE GRAVE RD 18 POLES AND 17 LINKS 2.5 MI EAST OF BEDFORD, IN | Wed, Dec 14, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | FLOYD WEVER | 446 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BOX 13, BEDFORD, IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 8.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.22 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 42.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the SE 1/4 of Section 18 *Topo map:* BEDFORD EAST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2300 *Ft N of SL:* 100 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 660.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 655.0 *Aquifer elevation:*
*UTM Easting:* 538037.0 *UTM Northing:* 4301212.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 40.0 | WHITE LS HARD |
| 40.0 | 65.0 | BLUE LS HARD |
| 65.0 | 83.0 | WHITE LS HARD |
| 83.0 | 100.0 | BLUE SHALE |

***Comments***

162

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220879** | APP 1 MI E OF NEDFORD IN | Tue, Aug 06, 1963 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | GLENN D. WOODY | RR#6, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 100.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the SE 1/4 of Section 18 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1200 *Ft N of SL:* 1900 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 560.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 555.0 *Aquifier elevation:*
*UTM Easting:* 538360.0 *UTM Northing:* 4301779.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 2.5 | DIRT |
| 2.5 | 23.0 | BLUE LS HARD |
| 23.0 | 51.0 | GRAY LS HARD |
| 51.0 | 70.0 | WH LS HARD |
| 70.0 | 103.0 | BLUE LS HARD |
| 103.0 | 200.0 | BLUE SHALE SOFT |

*Comments*

# Record of Water Well

163

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220884** | .25 MI N OF EUREKA IN. TRAILE. | Sat, Jul 25, 1964 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | RONNIE WALLCOTT | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | EUGENE & CHARLES UMPHRESS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 151.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 52.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2650 *Ft N of SL:* 4700 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 610.0 *Aquifer elevation:*
*UTM Easting:* 537927.0 *UTM Northing:* 4302614.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | DIRT |
| 18.0 | 44.0 | LS BOULDERS & MUD HOLES |
| 44.0 | 57.0 | BLUE LS SOFT |
| 57.0 | 73.0 | GRAY LS SOFT |
| 73.0 | 86.0 | BLUE LS HARD |
| 86.0 | 134.0 | GRAY LS SOFT |
| 134.0 | 151.0 | WH LS SOFT |

*Comments* MC 610;

# Record of Water Well

164

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220889** | EUREKA IN, S SIDE OF RD. | Mon, Sep 13, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES MOSIER | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 137.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 35.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.75 gpm for hrs.

*Drawdown:* ft. *Static water level:* 20.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* NE 1/4 of the SE 1/4 of the NW 1/4 of Section 18 *Topo map:* BEDFORD WEST

*Field located by:* JCH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* 3500 *Ft E of WL:* 2400 *Ft S of NL:*

*Ground elevation:* 620.0 *Depth to bedrock:* 25.0 *Bedrock elevation:* 595.0 *Aquifier elevation:*

*UTM Easting:* 537811.0 *UTM Northing:* 4302236.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 24.0 | DIRT |
| 24.0 | 27.0 | BROKEN LS SOFT |
| 27.0 | 33.0 | GRAY LS HARD |
| 33.0 | 64.0 | BLUE LS SOFT |
| 64.0 | 67.0 | BROKEN LS SOFT |
| 67.0 | 89.0 | BLUE LS HARD |
| 89.0 | 108.0 | GRAY LS SOFT |
| 108.0 | 124.0 | BR LS SOFT |
| 124.0 | 137.0 | WH LS SOFT |

*Comments* MC 595;

# Record of Water Well

165

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220894** | EUREKA IN. | Fri, Feb 10, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES TERRY | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 90.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 49.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 4.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 65.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W

*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 18 *Topo map:* BEDFORD WEST

*Field located by:* PW *on:* Tue, Aug 17, 1971

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 2150 *Ft N of SL:* 3950 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 625.0 *Depth to bedrock:* 39.0 *Bedrock elevation:* 586.0 *Aquifier elevation:*

*UTM Easting:* 538073.0 *UTM Northing:* 4302407.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | DIRT |
| 30.0 | 39.0 | BOULDERS & MUD HOLES |
| 39.0 | 68.0 | BLUE LS SOFT |
| 68.0 | 75.0 | GRAY LS HARD |
| 75.0 | 90.0 | BLUE LS HARD |

*Comments* MC 585; VERIFIED BY NEIGHBOR;

# Record of Water Well

1666

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220899** | FROM BEDFORD GO WEST APPROX. 5MI ON 158, ACROSS RD FROM NEW UNION CHRISTIAN CHURCH | Thu, Mar 18, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAKE MULLIS | R2 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 205.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 35.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for 4.0 hrs.
*Drawdown:* ft. *Static water level:* 120.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the NE 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 800 *Ft N of SL:* 4100 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 650.0 *Depth to bedrock:* 30.0 *Bedrock elevation:* 620.0 *Aquifier elevation:*
*UTM Easting:* 538494.0 *UTM Northing:* 4302443.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | CLAY |
| 30.0 | 70.0 | BROWN LIME |
| 70.0 | 90.0 | GRAY LIME |
| 90.0 | 120.0 | LIGHT GRAY |
| 120.0 | 155.0 | DARK LIME |
| 155.0 | 202.0 | WHITE LIME |
| 202.0 | 205.0 | HARD LIME |

*Comments* MC620

# Record of Water Well

167

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220904** | APPROX 5 MI W OF BEDFORD TURN RIGHT AT EUREKA 1ST TRAILER ON RIGHT | Mon, Jun 21, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LESLIE GRISSOM | R2 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R1 BEDFORD | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 187.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 36.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.5 gpm for 3.0 hrs.
*Drawdown:* ft. *Static water level:* 87.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the NE 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2500 *Ft N of SL:* 4600 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* 35.0 *Bedrock elevation:* 595.0 *Aquifier elevation:*
*UTM Easting:* 537933.0 *UTM Northing:* 4302541.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 35.0 | CLAY |
| 35.0 | 40.0 | SOFT LIME |
| 40.0 | 42.0 | GRAY LIME |
| 42.0 | 63.0 | BROWN LIME |
| 63.0 | 64.0 | BLANK |
| 64.0 | 68.0 | HARD LIME |
| 68.0 | 71.0 | SHELL |
| 71.0 | 74.0 | LIME |
| 74.0 | 77.0 | SHELL |
| 77.0 | 90.0 | HARD LIME |
| 90.0 | 140.0 | WHITE LIME |
| 140.0 | 185.0 | GRAY LIME |
| 185.0 | 188.0 | HARD LIME |

*Comments* MC

168

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220919** | APP 3 MI W OF BEDFORD IN ON SR450, S SIDE OF RD. | Fri, Nov 19, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES E. HILLENBURG | RR2, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 137.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 42.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SW 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2400 *Ft E of WL:* 1600 *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 615.0 *Aquifier elevation:*
*UTM Easting:* 537531.0 *UTM Northing:* 4301931.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 7.0 | DIRT |
| 7.0 | 15.0 | BOULDERS & MUD HOLES |
| 15.0 | 34.0 | GRAY LS HARD |
| 34.0 | 48.0 | WH LS SOFT |
| 48.0 | 60.0 | BLUE LS SOFT |
| 60.0 | 96.0 | BR LS SOFT |
| 96.0 | 112.0 | GRAY LS SOFT |
| 112.0 | 137.0 | BLUE LS HARD |

***Comments*** MC 615;

169

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220924** | APP 2.5 MI W OF BEDFORD IN. | Tue, Jan 28, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ELIZABETH DONALDSON | BEDFORD IN, RR2 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.08 gpm for hrs.
*Drawdown:* ft. *Static water level:* 70.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the SE 1/4 of Section 17 *Topo map:* BEDFORD WEST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2600 *Ft N of SL:* 2500 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 610.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 590.0 *Aquifier elevation:*
*UTM Easting:* 539530.0 *UTM Northing:* 4301974.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | DIRT |
| 12.0 | 20.0 | BROKEN LS & BOULDERS |
| 20.0 | 63.0 | BLUE LS HARD |
| 63.0 | 71.0 | GRAY LS SOFT |
| 71.0 | 77.0 | BLUE LS HARD |
| 77.0 | 118.0 | WH LS SOFT |
| 118.0 | 132.0 | GRAY LS HARD |
| 132.0 | 140.0 | BLUE LS HARD |

***Comments*** MC 590:

170

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220929** | 100' SW OF TILE BLOCK CHICKEN HOUSE. WEST OF BEDFORD ON 450, WEST OF NEW BRIDGE ON FAYETTE RD | Thu, Nov 16, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HUGH SCHENSCHEL | RR2 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IN RR6 | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.75 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 55.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the NE 1/4 of Section 17 *Topo map:* BEDFORD WEST
*Field located by:* *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2200 *Ft N of SL:* 3500 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 560.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 539652.0 *UTM Northing:* 4302272.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 23.0 | DIRT |
| 23.0 | 30.0 | BLUE LS HARD |
| 30.0 | 40.0 | GRAY LS HARD |
| 40.0 | 62.0 | BROWN LS SOFT |
| 62.0 | 68.0 | BROKEN LS SOFT |
| 68.0 | 125.0 | BLUE LS HARD |
| 125.0 | 140.0 | BLUE LS SOFT |
| 140.0 | 163.0 | WHITE LS HARD |
| 163.0 | 175.0 | BLUE SHALE SOFT |

*Comments* BROTHER VERIFIED

171

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220934** | ON THE N SIDE OF SR 158 APROX 1300' W OF JCT WITH SR458. | Sat, Oct 03, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | O. COOPER MILLER | RR#2, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLE UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 150.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 43.5 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

| | | | |
|---|---|---|---|
| ***Well Capacity Test*** | ***Type of test:*** | ***Test rate:*** gpm for hrs. | ***BailTest rate:*** 1.0 gpm for hrs. |
| | ***Drawdown:*** ft. | ***Static water level:*** 30.0 ft. | |

| | | |
|---|---|---|
| ***Grouting Information*** | ***Material:*** | ***Depth:*** from to |
| | ***Installation Method:*** | ***Number of bags used:*** |

| | | |
|---|---|---|
| ***Well Abandonment*** | ***Sealing material:*** | ***Depth:*** from to |
| | ***Installation Method:*** | ***Number of bags used:*** |

| | | | | |
|---|---|---|---|---|
| ***Administrative*** | ***County:*** LAWRENCE | | ***Township:*** 5N ***Range:*** 1W | |
| | ***Section:*** NE 1/4 of the NW 1/4 of the NW 1/4 of Section 17 | | | ***Topo map:*** BEDFORD WEST |
| | ***Field located by:*** JCH | | ***on:*** Mon, Aug 01, 1966 | |
| | ***Courthouse location by:*** | | ***on:*** | |
| | ***Location accepted w/o verification by:*** | | ***on:*** | |
| | ***Subdivision name:*** | | ***Lot number:*** | |
| | ***Ft W of EL:*** | ***Ft N of SL:*** 4900 | ***Ft E of WL:*** 1100 | ***Ft S of NL:*** |
| | ***Ground elevation:*** 580.0 | ***Depth to bedrock:*** 20.0 | ***Bedrock elevation:*** 560.0 | ***Aquifier elevation:*** |
| | ***UTM Easting:*** 539067.0 | | ***UTM Northing:*** 4302687.0 | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | DIRT |
| 18.0 | 41.0 | BROKEN LS SOFT |
| 41.0 | 67.0 | GRAY LS HARD |
| 67.0 | 84.0 | BLUE LS HARD |
| 84.0 | 116.0 | BR LS SOFT |
| 116.0 | 150.0 | WH LS SOFT |

***Comments*** MC 560;

172

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220939** | 4 MI WEST OF BEDFORD, IN ON BEDFORD & FAYETTEVILLE RD RT 158; E OF EUREKA | Fri, Feb 12, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | SAM G. MITCHELL | 944 I ST BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BOX 13, BEDFORD, IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* OTHER | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 25.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the NW 1/4 of Section 17 *Topo map:* BEDFORD WEST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 4200 *Ft E of WL:* 1550 *Ft S of NL:*
*Ground elevation:* 560.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 539195.0 *UTM Northing:* 4302492.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | DIRT |
| 22.0 | 70.0 | BLUE LS SOFT |
| 70.0 | 85.0 | WHITE LS HARD |
| 85.0 | 125.0 | BLUE LS HARD |
| 125.0 | 150.0 | WHITE LS HARD |

***Comments*** MC; SEE MAP; WE DRILL THIN WELL IN 5' PIT AND YOU COULD SAY 5' MOREDIRT

173

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220944** | 2 MI W OF BEDFORD ON RR2 SR58 ON FAYETTEVILLE RD & ON S SIDE OF RD. CLOSE TO JCT OF PURDUE FARM RD & FAYETTEVILLE RD. | Tue, Nov 16, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MILO V. MARCHETTI | 1408 20TH, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13,BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 13.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 59.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the NW 1/4 of Section 17 — *Topo map:* BEDFORD WEST
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 5000 — *Ft E of WL:* 1450 — *Ft S of NL:*
*Ground elevation:* 575.0 — *Depth to bedrock:* 5.0 — *Bedrock elevation:* 570.0 — *Aquifier elevation:*
*UTM Easting:* 539177.0 — *UTM Northing:* 4302717.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 33.0 | GRAY LS HARD |
| 33.0 | 60.0 | WH LS SOFT |
| 60.0 | 111.0 | GRAY LS SOFT |
| 111.0 | 117.0 | WH LS SOFT |
| 117.0 | 143.0 | BLUE LS HARD |
| 143.0 | 150.0 | WH LS SOFT |

***Comments*** MC 570.

# Record of Water Well

174

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220846** | FROM BEDFORD GOING W TURN R ON PURDUE TOWN RD. 2ND HOUSE ON L. J. CONERS RES. | Wed, Jan 23, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | VIRGIL ARNEY | R#2, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIS O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIS O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 20.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for 2.0 hrs.
*Drawdown:* ft. — *Static water level:* 43.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 8 — *Topo map:* OOLITIC
*Field located by:* U — *on:* Tue, Oct 01, 1963
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 900 — *Ft E of WL:* 1100 — *Ft S of NL:*
*Ground elevation:* 615.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* 539086.0 — *UTM Northing:* 4303125.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 17.0 | CLAY |
| 17.0 | 60.0 | LIME |
| 60.0 | 120.0 | WH LIME |
| 120.0 | 128.0 | GRAY LIME |

***Comments***

175

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220851** | 3 MI W OF BEDFORD, IN ON DARK HOLLOW RD; ANNA SWANGO ON PURDUE FARM RD | Thu, Nov 09, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ANNA SWANGO | RR2 BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6 BEDFORD, IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 64.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 8 *Topo map:* OOLITIC
*Field located by:* *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1350 *Ft E of WL:* 1400 *Ft S of NL:*
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 539141.0 *UTM Northing:* 4303265.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | DIRT |
| 10.0 | 39.0 | BLUE LS HS |
| 39.0 | 42.0 | MUD SOFT |
| 42.0 | 67.0 | GRAY LS HARD |
| 67.0 | 80.0 | WHITE LS HARD |
| 80.0 | 115.0 | BROWN LS SOFT |
| 115.0 | 150.0 | WHITE LS SOFT |

***Comments*** MC; MAILBOX

176

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220856** | ABOUT .375 MI N OF BEDFORD & FAYETVILLE RD ON SR158. | Tue, Feb 23, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | SAM O'MITCHEL | 944 N I ST, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BOX 13, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for 1.0 hrs. — *Drawdown:* ft. — *Static water level:* 45.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to — *Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W

*Section:* NW 1/4 of the SE 1/4 of the SW 1/4 of Section 8 — *Topo map:* OOLITIC

*Field located by:* S&H — *on:* Tue, Nov 01, 1960

*Courthouse location by:* — *on:*

*Location accepted w/o verification by:* — *on:*

*Subdivision name:* — *Lot number:*

*Ft W of EL:* — *Ft N of SL:* 800 — *Ft E of WL:* 1400 — *Ft S of NL:*

*Ground elevation:* 615.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifer elevation:*

*UTM Easting:* 539128.0 — *UTM Northing:* 4303088.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 25.0 | DIRT |
| 25.0 | 50.0 | WH LS HARD |
| 50.0 | 103.0 | BR LS SOFT |
| 103.0 | 125.0 | WH LS SOFT |
| 125.0 | 140.0 | BLUE LS HARD |

*Comments* MC 590; OFFICE CHAM; FE 0.6 PPM, HARDNESS 335 PPM, PH 7.2, CHLORIDE 6 PPMPage 9784

177

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220861** | FROM BEDFORD GOING W. ON 158 TO PURDUE FARM RD, GO TO 5TH HOUSE ON R. | Thu, Aug 01, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHN BUNDY | RRT. #2, BEDFOR, IN. | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | RRT. #1, BEDFORD, IN. | |
| Equipment Operator | LOUIE O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 5.0 gpm for 2.0 hrs.
*Drawdown:* ft. — *Static water level:* 50.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SW 1/4 of Section 8 — *Topo map:* OOLITIC
*Field located by:* U — *on:* Tue, Oct 01, 1963
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 2600 — *Ft E of WL:* 1200 — *Ft S of NL:*
*Ground elevation:* 655.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifer elevation:*
*UTM Easting:* 539093.0 — *UTM Northing:* 4303631.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 26.0 | RED CLAY |
| 26.0 | 35.0 | LS |
| 35.0 | 37.0 | SOFT LIME |
| 37.0 | 40.0 | WHITE LIME |
| 40.0 | 41.0 | BLANK |
| 41.0 | 45.0 | SHELL |
| 45.0 | 66.0 | BLUE LIME |
| 66.0 | 70.0 | WHITE LIME |
| 70.0 | 105.0 | HARD LIME |
| 105.0 | 145.0 | WHITE BUFF LIME |
| 145.0 | 185.0 | HARD LIME |

*Comments* — MC 600:

178

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220866** | APPROX. 200' E. OF THE PURDUE FARM RD. | Wed, Aug 22, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HARRY & PAULINE KERN | RRT. #2, BEDFOR, IN. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RRT. 6, BEDFORD, IN. | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 148.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 34.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 95.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 8 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1600 *Ft E of WL:* 1480 *Ft S of NL:*
*Ground elevation:* 645.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 539141.0 *UTM Northing:* 4303356.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 27.0 | DIRT |
| 27.0 | 33.0 | GRAY LS-SOFT |
| 33.0 | 45.0 | BLUE LS-SOFT |
| 45.0 | 59.0 | GRAY LS-SOFT |
| 59.0 | 77.0 | BLUE LS-HARD |
| 77.0 | 95.0 | GRAY LS-SOFT |
| 95.0 | 127.0 | BRN LS-SOFT |
| 127.0 | 139.0 | GRAY LS-SOFT |
| 139.0 | 148.0 | WHITE LS-SOFT |

*Comments* MC:

# Record of Water Well

179

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220871** | E OPPOSITE PARDUE FARMS. | Wed, Oct 12, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WM. FITZGERALD | BEDFORD RR 2, IN | |
| Building Contractor | | | |
| Drilling Contractor | ELMER ALFORD | MITCHELL IN | |
| Equipment Operator | ELMER ALFORD | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 160.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.0 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 90.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the NW 1/4 of Section 8 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1200 *Ft S of NL:* 400
*Ground elevation:* 653.0 *Depth to bedrock:* 28.0 *Bedrock elevation:* 625.0 *Aquifier elevation:*
*UTM Easting:* 539094.0 *UTM Northing:* 4304301.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | RED CLAY & BOULDERS |
| 28.0 | 100.0 | GRAY LIME MD |
| 100.0 | 160.0 | WH LIME MD |

***Comments*** MC 625;

180

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220876** | APP 1.5 MI N OF EURKA IN. | Thu, Jul 23, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MICHAEL K. SKEEN | RR#2, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN, RR6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 104.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 9.0 gpm for hrs.
*Drawdown:* ft. | *Static water level:* 40.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE | *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 7 | *Topo map:* OOLITIC
*Field located by:* JCH | *on:* Mon, Aug 01, 1966
*Courthouse location by:* | *on:*
*Location accepted w/o verification by:* | *on:*
*Subdivision name:* | *Lot number:*
*Ft W of EL:* 2500 | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* 100
*Ground elevation:* 650.0 | *Depth to bedrock:* | *Bedrock elevation:* 625.0 | *Aquifer elevation:*
*UTM Easting:* 537941.0 | *UTM Northing:* 4304126.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 27.0 | DIRT |
| 27.0 | 61.0 | BLUE LS HARD |
| 61.0 | 87.0 | GRAY LS SOFT |
| 87.0 | 93.0 | WH LS SOFT |
| 93.0 | 104.0 | BLUE LS HARD |

*Comments* MC 625:

# Record of Water Well

181

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220881** | FROM BEDFORD GOING W. ON 158 APPROX. 5 MI., TURN N ON PENDUE FARM RD. GO 1ST RD TO L., 2ND HOUSE ON L. | Sat, Sep 12, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LESTER COMPTON | RRT. #2, BEDFORD, IN. | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | RRT. #1, BEDFORD, IN. | |
| Equipment Operator | LOUIE O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for 3.0 hrs.
*Drawdown:* ft. *Static water level:* 45.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SE 1/4 of the SE 1/4 of Section 7 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1250 *Ft E of WL:* 2700 *Ft S of NL:*
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* 615.0 *Aquifier elevation:*
*UTM Easting:* 537848.0 *UTM Northing:* 4303218.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 25.0 | CLAY |
| 25.0 | 33.0 | LIME |
| 33.0 | 45.0 | SOFT LIME |
| 45.0 | 47.0 | HARD LIME |
| 47.0 | 53.0 | SOFT LIME |
| 53.0 | 100.0 | MED. LIME |

*Comments* MC 615:

# Record of Water Well

182

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220886** | 279-2161 BOB WAKEFIELD; INDIAN CREEK CAMP | Sat, May 26, 1951 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BAPTIST CONVENTION | WELL #1, AVOC, IN | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR2 MITCHELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 37.0 | *Material:* | *Diameter:* 5.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test* — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 18.0 gpm for 0.5 hrs.
*Drawdown:* ft. — *Static water level:* 52.0 ft.

*Grouting Information* — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Well Abandonment* — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Administrative*

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the SE 1/4 of Section 6 — *Topo map:* OOLITIC
*Field located by:* JRD — *on:* Mon, Aug 09, 1971
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 2500 — *Ft N of SL:* 2400 — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 615.0 — *Depth to bedrock:* 37.0 — *Bedrock elevation:* 578.0 — *Aquifer elevation:*
*UTM Easting:* 537937.0 — *UTM Northing:* 4305181.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | CLAY BOULDERS BROKEN LS |
| 0.0 | 37.0 | OVERBURDEN,CLAY,BLDRS,LS |
| 37.0 | 125.0 | LS |

*Comments* MC578; 50' S OF WHITE TRAILER; TOTAL DRAWDOWN DURING TEST

183

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220891** | .5 MILE W. AVACO, HATCHERY ON AVOCA RD. | Fri, May 20, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BARB KIRKMAN | OVACA, IN. | |
| Building Contractor | | | |
| Drilling Contractor | ELMER ALFORD | RRT. #, MITCHELL, IN. | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 98.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 43.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 10.0 gpm for 0.5 hrs.
*Drawdown:* ft. — *Static water level:* 18.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the NE 1/4 of Section 6 — *Topo map:* OOLITIC
*Field located by:* BARNES — *on:* Fri, Jul 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 950 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 700
*Ground elevation:* 640.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* 538456.0 — *UTM Northing:* 4305893.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 43.0 | RED CLAY |
| 43.0 | 98.0 | LS GRAY |

***Comments*** MC:

184

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220896** | AVACA & EUREKA RD, 2 WEST, OOLITIC; | Fri, Jun 08, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RAYMOND JONES | BEDFORD, IN. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RRT. 6, BOX 13, BEDFORD, IN. | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 67.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 75.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SE 1/4 of the NW 1/4 of Section 6 *Topo map:* OOLITIC
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2250 *Ft S of NL:* 2600
*Ground elevation:* 645.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:* 630.0
*UTM Easting:* 537724.0 *UTM Northing:* 4305261.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 16.0 | DIRT |
| 16.0 | 67.0 | LS BOULDERS & MUD HOLES |
| 67.0 | 74.0 | BLUE LS-HARD |
| 74.0 | 100.0 | GRAY LS-SOFT |

***Comments*** MC 630:

185

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220901** | FROM PATTON HILL(W OF OOLITIC) GOING W APPROX .25 MI. SMALL FARM ON R. | Sat, Jul 25, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | OPAL WEBB | 821 SMITH DR, OOLITIC | |
| Building Contractor | | | |
| Drilling Contractor | LOUIS O. SMITH | R#1, BEDFORD | |
| Equipment Operator | LOUIS O. SMITH | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 163.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 26.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* 90.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the NW 1/4 of Section 5 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1900 *Ft S of NL:* 1200
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* 640.0 *Aquifier elevation:*
*UTM Easting:* 539303.0 *UTM Northing:* 4305685.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | CLAY |
| 22.0 | 28.0 | HARD LS |
| 28.0 | 40.0 | MD LIME |
| 40.0 | 45.0 | HARD LIME |
| 45.0 | 63.0 | SOFT LIME |
| 63.0 | 95.0 | MUD |
| 95.0 | 105.0 | BR LIME |
| 105.0 | 115.0 | GRAY |
| 115.0 | 150.0 | WH LS |
| 150.0 | 163.0 | HARD LIME |

***Comments*** MC 640

186

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220906** | PATTON HILL APP 1 MI W OF OOLITIC IN. | Tue, Jul 21, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ELI TAYLOR JR & NELLIE TAYLOR | BEDFORD IN, RR2 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IN, RR6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 167.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 58.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 87.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the NE 1/4 of Section 5 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1300 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1700
*Ground elevation:* 690.0 *Depth to bedrock:* *Bedrock elevation:* 650.0 *Aquifer elevation:*
*UTM Easting:* 539919.0 *UTM Northing:* 4305543.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 41.0 | DIRT |
| 41.0 | 54.0 | BLUE LS HARD |
| 54.0 | 56.0 | MUD HOLE |
| 56.0 | 71.0 | BLUE LS HARD |
| 71.0 | 121.0 | GRAY LS SOFT |
| 121.0 | 154.0 | WH LS SOFT |
| 154.0 | 167.0 | BLUE LS HARD |

***Comments*** MC 650:

187

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220911** | PATTON HILL, R PAST CAMP, KEEP R. | Sat, Apr 01, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WM. STRUNK | R#2, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE O. SMITH | R#1, BEDFORD IN | |
| Equipment Operator | LOUIE O. SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* | *Pump type:* |
| | *Depth:* 190.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 26.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 92.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* NE 1/4 of the SE 1/4 of the NE 1/4 of Section 5 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2200 *Ft S of NL:* 1900
*Ground elevation:* 650.0 *Depth to bedrock:* *Bedrock elevation:* 625.0 *Aquifer elevation:*
*UTM Easting:* 539394.0 *UTM Northing:* 4305496.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 24.0 | CLAY |
| 24.0 | 25.0 | BLANK |
| 25.0 | 50.0 | LS |
| 50.0 | 85.0 | HARD LIME BLUE |
| 85.0 | 90.0 | GREY LIME |
| 90.0 | 120.0 | WH BUFF |
| 120.0 | 135.0 | MD LIME |
| 135.0 | 155.0 | SOFT GREY |
| 155.0 | 190.0 | HARD LIME |

*Comments* MC 625;

188

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220916** | W OF OOLITIC 2 MI OVER PATTEN HILL ON N SIDE OF RD. | Sat, Jun 17, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BYRON BAKER | BEDFORD R | |
| Building Contractor | | | |
| Drilling Contractor | ROY EALFORD | R2, MITCHELL | |
| Equipment Operator | ROY EALFORD | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 44.5 | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 85.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NW 1/4 of Section 5 *Topo map:* OOLITIC
*Field located by:* JRD *on:* Tue, Aug 08, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 550 *Ft S of NL:* 1200
*Ground elevation:* 660.0 *Depth to bedrock:* 44.0 *Bedrock elevation:* 616.0 *Aquifier elevation:*
*UTM Easting:* 538913.0 *UTM Northing:* 4305710.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 44.5 | SOIL & CLAY |
| 44.5 | 57.0 | GRAY LIME |
| 57.0 | 68.0 | BR LIME |
| 68.0 | 82.0 | GRAY LIME |
| 82.0 | 125.0 | WH LIME |

*Comments* MC 616; OWNER VERIFIED/50' NW OF HOUSE;

# Record of Water Well

189

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217979** | 5MI E OF BEDFORD, ON THE LEATHERWOOD RD. & DIRECTLY S OF LEATHERWOOD CHURCH | Wed, Dec 02, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | H.E. WEAVER | R.R. 6 BEDFORD, INDIANA | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BOX 13 R.R. 6 BEDFORD, INDIANA | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 15.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 5.0 gpm for 0.5 hrs.
*Drawdown:* ft. — *Static water level:* 40.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NW 1/4 of the NE 1/4 of Section 22 — *Topo map:* BEDFORD EAST
*Field located by:* BARNES — *on:* Fri, Jul 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 1700 — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:* 100
*Ground elevation:* 700.0 — *Depth to bedrock:* 12.0 — *Bedrock elevation:* 688.0 — *Aquifier elevation:*
*UTM Easting:* 552845.0 — *UTM Northing:* 4301263.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | DIRT FLINT ROCK |
| 12.0 | 40.0 | GRAY LS |
| 40.0 | 90.0 | BLUE LS HARD |
| 90.0 | 100.0 | BLUE SH |

***Comments*** MC690:

190

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217984** | 5MI E OF BEDFORD ON LEATHERWOOD RD, ABOUT .2MI E OF SHAWSWICK SCHOOL HOUSE | Fri, Nov 11, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | K. SNOW | R. 6 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 90.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 25.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 6.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 45.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NW 1/4 of the NE 1/4 of Section 22 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2300 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 100
*Ground elevation:* 705.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 695.0 *Aquifier elevation:*
*UTM Easting:* 552646.0 *UTM Northing:* 4301267.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | DIRT |
| 10.0 | 20.0 | LS BOULDERS HARD |
| 20.0 | 60.0 | WH LS HARD |
| 60.0 | 75.0 | BLUE LS HARD |
| 75.0 | 90.0 | BLUE SH SOFT |

***Comments*** MC695:Page 9605

191

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217989** | 3MI E. OF BEDFORD ON LEATHERWOOD RD, 1MI W SHAWSWICK SCHOOL | Mon, Aug 03, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | KEDRIC BOLTON | R. 6 BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 12.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. | *Static water level:* 95.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Administrative*

*County:* LAWRENCE | *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NE 1/4 of the NW 1/4 of Section 21 | *Topo map:* BEDFORD EAST
*Field located by:* JCH | *on:* Mon, Aug 01, 1966
*Courthouse location by:* | *on:*
*Location accepted w/o verification by:* | *on:*
*Subdivision name:* | *Lot number:*
*Ft W of EL:* | *Ft N of SL:* | *Ft E of WL:* 1900 | *Ft S of NL:* 100
*Ground elevation:* 685.0 | *Depth to bedrock:* 5.0 | *Bedrock elevation:* 680.0 | *Aquifier elevation:*
*UTM Easting:* 550770.0 | *UTM Northing:* 4301287.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DIRT |
| 3.0 | 9.0 | BLUE LS HARD |
| 9.0 | 23.0 | GRAY LS SOFT |
| 23.0 | 57.0 | BLUE LS HARD |
| 57.0 | 78.0 | BLUE LS SOFT |
| 78.0 | 110.0 | WH LS HARD |
| 110.0 | 200.0 | BLUE SH SOFT |

*Comments*: MC680;

192

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218029** | NEAR SW CORNER OF SW QUARTER OF NE QUARTER OF ABOVE LOCATION - 100' SOUTH FROM LEATHERWOOD CREEK | Mon, Nov 07, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | J. E. SPEER | ROUTE 6, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BOX 13, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 10.58 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.05 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 20.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 16 *Topo map:* BEDFORD EAST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2400 *Ft N of SL:* 3100 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 650.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 645.0 *Aquifer elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | |

*Comments* WELL 2 OF 2

MW6 193

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218034** | APP. 3MI E OF BEDFORD, IND. ON S LEATHERWOOD RD | Fri, Jun 26, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | J.E. SPEER | R. 6 BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 200.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 5.5 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 0.33 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 88.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1E
***Section:*** SW 1/4 of the SW 1/4 of the NE 1/4 of Section 16 ***Topo map:*** BEDFORD EAST
***Field located by:*** JCH ***on:*** Mon, Aug 01, 1966
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***

| | | | |
|---|---|---|---|
| ***Ft W of EL:*** 2400 | ***Ft N of SL:*** 3100 | ***Ft E of WL:*** | ***Ft S of NL:*** |
| ***Ground elevation:*** 650.0 | ***Depth to bedrock:*** 5.0 | ***Bedrock elevation:*** 645.0 | ***Aquifer elevation:*** |
| ***UTM Easting:*** 550999.0 | | ***UTM Northing:*** 4302262.0 | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 29.0 | GRAY LS HARD |
| 24.0 | 60.0 | GRAY LS SOFT |
| 60.0 | 109.0 | BLUE LS HARD |
| 109.0 | 133.0 | GRAY LS HARD |
| 133.0 | 138.0 | BLUE SH SOFT |
| 138.0 | 150.0 | WH LS HARD |
| 150.0 | 156.0 | BLUE LS SOFT |
| 156.0 | 200.0 | BLUE SH SOFT |

***Comments*** MC645: WELL 1 OF 2:

194

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218039** | NE ABOUT .25MI FROM SHAWSWICK SCHOOL IN REVEIN | Wed, Nov 28, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES A SNOW | R F D #6 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 60.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 14.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 14.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* NW 1/4 of the NE 1/4 of the SE 1/4 of Section 15 *Topo map:* BEDFORD EAST

*Field located by:* JUH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 900 *Ft N of SL:* 2300 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 650.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*

*UTM Easting:* 553068.0 *UTM Northing:* 4301992.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 36.0 | ORIGINAL WELL |
| 36.0 | 60.0 | BLUE SH |

*Comments* MC: OLD WELL DRILLED DEEPER;

195

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218044** | E OF BEDFORD OFF SR 50 1MI AT SHAWSWICK SCHOOL | Tue, Aug 23, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | SHAWSWICK TOWNSHIP SCHOOL | R.R. #6 BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | | | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 8.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.5 gpm for 2.0 hrs.
*Drawdown:* 140.0 ft. *Static water level:* 60.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SE 1/4 of the SW 1/4 of Section 15 *Topo map:* BEDFORD EAST
*Field located by:* S&H *on:* Thu, Nov 03, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 25 *Ft E of WL:* 2550 *Ft S of NL:*
*Ground elevation:* 720.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 715.0 *Aquifier elevation:*
*UTM Easting:* 552534.0 *UTM Northing:* 4301313.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 70.0 | BLUE LS HARD |
| 70.0 | 200.0 | BLUE SH |

***Comments*** MC715 OFFIC CHEM; IRON 0.2PPM, HARDNESS 335PPM , PH 8.0, CHLORIDE12PPM;

196

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218049** | E OF BEDFORD 1MI S OF US RD 50 AT SHAWSWICK SCHOOL | Sat, Aug 20, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | SHAWSWICK TOWNSHIP | R.R. 6 BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 BOX 13 | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* gpm for hrs.
*Drawdown:* ft. — *Static water level:* ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SE 1/4 of the SW 1/4 of Section 15 — *Topo map:* BEDFORD EAST
*Field located by:* S&H — *on:* Thu, Nov 03, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 100 — *Ft E of WL:* 2400 — *Ft S of NL:*
*Ground elevation:* 730.0 — *Depth to bedrock:* 6.0 — *Bedrock elevation:* 724.0 — *Aquifer elevation:*
*UTM Easting:* 552486.0 — *UTM Northing:* 4301334.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 80.0 | BLUE LS HARD |
| 80.0 | 150.0 | BLUE SH SOFT |

*Comments* — FC ONLY; DRY WELL;

# Record of Water Well

197

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217369** | SHAWSWICK STATION ERIE RD | Thu, Oct 08, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROLAPH BECHNER | R. 3 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 275.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 15.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.08 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 117.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the NW 1/4 of the SE 1/4 of Section 9 *Topo map:* BARTLETTSVILLE
*Field located by:* J&H *on:* Thu, Nov 03, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2000 *Ft N of SL:* 1900 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 725.0 *Depth to bedrock:* 8.0 *Bedrock elevation:* 717.0 *Aquifer elevation:*
*UTM Easting:* 551113.0 *UTM Northing:* 4303501.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | DIRT |
| 8.0 | 21.0 | GRAY LS SOFT |
| 21.0 | 70.0 | WH LS SOFT |
| 70.0 | 90.0 | WH LS HARD |
| 90.0 | 95.0 | BLUE LS SOFT |
| 95.0 | 110.0 | WH LS SOFT |
| 110.0 | 145.0 | BLUE LS SOFT |
| 145.0 | 275.0 | BLUE SH SOFT |

*Comments* MC:

198

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217374** | 1/4 MI N OF US HIGHWAY 50, 4 MILE EAST OF BEDFORD IN ON SHAWSWICK STATION AND ERIE ROAD | Mon, Sep 19, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ALDOLPH BECKNER | | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 125.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** | ***Material:*** | ***Diameter:*** |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1E
***Section:*** SE 1/4 of the NW 1/4 of the SE 1/4 of Section 9 ***Topo map:*** BARTLETTSVILLE
***Field located by:*** H & S ***on:*** Thu, Nov 03, 1960
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** 2000 ***Ft N of SL:*** 1400 ***Ft E of WL:*** ***Ft S of NL:***
***Ground elevation:*** 725.0 ***Depth to bedrock:*** 8.0 ***Bedrock elevation:*** 717.0 ***Aquifier elevation:***
***UTM Easting:*** ***UTM Northing:***

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | DIRT |
| 8.0 | 21.0 | GRAY LIMESTONE SOFT |
| 21.0 | 70.0 | WHITE LIMESTONE SOFT |
| 70.0 | 90.0 | WHITE LIMESTONE HARD |
| 90.0 | 95.0 | BLUE LIMESTONE SOFT |
| 95.0 | 110.0 | WHITE LIMESTONE SOFT |
| 110.0 | 125.0 | BLUE LIMESTONE SOFT |

*Comments* DRY HOLE

# Record of Water Well

199

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217379** | APPR. 3MI E OF BEDFORD, IND. ON SR 50 N/SIDE OF HIGHWAY | Thu, Jul 22, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES HEWITT | BEDFORD, IND. R.R. 6 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 85.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 10.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 9 *Topo map:* BARTLETTSVILLE
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 100 *Ft E of WL:* 300 *Ft S of NL:*
*Ground elevation:* 645.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 630.0 *Aquifier elevation:*
*UTM Easting:* 550222.0 *UTM Northing:* 4302962.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 14.0 | DIRT |
| 14.0 | 43.0 | BLUE LS HARD |
| 43.0 | 55.0 | GRAY LS HARD |
| 55.0 | 78.0 | BLUE LS HARD |
| 78.0 | 85.0 | WH LS HARD |

***Comments*** MC630;

200

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **336984** | GO TO OTIS PARK, TURN FIRST R HANG TO RT THEN YOU COME AROUND A STEEP CURVE W/DRIVEWAY CLOST HANG R DOWN LANE | Sat, Dec 19, 1998 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | DON L. TAYLOR | RR18 BOX 205, BEDFORD, IN 47421 | (812)279-5190 |
| Building Contractor | | | |
| Drilling Contractor | PHILLIPS WELL DRLNG & PUMP SVC | RR12 BOX 444, BEDFORD, IN 47421 | (812)279-4843 |
| Equipment Operator | KEVIN MATHIES | License: 1679 | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 160.0 | *Pump setting depth:* | *Water quality:* CLEAR |
| Casing | *Length:* 25.0 | *Material:* PVC | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* BAILING *Test rate:* 7.0 gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

*Grouting Information*

*Material:* BENONITE *Depth:* from 0.0 to 42.0
*Installation Method:* AIR *Number of bags used:* 4.0

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* 1/4 of the NE 1/4 of the SW 1/4 of Section 10 *Topo map:* BARTLETTSVILLE
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | CLAY |
| 20.0 | 22.0 | BRKN SS |
| 22.0 | 30.0 | LS |
| 30.0 | 42.0 | GRAY SANDY LS |
| 42.0 | 47.0 | HD SANDY SH |
| 47.0 | 49.0 | LS |
| 49.0 | 53.0 | SHALEY LS |
| 53.0 | 56.0 | LS |
| 56.0 | 59.0 | SHALEY LS |
| 59.0 | 67.0 | LS |
| 67.0 | 70.0 | SHALEY LS |
| 70.0 | 76.0 | LS |
| 76.0 | 85.0 | HD SHALEY LS |

| | | |
|---|---|---|
| 85.0 | 89.0 | SANDY SH |
| 89.0 | 120.0 | LS WATER |
| 120.0 | 160.0 | SHALEY LS |

*Comments* SEE MAP

# Record of Water Well

201

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217479** | STATE ROAD #58 APP. 600YARDS E OF MILWAKIE RR | Fri, May 06, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | FRANK E. TODD | R.R. 3 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | | | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.1 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 63.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NW 1/4 of the SE 1/4 of Section 4 *Topo map:* BARTLETTSVILLE
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1500 *Ft N of SL:* 2300 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 670.0 *Depth to bedrock:* 17.0 *Bedrock elevation:* 653.0 *Aquifer elevation:*
*UTM Easting:* 551224.0 *UTM Northing:* 4305186.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 17.0 | DIRT |
| 17.0 | 40.0 | BLUE LS HARD |
| 40.0 | 175.0 | BLUE SH SOFT |

***Comments*** MC 655; LOC. ACCEPTED W/O VERIF.,NO;

# Record of Water Well

202

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217484** | WELL IS APPR. 5MI E OF BEDFORD CITY LIMITS; OFF SR 58 TURN N ONTO RD 350E&PROCEED APP. .75MI;WELL IS APP.90'OFF RD 350E ON W/SIDE | Sat, Mar 01, 1969 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | J.D.PEXTON&C.M. PEXTON | R. 1, HELTONVILLE, IND 47436 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R 6, BEFORD INDIANA 47421 | |
| Equipment Operator | CHARLES EMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.13 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 80.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* 1/4 of the 1/4 of the 1/4 of Section 4 — *Topo map:* BARTLETTSVILLE
*Field located by:* — *on:*
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* — *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | DIRT |
| 28.0 | 200.0 | BLUE SH SOFT |

***Comments*** APPROX LOCATION:

203

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217489** | N OF SR #58 .25MI SW OF HELTONVILLE 4MI OR 5.5MI NE OF BEDFORD IND | Thu, Feb 16, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | PAUL S. NEAL | R.R. #3 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS | LEATHER WOOD RD, BEDFORD R.R. 6 BOX 13 | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 165.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.

*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* NW 1/4 of the SW 1/4 of the NW 1/4 of Section 3 *Topo map:* BARTLETTSVILLE

*Field located by:* UHL *on:* Tue, Jun 01, 1965

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 500 *Ft S of NL:* 1400

*Ground elevation:* 700.0 *Depth to bedrock:* 21.0 *Bedrock elevation:* 679.0 *Aquifier elevation:*

*UTM Easting:* 551799.0 *UTM Northing:* 4305631.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 21.0 | DIRT |
| 21.0 | 25.0 | BLUE LS HARD |
| 25.0 | 165.0 | BLUE SH SOFT |

***Comments*** DRY HOLE, PLUGGED; MC680;

# Record of Water Well

204

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221461** | E VINEGAR HILL RD 6MI FROM BEDFORD INDIANA 250S ? USE; | Fri, May 02, 1969 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | HAROLD GUTHRIE | R.R. 6 BEDFORD, IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND R.R. 6 | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 220.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.17 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 110.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SE 1/4 of the NW 1/4 of Section 33 *Topo map:* BEDFORD EAST
*Field located by:* DW *on:* Thu, Aug 13, 1970
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2300 *Ft S of NL:* 2500
*Ground elevation:* 660.0 *Depth to bedrock:* 28.0 *Bedrock elevation:* 632.0 *Aquifier elevation:*
*UTM Easting:* 550958.0 *UTM Northing:* 4297342.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | DIRT |
| 28.0 | 105.0 | LS HARD |
| 105.0 | 220.0 | BLUE SH SOFT |

*Comments* MC630; VERIFIED BY NEIGHBOR , MC;

205

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221471** | 4MI SE OF BEDFORD ON TUNNELTON RD | Wed, Feb 17, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HERB KINDER | R.R. 5 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 89.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 44.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 59.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 32 *Topo map:* BEDFORD EAST

*Field located by:* JCH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 700 *Ft S of NL:* 2000

*Ground elevation:* 730.0 *Depth to bedrock:* 40.0 *Bedrock elevation:* 690.0 *Aquifier elevation:*

*UTM Easting:* 548870.0 *UTM Northing:* 4297488.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | DIRT |
| 28.0 | 41.0 | BOULDERS & MUD HOLES |
| 41.0 | 63.0 | BLUE LS HARD |
| 63.0 | 89.0 | GRAY LS HARD |

*Comments* MC690:

206

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221476** | APPR. 4MI SE OF BEDFORD IND. ON VINEGAR HILL RD | Tue, Feb 18, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RAY E. WOODWARD | PO BOX 472 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 25.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 55.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 32 — *Topo map:* BEDFORD EAST
*Field located by:* JUH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* 800 — *Ft S of NL:* 2200
*Ground elevation:* 725.0 — *Depth to bedrock:* 20.0 — *Bedrock elevation:* 705.0 — *Aquifer elevation:*
*UTM Easting:* 548905.0 — *UTM Northing:* 4297430.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 19.0 | DIRT |
| 19.0 | 74.0 | BLUE LS HARD |
| 74.0 | 127.0 | GRAY LS HARD |
| 127.0 | 183.0 | BLUE LS HARD |
| 183.0 | 200.0 | BLUE SH SOFT |

*Comments* MC705;

207

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221481** | APPR. 3MI SE OF BEDFORD, IND. ON TUNNELTON RD, NW CORNER OF TUNNELTON RD, & VINEGAR HILL RD | Thu, Aug 19, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | EUGENE SPAULDING | SPRINGVILLE, IND. R.R. 1 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 136.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 59.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 5.0 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 90.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 32 — *Topo map:* BEDFORD EAST
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* 900 — *Ft S of NL:* 2500
*Ground elevation:* 700.0 — *Depth to bedrock:* 55.0 — *Bedrock elevation:* 645.0 — *Aquifier elevation:*
*UTM Easting:* 548919.0 — *UTM Northing:* 4297323.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 15.0 | DIRT |
| 15.0 | 54.0 | BOULDERS & MUD HOLES |
| 54.0 | 69.0 | GRAY LS HARD |
| 69.0 | 90.0 | BLUE LS SOFT |
| 90.0 | 116.0 | GRAY LS HARD |
| 116.0 | 136.0 | WH LS SOFT |

***Comments*** MC645;

# Record of Water Well

208

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221486** | 4MI OUT ON THE L SIDE OF TUNNERTOWN RD ON L SIDE | Thu, Sep 15, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | STEPHEN E. JONES | ROUTE 5 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 225.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 34.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.05 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SE 1/4 of the SW 1/4 of Section 32 *Topo map:* BEDFORD EAST
*Field located by:* S& H *on:* Fri, Nov 04, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 100 *Ft E of WL:* 1500 *Ft S of NL:*
*Ground elevation:* 670.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 650.0 *Aquifier elevation:*
*UTM Easting:* 549116.0 *UTM Northing:* 4296531.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | DIRT |
| 20.0 | 30.0 | LS BOULDERS HARD |
| 30.0 | 70.0 | BR LS SOFT |
| 70.0 | 79.0 | BLUE LS HARD |
| 79.0 | 85.0 | BLUE SH SOFT |
| 85.0 | 110.0 | BLUE LS HARD |
| 110.0 | 127.0 | WH LS HARD |
| 127.0 | 156.0 | BLUE LS HARD |
| 156.0 | 168.0 | WH LS HARD |
| 168.0 | 190.0 | BLUE LS SOFT |
| 190.0 | 225.0 | BLUE SH SOFT |

*Comments*

MC650; FE-4.0PPM HARDNESS 300PPM PH 8.0 CHLOUDE 15PPM; APPROXLOCATION; LOC. ACCEPTED W/O VERIFI. YES;

209

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221491** | 1ST. CROSS RD S OF VIRGIL GRISSIOM AIRPORT, TURN W , APPR. .5MI N/SIDE OF RD VINEGAR HILL RD | Fri, Aug 12, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES E. MAICK | BEDFORD IND. R.R. 5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 113.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 29.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 31 *Topo map:* BEDFORD EAST
*Field located by:* PW *on:* Mon, Aug 16, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2000 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2500
*Ground elevation:* 670.0 *Depth to bedrock:* 24.0 *Bedrock elevation:* 646.0 *Aquifer elevation:*
*UTM Easting:* 548068.0 *UTM Northing:* 4297330.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 24.0 | DIRT |
| 24.0 | 43.0 | BLUE LS HARD |
| 43.0 | 77.0 | WH LS HARD |
| 77.0 | 98.0 | GRAY LS HARD |
| 98.0 | 113.0 | SH LS SOFT |

***Comments*** MC645; VERIFIED BY OWNER, MC;

210

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221496** | APPR. 3MI S OF BEDFORD IND. IN S I STREET TO VINEGAR HILL RD, APPR. 1MI | Wed, Mar 30, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GLENN EDWARDS | R.R. 5 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 24.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.07 gpm for hrs.
*Drawdown:* ft. *Static water level:* 110.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SE 1/4 of the NW 1/4 of Section 31 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 3200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2500
*Ground elevation:* 680.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 660.0 *Aquifier elevation:*
*UTM Easting:* 547687.0 *UTM Northing:* 4297344.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 16.0 | DIRT |
| 16.0 | 19.0 | LS BOULDERS |
| 19.0 | 28.0 | BLUE LS BOULDERS HARD |
| 28.0 | 45.0 | GRAY LS BOULDERS SOFT |
| 45.0 | 79.0 | WH LS BOULDERSSOFT |
| 79.0 | 93.0 | BLUE LS BOULDERS HARD |
| 93.0 | 126.0 | WH LS BOULDERS HARD |
| 126.0 | 150.0 | GRAY LS BOULDERS HARD |

***Comments*** MC660;

211

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221501** | S AND SLIGHTLY E FROM BEDFORD ON VINEGAR HILL RD | Sat, Mar 13, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WALTER CRAWFORD | R.R. 5 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BEDFORD, IND | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 26.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.13 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 107.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 31 — *Topo map:* BEDFORD EAST
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 2300 — *Ft E of WL:* 2700 — *Ft S of NL:*
*Ground elevation:* 680.0 — *Depth to bedrock:* 20.0 — *Bedrock elevation:* 660.0 — *Aquifier elevation:*
*UTM Easting:* 547582.0 — *UTM Northing:* 4297214.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | DIRT |
| 20.0 | 26.0 | GRAY LS HARD |
| 26.0 | 54.0 | BLUE LS SOFT |
| 54.0 | 71.0 | BR LS SOFT |
| 71.0 | 94.0 | BLUE LS HARD |
| 94.0 | 100.0 | BLUE SH SOFT |
| 100.0 | 112.0 | WH LS HARD |
| 112.0 | 175.0 | BLUE LS HARD |
| 175.0 | 200.0 | BLUE SH SOFT |

***Comments*** MC660:

# Record of Water Well

212

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221506** | 80' IN FROM N COUNTY LINE 80' FROM E BOUNDRY JUST S OF COUNTY HOUSE & A LITTLE W | Thu, Nov 05, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HAROLD LESLIE MOORE | R.R. #5 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | LEATHERWOOD RD BEDFORD, IND. R.R. 6 BOX 13 | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 95.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 4.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 22.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NW 1/4 of the NE 1/4 of Section 31 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2450 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 50
*Ground elevation:* 700.0 *Depth to bedrock:* 16.0 *Bedrock elevation:* 684.0 *Aquifer elevation:*
*UTM Easting:* 547904.0 *UTM Northing:* 4298083.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 16.0 | DIRT |
| 16.0 | 60.0 | BLUE LS HARD |
| 60.0 | 75.0 | GRAY LS SOFT |
| 75.0 | 95.0 | WH LS HARD |

*Comments* MC680; OWNER NOT HOME; LOC. ACCEPTED W/O VERIF. YES:

# Record of Water Well

213

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221511** | FROM BEDFORD GO E TO TUNNELTON RD., PASS BROOK KNOLL TURN W, 1ST RD TO R, TO GO POOR FARM RD., TURN R, 3RD HOUSE ON L, 1/4 MI W OF OLD POOR FARM | Fri, Aug 21, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | WARREN & SUE RAINEY | R 5, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BOX 13, BEDFORD IN | |
| Equipment Operator | BUCYRUS-ERIC | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 108.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.06 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 38.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 31 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 3250 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 50
*Ground elevation:* 700.0 *Depth to bedrock:* 25.0 *Bedrock elevation:* 675.0 *Aquifer elevation:*
*UTM Easting:* 547627.0 *UTM Northing:* 4298094.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

*Comments* MC675; OWNER NOT HOME

214

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221516** | 4MI SE OF BEDFORD ON VINEGAR HILL RD | Sat, Mar 24, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES W. EDWARDS | R.R. 5 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.18 gpm for hrs.
*Drawdown:* ft. *Static water level:* 100.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SE 1/4 of the NW 1/4 of Section 31 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 3300 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2500
*Ground elevation:* 680.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 660.0 *Aquifier elevation:*
*UTM Easting:* 547653.0 *UTM Northing:* 4297345.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | DIRT |
| 18.0 | 44.0 | BLUE LS HARD |
| 44.0 | 63.0 | BR LS SOFT |
| 63.0 | 75.0 | WH LS HARD |
| 75.0 | 91.0 | BLUE LS HARD |
| 91.0 | 134.0 | GRAY LS HARD |
| 134.0 | 165.0 | BLUE LS HARD |
| 165.0 | 200.0 | BLUE SH SOFT |

***Comments*** MC660:

215

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221521** | APPR. 3 BLOCKS W OF POOR FARM ON POOR FARM RD, S/SIDE OF RD | Thu, Jun 02, 1966 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | DAVID L. TIDD | BEDFORD IND. R.R. 5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 103.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 32.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.3 gpm for hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the NE 1/4 of the NW 1/4 of Section 31 *Topo map:* BEDFORD EAST
*Field located by:* DW *on:* Mon, Aug 16, 1971
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 3050 *Ft S of NL:* 50
*Ground elevation:* 695.0 *Depth to bedrock:* 26.0 *Bedrock elevation:* 669.0 *Aquifier elevation:*
*UTM Easting:* 547684.0 *UTM Northing:* 4298095.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 24.0 | DIRT |
| 24.0 | 26.0 | BOULDERS |
| 26.0 | 47.0 | GRAY LS HARD |
| 47.0 | 72.0 | BLUE LS HARD |
| 72.0 | 94.0 | WH LS HARD |
| 94.0 | 103.0 | GRAY LS HARD |

***Comments***

MC 675; MC;

# Record of Water Well

216

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221526** | .5MI W OF OLD VINEGAR HILL SCHOOL VINEGAR HILL SCHOOL IS LOCATED ABOUT 4MI SE OF BEDFORD ON THE TUNNELTON RD. PAST AIR PORT CROSSROADS | Mon, May 16, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | FAY JOHNSON | R.R. #5 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | WINFRED PHILLIPS | R.R. #5 BEDFORD IND. | |
| Equipment Operator | WINFRED PHILLIPS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 85.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 2.0 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 9.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 31 — *Topo map:* BEDFORD EAST
*Field located by:* BARNES — *on:* Fri, Jul 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 1300 — *Ft N of SL:* 50 — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 670.0 — *Depth to bedrock:* 12.0 — *Bedrock elevation:* 658.0 — *Aquifier elevation:*
*UTM Easting:* 548254.0 — *UTM Northing:* 4297327.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | CLAY |
| 12.0 | 15.0 | LIME |
| 15.0 | 16.0 | MUD SEAM |
| 16.0 | 35.0 | BLUE LIME |
| 35.0 | 65.0 | BR LIME |
| 65.0 | 85.0 | BLUE LIME |

***Comments*** — MC655; LOC. ACCEPTED W/O VERIF. YES;

# Record of Water Well

217

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217965** | NEAR INTERSECTOIN OF POOR FARM & TUNNELTON ROADS, APPROX. 100 FT. SOUTH OF POOR FARM RD AND 70 FT WEST OF TENNELTON ROAD | Thu, Dec 07, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ALBERT E. WHITNER | RR 5, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BOX 13, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 250.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.05 gpm for hrs.
*Drawdown:* ft. *Static water level:* 150.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 600 *Ft E of WL:* 1200 *Ft S of NL:*
*Ground elevation:* 735.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

***Comments*** WELL DEEPENED

# Record of Water Well

218

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217970** | NEAR INTERSECTION OF POOR FARM & TUNTILTON RD | Thu, Dec 07, 1961 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | ALBERT E. WHITNER | R.R. 5 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 144.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.

*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* SE 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST

*Field located by:* JCH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* 600 *Ft E of WL:* 1200 *Ft S of NL:*

*Ground elevation:* 735.0 *Depth to bedrock:* 25.0 *Bedrock elevation:* 710.0 *Aquifer elevation:*

*UTM Easting:* 548999.0 *UTM Northing:* 4298280.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 25.0 | DIRT |
| 25.0 | 65.0 | BLUE LS HARD |
| 65.0 | 102.0 | BR LS SOFT |
| 102.0 | 144.0 | SH LS HARD |

***Comments***

MC710; NO GOOD. DRY HOLEPage 9604

# Record of Water Well

219

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217975** | 1ST ROAD NORTH GOOSETOWN SCHOOL 1/4 MILE NORTH PINHOOK ROAD | Tue, Oct 11, 1960 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | GEORGE BARNETT | R 5, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BOX 13, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 5.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.13 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NW 1/4 of the NW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* S&H *on:* Thu, Nov 03, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 25 *Ft N of SL:* 200 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 650.0 *Depth to bedrock:* 4.0 *Bedrock elevation:* 646.0 *Aquifier elevation:*
*UTM Easting:* 550171.0 *UTM Northing:* 4299669.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

***Comments***

MC645; OFFICE CHEM: FE - .5 PPM; HARDNESS - 410 PPM; PH - 7.5; CHLORIDE -11 PPM

220

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217980** | ON TUNTELTON & BEDFORD RD ACROSS FROM BEDFORD AIR PORT | Fri, Nov 04, 1960 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | ERNEST G.-BARBARA S. SPEER | BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 130.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 31.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 85.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the SE 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1200 *Ft E of WL:* 1400 *Ft S of NL:*
*Ground elevation:* 725.0 *Depth to bedrock:* 20.0 *Bedrock elevation:* 705.0 *Aquifier elevation:*
*UTM Easting:* 549048.0 *UTM Northing:* 4298491.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | DIRT |
| 20.0 | 28.0 | LS BOULDERS |
| 28.0 | 100.0 | WH LS HARD |
| 100.0 | 130.0 | GRAY LS SOFT |

*Comments* MC705:

221

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217985** | ON AIRPORT & POOR FARM RD | Sat, Apr 23, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CARL CASIDY | R.R. 5 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 121.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.58 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.67 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 43.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 700 *Ft E of WL:* 300 *Ft S of NL:*
*Ground elevation:* 725.0 *Depth to bedrock:* 30.0 *Bedrock elevation:* 695.0 *Aquifier elevation:*
*UTM Easting:* 548709.0 *UTM Northing:* 4298332.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | DIRT |
| 30.0 | 50.0 | WH LS |
| 50.0 | 90.0 | GRAY LS |
| 90.0 | 121.0 | WH LS |

*Comments* MC700; LOC. ACCEPTED W/O VERIF. NO; HARD WATER;

222

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217990** | 3MI SE OF BEDFORD IND. ON POOR FARM RD | Thu, Mar 29, 1962 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | LEONARD PAREY | R.R. 5 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BEDFORD IND | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 31.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 700 *Ft E of WL:* 700 *Ft S of NL:*
*Ground elevation:* 730.0 *Depth to bedrock:* 25.0 *Bedrock elevation:* 705.0 *Aquifier elevation:*
*UTM Easting:* 548848.0 *UTM Northing:* 4298334.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 26.0 | DIRT |
| 26.0 | 36.0 | WH LS HARD |
| 36.0 | 44.0 | BLUE LS HARD |
| 44.0 | 75.0 | BR LS SOFT |
| 75.0 | 100.0 | BLUE LS HARD |

*Comments* MC705;

223

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217995** | WELL DRILLED ON PEER FARM RD JUST S OF BEDFORD AIR PORT | Sat, Jul 11, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GEORGE HICHISON | R.R. 5 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | WINFRED PHILLIPS | R.R. 5, BEDFORD, IND. | |
| Equipment Operator | WINFRED PHILLIPS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 110.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.58 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 700 *Ft E of WL:* 450 *Ft S of NL:*
*Ground elevation:* 730.0 *Depth to bedrock:* 21.0 *Bedrock elevation:* 709.0 *Aquifier elevation:*
*UTM Easting:* 548778.0 *UTM Northing:* 4298328.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 21.0 | RED CLAY |
| 21.0 | 27.0 | BOULDERS |
| 27.0 | 44.0 | HARD WH LIME |
| 44.0 | 95.0 | SOFT BR LIME |
| 95.0 | 110.0 | VERY HARD BLUE LIME |

***Comments***

MC710; HIT WATER BETWEEN 64 & 65'; LOC. ACCEPTED W/O VERIF. YES;

224

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218000** | ON TUNNELTON & BEDFORD RD APPR. 4MI FROM BEDFORD IND ACROSS RD FROM AIR PORT | Thu, Apr 27, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HOMER GRUFF JR. | 2120 2ST BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R 6 BOX 13 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 180.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 32.17 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 28.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 75.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2100 *Ft E of WL:* 1800 *Ft S of NL:*
*Ground elevation:* 730.0 *Depth to bedrock:* 30.0 *Bedrock elevation:* 700.0 *Aquifier elevation:*
*UTM Easting:* 549156.0 *UTM Northing:* 4298766.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | DIRT |
| 28.0 | 30.0 | BLUE LS BOULDERS |
| 30.0 | 100.0 | WH LS HARD |
| 100.0 | 130.0 | GRAY LS SOFT |
| 130.0 | 180.0 | WH LS AVERAGE |

***Comments*** MC700:

225

# Record of Water Well

**Indiana Department of Natural Resources**

| | | | |
|---|---|---|---|
| ***Reference Number*** | ***Driving directions to well*** | | ***Date completed*** |
| **218005** | APP 3 MI SE OF BEDFORD, ON TUNNELTON ROAD, ACROSS FROM VIRGIL GIRISSIOM AIR PORT | | Thu, Sep 08, 1966 |

| | ***Name*** | ***Address*** | ***Telephone*** |
|---|---|---|---|
| ***Owner-Contractor*** | | | |
| Well Owner | SLFRED & ORA COLLINS | BEDFORD, IND RR6 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS&SONS | RR6 BOX 13 BEDFORD, IND | |
| Equipment Operator | EUGENE&CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** STOCK | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 110.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 46.0 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** — ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 0.8 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 40.0 ft.

***Grouting Information*** — ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** — ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 5N ***Range:*** 1E
***Section:*** NW 1/4 of the NE 1/4 of the SW 1/4 of Section 29 ***Topo map:*** BEDFORD EAST
***Field located by:*** DCS ***on:***
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** 2200 ***Ft E of WL:*** 1900 ***Ft S of NL:***
***Ground elevation:*** 730.0 ***Depth to bedrock:*** 42.0 ***Bedrock elevation:*** 688.0 ***Aquifier elevation:***
***UTM Easting:*** 549197.0 ***UTM Northing:*** 4298784.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 42.0 | DIRT |
| 42.0 | 53.0 | BLUE LS HARD |
| 53.0 | 91.0 | GRAY LS SILT |
| 91.0 | 110.0 | WHITE LS HARD |

***Comments*** mc 690; verified by owner; mc

226

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218010** | APPR. 1.5MI SE OF BEDFORD, IND. CORNER OF TUNNELTURN & PINHOOK RD | Mon, Dec 14, 1964 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | CHARLES R. BOTTS | R.R. 6 BEDFORD, IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 3.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.33 gpm for hrs.
*Drawdown:* ft. *Static water level:* 20.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the NW 1/4 of the NW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 400 *Ft S of NL:* 100
*Ground elevation:* 630.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 625.0 *Aquifer elevation:*
*UTM Easting:* 578704.0 *UTM Northing:* 4299671.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 26.0 | WH LS SOFT |
| 26.0 | 51.0 | BLUE LS HARD |
| 51.0 | 56.0 | BLUE SH SOFT |
| 56.0 | 92.0 | WH LS HARD |
| 92.0 | 140.0 | BLUE SH SOFT |

*Comments* MC625:

227

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218015** | 1MI OFF TUNNELTON RD ON PINHOOK RD | Tue, Jul 07, 1964 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | DONALD NORDHOFF | BEDFORD IND. 616 TST. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 107.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.25 gpm for hrs.
*Drawdown:* ft. *Static water level:* 20.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the NW 1/4 of the NW 1/4 of Section 28 *Topo map:* BEDFORD EAST
*Field located by:* JUH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 600 *Ft S of NL:* 1000
*Ground elevation:* 660.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 655.0 *Aquifer elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 2.0 | DIRT |
| 2.0 | 33.0 | GRAY LS HARD |
| 33.0 | 59.0 | BLUE LS HARD |
| 59.0 | 65.0 | BLUE LS SOFT |
| 65.0 | 101.0 | BLUE LS HARD |
| 101.0 | 107.0 | BLUE SH SOFT |

*Comments*

# Record of Water Well

228

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218020** | 3MI SE ON TUNNELTON RD ; FROM BEDFORD IND. & ACROSS RD TROM AIRPORT A LITTLE TO THE N | Thu, Apr 14, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GIRL SCOUT ASSN. LAW. CO | 1415 1/2 W 15TH ST. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | LEATHERWOOD RD, BEDFORD, INDIANA R.R. 6 BOX 13 | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* PUBLIC SUPPLY | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 205.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 47.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 43.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SE 1/4 of the SE 1/4 of the NW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2800 *Ft N of SL:* 2900 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 730.0 *Depth to bedrock:* 30.0 *Bedrock elevation:* 700.0 *Aquifier elevation:*
*UTM Easting:* 549353.0 *UTM Northing:* 4299026.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | DIRT |
| 30.0 | 42.0 | DIRT & HARD LS BOULDERS |
| 42.0 | 60.0 | WH LS HARD |
| 60.0 | 75.0 | BR LS SOFT |
| 75.0 | 150.0 | BLUE LS HARD |
| 150.0 | 190.0 | WH LS EXTRA HARD |
| 190.0 | 205.0 | BLUE LS HARD |

*Comments* MC730;

229

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218025** | 4 MILES EAST OF BEDFORD ON PINHOOK ROAD, BRIDGE CROSSING SAND CREEK AT START, LEFT SIDE OF ROAD | Tue, Aug 27, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DONALD AND LEE NORDHOFF | #10 MURRAY COURT | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BOX 13, BEDFORD IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 5.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.1 gpm for hrs.
*Drawdown:* ft. *Static water level:* 110.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the NW 1/4 of the NW 1/4 of Section 28 *Topo map:* BEDFORD EAST
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 600 *Ft S of NL:* 1000
*Ground elevation:* 660.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | BLANK |

***Comments***

230

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218030** | 1MI E OFF TUNNELTON RD ON PINHOOK RD | Thu, Sep 24, 1964 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* Well Owner | DONALD NORDHOFF | BEDFORD, IND. 616 TST | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 12.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test* — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.2 gpm for hrs.
*Drawdown:* ft. — *Static water level:* 114.0 ft.

*Grouting Information* — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Well Abandonment* — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Administrative*

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the NW 1/4 of the NW 1/4 of Section 28 — *Topo map:* BEDFORD EAST
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* 600 — *Ft S of NL:* 1000
*Ground elevation:* 660.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* — *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 28.0 | GRAY LS HARD |
| 28.0 | 53.0 | BLUE LS HARD |
| 53.0 | 60.0 | BLUE LS SOFT |
| 60.0 | 108.0 | BLUE LS HARD |
| 108.0 | 200.0 | BLUE SH SOFT |

*Comments*

231

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218035** | APPR. 3MI E OF BEDFORD, IND. APPR. 0.125MI N OF OLD SOOSE TOWN SCHOOL | Wed, Apr 07, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DONALD NORDHOFF | BEDFORD, IND. R.R. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 7.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.27 gpm for hrs.
*Drawdown:* ft. *Static water level:* 92.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the NW 1/4 of the NW 1/4 of Section 28 *Topo map:* BEDFORD EAST
*Field located by:* JNH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 600 *Ft S of NL:* 1000
*Ground elevation:* 660.0 *Depth to bedrock:* 4.0 *Bedrock elevation:* 656.0 *Aquifer elevation:*
*UTM Easting:* 550378.0 *UTM Northing:* 4299403.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 28.0 | GRAY LS HARD |
| 28.0 | 53.0 | BLUE LS HARD |
| 53.0 | 60.0 | BLUE LS SOFT |
| 60.0 | 116.0 | BLUE LS HARD |
| 116.0 | 200.0 | BLUE SH SOFT |

*Comments* MC655;

232

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218040** | APPR. 4MI SE OF BEDFORD, IND. ON PINHOOK RD | Fri, Oct 16, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HAZEL L. GILSLEEP | BEDFORD, IND. R.R. 5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IND. R.R. 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.

*Drawdown:* ft. *Static water level:* 20.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* NW 1/4 of the NE 1/4 of the SE 1/4 of Section 28 *Topo map:* BEDFORD EAST

*Field located by:* JCH *on:* Mon, Aug 01, 1966

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* 700 *Ft N of SL:* 2600 *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* 635.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 620.0 *Aquifier elevation:*

*UTM Easting:* 551635.0 *UTM Northing:* 4298887.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 17.0 | DIRT |
| 17.0 | 100.0 | BLUE SH SOFT |

*Comments* MC620;

233

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218045** | 1.5MI OFF THE BEDFORD , TUNNELTON RD ON THE GOOSE TOWN RD | Tue, May 23, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CAM ANDERSON | R.R. 5, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | WINFRED PHILLIPS | R.R. 5 BEDFORD | |
| Equipment Operator | WINFRED PHILLIPS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 210.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 7.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.09 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 65.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* NE 1/4 of the SE 1/4 of the NW 1/4 of Section 28 *Topo map:* BEDFORD EAST
*Field located by:* JCH *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2600 *Ft S of NL:* 1500
*Ground elevation:* 610.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 605.0 *Aquifer elevation:*
*UTM Easting:* 550986.0 *UTM Northing:* 4299255.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | CLAY |
| 6.0 | 58.0 | LS |
| 58.0 | 210.0 | BLUE SH |

*Comments* MC605;

234

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **218050** | APP. .5MI S OF GOOSE TOWN SCHOOL ON PINHOOK RD | Sat, Jun 14, 1969 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BOB MEDOWS | BEDFORD, R5 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R. 6 BEDFORD, IND. | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* | *Pump type:* |
| | *Depth:* 219.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.

*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E

*Section:* NE 1/4 of the NW 1/4 of the SW 1/4 of Section 28 *Topo map:* BEDFORD EAST

*Field located by:* PW *on:* Fri, Aug 13, 1971

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* 2300 *Ft E of WL:* 1300 *Ft S of NL:*

*Ground elevation:* 700.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 685.0 *Aquifer elevation:*

*UTM Easting:* 550611.0 *UTM Northing:* 4298819.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 15.0 | DIRT |
| 15.0 | 30.0 | BROKEN STONE |
| 30.0 | 60.0 | BLUE LS SOFT |
| 60.0 | 85.0 | BLUE LS HARD |
| 85.0 | 120.0 | WH LS HARD |
| 120.0 | 145.0 | BLUE LS HARD |
| 145.0 | 219.0 | BLUE SH SOFT |

***Comments*** MC685; DRY HOLE. VERIFIED BY OWNER. MC;

# Record of Water Well

235

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221541** | JUST S OF POOR FARM RD & ABOUT .5MI OF TUNTELTON RD TO W #2 | Sat, Dec 05, 1959 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | HIRKMAN & PARLEY | R.R. 6 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 18 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 38.83 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.5 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 57.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 550 *Ft E of WL:* 300 *Ft S of NL:*
*Ground elevation:* 730.0 *Depth to bedrock:* 33.0 *Bedrock elevation:* 697.0 *Aquifier elevation:*
*UTM Easting:* 548732.0 *UTM Northing:* 4298267.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 33.0 | DIRT |
| 33.0 | 52.0 | BLUE LS HARD |
| 52.0 | 70.0 | GRAY LS SOFT |
| 70.0 | 125.0 | WH LS HARD |

*Comments* MC700: INFOR FROM NEIGHBOR; LOC ACCEPTED W/O VERIF. YES;

# Record of Water Well

2360

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221546** | JUST S OF POOR FARM RD AND ABOUT .5MI OF TUNTELTON RD TO W | Tue, Dec 08, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HIRKMAN & PARLEY | R.R. 6 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BEDFORD, IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 106.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 35.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.3 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 56.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 550 *Ft E of WL:* 500 *Ft S of NL:*
*Ground elevation:* 730.0 *Depth to bedrock:* 32.0 *Bedrock elevation:* 698.0 *Aquifier elevation:*
*UTM Easting:* 548779.0 *UTM Northing:* 4298269.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 32.0 | DIRT |
| 32.0 | 50.0 | BLUE LS HARD |
| 50.0 | 70.0 | GRAY LS SOFT |
| 70.0 | 106.0 | WH LS HARD |

***Comments*** MC700; VERIFIED BY NEIGHBOR; LOC. ACCEPTED W/O VERIF. YES;

237

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221551** | APPR. 200' S OF POOR FARM RD OR 3MI SE BEDFORD IND | Wed, Nov 11, 1959 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | JACK CUMMINS | R.R. 6 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.75 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.2 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 500 *Ft E of WL:* 100 *Ft S of NL:*
*Ground elevation:* 720.0 *Depth to bedrock:* 22.0 *Bedrock elevation:* 698.0 *Aquifier elevation:*
*UTM Easting:* 548643.0 *UTM Northing:* 4298267.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | DIRT |
| 23.0 | 43.0 | BLUE LS HARD |
| 43.0 | 77.0 | GRAY LS SOFT |
| 77.0 | 100.0 | BLUE LS EXTRA HARD |

*Comments* MC700 LOC. ACCEPTED W/O VERIF. YES;

238

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **221556** | ABOUT 3MI S OF BEDFORD OFF TUNTILTON RD ABOUT .5MI W ON POOR FARM RD | Wed, May 25, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES ROOT | R.R. 6 BEDFORD IND | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | R.R. 6 BOX 13 BEDFORD IND | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 3.0 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 45.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 5N *Range:* 1E
*Section:* NW 1/4 of the SW 1/4 of the SW 1/4 of Section 29 — *Topo map:* BEDFORD EAST
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 700 — *Ft E of WL:* 100 — *Ft S of NL:*
*Ground elevation:* 720.0 — *Depth to bedrock:* 20.0 — *Bedrock elevation:* 700.0 — *Aquifier elevation:*
*UTM Easting:* 548639.0 — *UTM Northing:* 4298335.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | DIRT |
| 20.0 | 30.0 | BLUE LS BOULDERS |
| 30.0 | 40.0 | BLUE LS |
| 40.0 | 75.0 | BR LS |
| 75.0 | 100.0 | WH LS |

***Comments*** MC700;

# Record of Water Well

139

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217262** | FROM FAYETTEVILLE GO E TO 1ST RD N GO APPROX 3 MI TO 1ST SEEP HILL 2ND HSE ON HILL | Fri, Apr 15, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ED STEELE | 2307 WASH AVE, BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | LOUIE A SMITH | R1, BEDFORD | |
| Equipment Operator | LOUIE A SMITH | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 150.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 8.0 gpm for 2.0 hrs.
*Drawdown:* ft. *Static water level:* ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 2W
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 36 *Topo map:* OOLITIC
*Field located by:* S&H *on:* Tue, Nov 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2500 *Ft E of WL:* 1000 *Ft S of NL:*
*Ground elevation:* 765.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 535841.0 *UTM Northing:* 4306708.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 9.0 | CLAY |
| 9.0 | 30.0 | BR LIME |
| 30.0 | 100.0 | WHITE LIME |
| 100.0 | 125.0 | HARD LIME |
| 125.0 | 150.0 | SOME SOFTER LIME |

*Comments* MC

240

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217267** | IN 3 MILES OF FAYETTEVILLE 2 MILES OF SPRINGVILLE, BETWEEN ST HIGHWAY 450 AND ST HIGHWAY 54 ON REUTER LANE | Fri, Sep 25, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | EDGAR W & ALURA A STEELE | 2307 WASHINGTON AVE., BEDFORD, INDIANA | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BEDFORD, IND. | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 95.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 2W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 36 *Topo map:* OOLITIC
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1800 *Ft E of WL:* 1400 *Ft S of NL:*
*Ground elevation:* 725.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 535854.0 *UTM Northing:* 4306610.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 9.0 | BLUE LS HARD |
| 9.0 | 15.0 | GRAY LS HARD |
| 15.0 | 16.0 | BROKEN LS SOFT |
| 16.0 | 52.0 | GRAY LS HARD |
| 52.0 | 70.0 | WHITE LS HARD |
| 70.0 | 73.0 | BROKEN LS SOFT |
| 73.0 | 79.0 | BLUE LS HARD |
| 79.0 | 82.0 | BROKEN LS SOFT |
| 82.0 | 89.0 | WHITE LS HARD |
| 89.0 | 95.0 | BROKEN LS & MUD SOFT |

***Comments*** MC: DRY HOLE;

241

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217272** | SPRINGVILLE, INDIANA | Sat, Mar 21, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CONSTANCE LACKY | R 2, SPRINGVILLE | |
| Building Contractor | | | |
| Drilling Contractor | EADS AND DECKARD | R 9, BLOOMINGTON, IND. | |
| Equipment Operator | ERNEST D. EADS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 130.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 2.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 10.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 93.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 2W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 36 *Topo map:* OOLITIC
*Field located by:* JRS *on:* Tue, Aug 08, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1850 *Ft E of WL:* 1450 *Ft S of NL:*
*Ground elevation:* 730.0 *Depth to bedrock:* 4.0 *Bedrock elevation:* 726.0 *Aquifer elevation:*
*UTM Easting:* 535848.0 *UTM Northing:* 4306616.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.1 | CLAY |
| 4.1 | 105.0 | HARD LIMESTONE |
| 105.0 | 130.0 | SLAPSTONE |

***Comments*** MC 726; MC; OWNER VERIFIED/ 10 FT. NW OF HOUSE;

# Record of Water Well

242

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217241** | LOCATED AT NEEDMORE INDIANA AP. 2 BLOCKS DUE S OF SCHOOL HOUSE | Thu, Jul 14, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GAROLD TURNER | RR 2 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 166.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 56.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 80.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* S&H *on:* Tue, Nov 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1100 *Ft S of NL:* 3000
*Ground elevation:* 700.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 540648.0 *UTM Northing:* 4308606.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 20.0 | DIRT |
| 20.0 | 53.0 | SHALIE LS & MUD |
| 53.0 | 70.0 | BLUE LS HARD |
| 70.0 | 166.0 | WH LS SOFT |

***Comments*** MC680

# Record of Water Well

243

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217246** | 2 BLOCKS E OF US HWY 37 NEEDMORE, IN | Wed, May 04, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HENRY GOODMAN | RR3, BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 37.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.5 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 70.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the SE 1/4 of the NW 1/4 of Section 28 — *Topo map:* OOLITIC
*Field located by:* BARNES — *on:* Fri, Jul 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 3100 — *Ft N of SL:* 2800 — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 680.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifer elevation:*
*UTM Easting:* 540941.0 — *UTM Northing:* 4308545.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | DIRT |
| 12.0 | 15.0 | LS BOULDERS |
| 15.0 | 34.0 | BLUE LS & MUD HOLES |
| 34.0 | 50.0 | BLUE LS HARD |
| 50.0 | 75.0 | WHTIE LS SOFT |
| 75.0 | 80.0 | BLUE LS HARD |
| 80.0 | 140.0 | WHITE LS SOFT |

*Comments* MC

244

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217251** | WELL WAS DRILLED DEEPER WELL IS LOCATED IN NEEDMORE | Wed, Jul 15, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | FRED DAVIS | RR #4 BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | WINFRED PHILLIPS | RR #5 BEDFORD , IND. | |
| Equipment Operator | WINFRED PHILLIPS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 150.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** | ***Material:*** | ***Diameter:*** 5.63 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 1.0 gpm for 1.0 hrs.
***Drawdown:*** ft. ***Static water level:*** 53.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 6N ***Range:*** 1W
***Section:*** SW 1/4 of the SW 1/4 of the NW 1/4 of Section 28 ***Topo map:*** OOLITIC
***Field located by:*** BARNES ***on:*** Fri, Jul 01, 1960
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** NO ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** 2800 ***Ft E of WL:*** 800 ***Ft S of NL:***
***Ground elevation:*** 700.0 ***Depth to bedrock:*** ***Bedrock elevation:*** ***Aquifier elevation:***
***UTM Easting:*** 540526.0 ***UTM Northing:*** 4308502.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 90.0 | BLANK |
| 90.0 | 150.0 | SOFT GRAY LIME |

***Comments*** MC; DRILLED WELL DEEPER

245

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217256** | APP 1/4 MI S OF NEEDMORE IND. & ON E SIDE OF SR37 | Wed, Dec 06, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JAMES HORNOCKER | | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 169.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 15.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the SE 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2500 *Ft N of SL:* 1700 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 541148.0 *UTM Northing:* 4308174.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 27.0 | BLUE LS HARD |
| 27.0 | 85.0 | WH LS SOFT |
| 85.0 | 155.0 | BLUE LS HARD |
| 155.0 | 169.0 | BR LS SOFT |

***Comments*** MC635

246

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217261** | NEAR NEEDMORE ON HIGHWAY 37 S | Sat, Aug 18, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOE ROBERTS | BEDFORD RR 3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. RR 4 BOX 72 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* | *Pump type:* |
| | *Depth:* 105.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 9.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for 8.0 hrs. *BailTest rate:* 2.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the SE 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2400 *Ft N of SL:* 800 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* 630.0 *Aquifer elevation:*
*UTM Easting:* 541192.0 *UTM Northing:* 4307912.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | CLAY |
| 8.0 | 78.0 | SOFT LS |
| 78.0 | 113.0 | HARD LS |

***Comments*** MC63Page 9558

247

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217266** | NEEDMORE IND. | Tue, Apr 04, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ORVILLE ARTHUR | BEDFORD RR 3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. RR 4 BOX 72 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* | *Pump type:* |
| | *Depth:* 120.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.8 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NW 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 650 *Ft S of NL:* 2100
*Ground elevation:* 710.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 540477.0 *UTM Northing:* 4308636.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | CLAY |
| 18.0 | 120.0 | SOFT LS |

***Comments***

248

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217271** | WELL WAS DRILLED IN NEEDMORE AT THE BAPTIST CHURCH | Tue, Jul 28, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BAPTIST CHURCH | RR #4 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | WINFRED PHILLIPS | RR #5 BEDFORD IND. | |
| Equipment Operator | WINFRED PHILLIPS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 19.0 | *Material:* | *Diameter:* 5.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 75.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2100 *Ft E of WL:* 800 *Ft S of NL:*
*Ground elevation:* 690.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 540837.0 *UTM Northing:* 4308314.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 14.0 | RED CLAY |
| 14.0 | 16.0 | LS |
| 16.0 | 19.0 | BLUE SH |
| 19.0 | 57.0 | BLUE HARD LIME |
| 57.0 | 70.0 | GRAY HARD LIME |
| 70.0 | 76.0 | BLUE SH |
| 76.0 | 85.0 | HARD BLUE LIME |
| 85.0 | 145.0 | SOFT GRAY LIME |
| 145.0 | 165.0 | VERY HARD WH LIME |
| 165.0 | 200.0 | HARD BLUE LIME |

***Comments*** ADD. CONST. INFO

249

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217276** | .5 MI N OF AVOCA ON HARROWSBURG RD LOCATED ON NW CORNER OF PLOT PT NW SW SEC 29 TW 6 R 5 | Sat, Jun 01, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MURLE HOSTETTER | RR2, SPRINGVILLE, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 78.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.4 gpm for hrs.
*Drawdown:* ft. *Static water level:* 73.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the SW 1/4 of Section 29 *Topo map:* OOLITIC
*Field located by:* JCA *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1000 *Ft E of WL:* 100 *Ft S of NL:*
*Ground elevation:* 610.0 *Depth to bedrock:* *Bedrock elevation:* 580.0 *Aquifer elevation:*
*UTM Easting:* 538735.0 *UTM Northing:* 4307975.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 32.0 | DIRT |
| 32.0 | 75.0 | MUD HOLES & BROKEN STONE |
| 75.0 | 96.0 | BLUE LS HARD |
| 96.0 | 108.0 | GRAY LS HARD |
| 108.0 | 134.0 | WHITE LS SOFT |
| 134.0 | 140.0 | BLUE LS HARD |
| 140.0 | 175.0 | WHITE LS SOFT |

*Comments* MC 580

250

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217281** | CENTE ROF THE SW 1/4 OF NW 1/4 OF N3 1/4 .5 MI W OF MARSHALL TWP SCHOOL | Wed, Jul 18, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DEAN PENNINGTON | RR4, BEDFORD, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD, IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 162.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 103.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 102.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NE 1/4 of Section 29 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2100 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1200
*Ground elevation:* 710.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 539629.0 *UTM Northing:* 4308897.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 40.0 | DIRT |
| 40.0 | 43.0 | BLUE LS HARD |
| 43.0 | 45.0 | RED CLAY |
| 45.0 | 70.0 | BROKEN LS & MUD SEAMS SOFT |
| 70.0 | 85.0 | BLUE LS HARD |
| 85.0 | 98.0 | BROKEN LS SOFT |
| 98.0 | 126.0 | BLUE LS SOFT |
| 126.0 | 138.0 | WHITE LS SOFT |
| 138.0 | 150.0 | BLUE LS SOFT |
| 150.0 | 162.0 | WHTIE LS SOFT |

*Comments* MC 67Page 9559

25D

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217286** | 1 MI S OF NEEDMORE | Wed, Jul 20, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | VON CRAIG | BEDFORD RR 3 IND. | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. RR 4 BOX 72 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 60.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 43.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 35.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the SE 1/4 of the SE 1/4 of Section 29 *Topo map:* OOLITIC
*Field located by:* IT -S *on:* Tue, Nov 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 400 *Ft N of SL:* 900 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 670.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 540174.0 *UTM Northing:* 4307941.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 43.0 | CLAY |
| 43.0 | 60.0 | LS |

***Comments*** MC630; CHEM ANALYSIS

152

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217291** | APP. 1/4 MI S OF NEEDMORE IND. & ON W SIDE OF SR37 | Wed, Nov 29, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BATOM EVANS | | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 17.5 | *Material:* | *Diameter:* 4.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the NE 1/4 of the SW 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 500 *Ft E of WL:* 2650 *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 541112.0 *UTM Northing:* 4308119.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 23.0 | BLUE LS EX HARD |
| 23.0 | 78.0 | WH LS SOFT |
| 78.0 | 100.0 | BLUE LS SOFT |

***Comments***

253

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217296** | AP 1/4 MI S OF NEEDMORE IND. ON SR37 AND ON E SIDE OF RD | Thu, Apr 05, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOE B. NORDHAFF | | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.8 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test* — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.2 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 75.0 ft.

*Grouting Information* — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Well Abandonment* — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Administrative*

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the SE 1/4 of Section 28 — *Topo map:* OOLITIC
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*

| | | | |
|---|---|---|---|
| *Ft W of EL:* 2400 | *Ft N of SL:* 1500 | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* 640.0 | *Depth to bedrock:* | *Bedrock elevation:* 635.0 | *Aquifier elevation:* |
| *UTM Easting:* 541161.0 | | *UTM Northing:* 4308119.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 4.0 | DIRT |
| 4.0 | 70.0 | BLUE LS HARD |
| 70.0 | 76.0 | WH LS SOFT |
| 76.0 | 92.0 | BR LS SOFT |
| 92.0 | 180.0 | WH LS SOFT |
| 180.0 | 184.0 | BLUE LS HARD |
| 184.0 | 200.0 | BLUE SH SOFT |

*Comments*

254

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217301** | AVOCA | Tue, Jul 07, 1953 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ELMER PATTON | | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR3 MITHCELL | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 114.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 39.5 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 4.0 gpm for hrs.
*Drawdown:* ft. — *Static water level:* ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the SE 1/4 of the SE 1/4 of Section 31 — *Topo map:* OOLITIC
*Field located by:* JRD — *on:* Tue, Aug 08, 1978
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* 750 — *Ft N of SL:* 1200 — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* 655.0 — *Depth to bedrock:* 35.0 — *Bedrock elevation:* 620.0 — *Aquifier elevation:*
*UTM Easting:* 538500.0 — *UTM Northing:* 4306438.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 35.0 | OVERBURDEN CLAY ROCKS |
| 35.0 | 39.0 | SOLID LS |
| 39.0 | 114.0 | LS |

***Comments*** MC620; ADDT'L CONST. INFO; NEIGHBOR VERIFIED; BREAK OR CREVICE @54-73'

255

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217306** | 2 MI W FROM OOLITIC ON SR54 TO GREEN LANE THEN 1 MI S | Wed, Dec 09, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JESSE STANLEY | 86 OOLITIC RD BEDFORD | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 46.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 4.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 76.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the SW 1/4 of Section 30 *Topo map:* OOLITIC
*Field located by:* JRD *on:* Tue, Aug 08, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 200 *Ft E of WL:* 100 *Ft S of NL:*
*Ground elevation:* 675.0 *Depth to bedrock:* 39.0 *Bedrock elevation:* 636.0 *Aquifier elevation:*
*UTM Easting:* 537041.0 *UTM Northing:* 4307704.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 39.0 | BOLDERS & CLAY |
| 39.0 | 58.0 | GRAY LIME MEDIUM |
| 58.0 | 69.0 | WH LS MEDIUM |
| 69.0 | 87.0 | GRAY LIME |
| 87.0 | 101.0 | WH LIME |

*Comments* MC636; OWNER VERIFIED/15 FT SW OF HOUSE

256

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217311** | AP. 1 MI W OF AVACA IND. ON SR54 | Fri, Jun 10, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GORDEN PORTER | SPRINGSVILLE RR 2 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 112.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 50.7 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.25 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 43.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the SE 1/4 of the SE 1/4 of Section 30 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* NO *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1150 *Ft N of SL:* 350 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 610.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 538357.0 *UTM Northing:* 4307755.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 48.0 | DIRT & LAYERS OF LS |
| 48.0 | 112.0 | GRAY LS NOT TO HARD |

*Comments* MC

# Record of Water Well

257

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217316** | 3/4 MI W OF AVACO ON SR54 | Tue, Jul 12, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ORDA O. TURNER & PEARL | SPRINGSVILLE RR 2 IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 18.25 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter:* 18.25 *Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 15.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the SE 1/4 of Section 30 *Topo map:* OOLITIC
*Field located by:* H - S *on:* Wed, Nov 01, 1961
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1700 *Ft N of SL:* 200 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 590.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 538193.0 *UTM Northing:* 4307724.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 15.0 | SJELLIE LS |
| 15.0 | 30.0 | HARD BLUE LS |
| 30.0 | 90.0 | GRAY LS SOFT |
| 90.0 | 100.0 | HARD BLUE LS |

***Comments*** MC585; CHEM ANALYSIS

# Record of Water Well

258

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217321** | APP. 2 MI W OF NEEDMORE IND. | Fri, May 24, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MAUDE HOTZ | RR #4 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. RR 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | ***Use:*** HOME | ***Drilling method:*** CABLE TOOL | ***Pump type:*** |
| | ***Depth:*** 165.0 | ***Pump setting depth:*** | ***Water quality:*** |
| Casing | ***Length:*** 77.0 | ***Material:*** | ***Diameter:*** 6.0 |
| Screen | ***Length:*** | ***Material:*** | ***Diameter: Slot size:*** |

***Well Capacity Test*** ***Type of test:*** ***Test rate:*** gpm for hrs. ***BailTest rate:*** 0.5 gpm for hrs.
***Drawdown:*** ft. ***Static water level:*** 60.0 ft.

***Grouting Information*** ***Material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Well Abandonment*** ***Sealing material:*** ***Depth:*** from to
***Installation Method:*** ***Number of bags used:***

***Administrative***

***County:*** LAWRENCE ***Township:*** 6N ***Range:*** 1W
***Section:*** SW 1/4 of the NE 1/4 of the NW 1/4 of Section 29 ***Topo map:*** OOLITIC
***Field located by:*** JCH ***on:*** Mon, Aug 01, 1966
***Courthouse location by:*** ***on:***
***Location accepted w/o verification by:*** ***on:***
***Subdivision name:*** ***Lot number:***
***Ft W of EL:*** ***Ft N of SL:*** ***Ft E of WL:*** 1000 ***Ft S of NL:*** 1300
***Ground elevation:*** 690.0 ***Depth to bedrock:*** ***Bedrock elevation:*** 661.0 ***Aquifier elevation:***
***UTM Easting:*** 539142.0 ***UTM Northing:*** 4308878.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 33.0 | DIRT |
| 33.0 | 71.0 | BOULDERS & MUD HOLES |
| 71.0 | 90.0 | WH LS HARD |
| 90.0 | 122.0 | BLUE LS HARD |
| 122.0 | 165.0 | WH LS SOFT |

***Comments*** MC660

259

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217326** | APP. 1 1/2 MI NE OF AVOCA IND. ON N PIKE RD | Fri, Apr 10, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ARTHUR SYKES | SPRINGVILLE IND. R 2 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. RR 6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 161.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.1 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 66.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the NW 1/4 of the SW 1/4 of Section 29 — *Topo map:* OOLITIC
*Field located by:* JCH — *on:* Mon, Aug 01, 1966
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 2400 — *Ft E of WL:* 100 — *Ft S of NL:*
*Ground elevation:* 665.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* 538722.0 — *UTM Northing:* 4308383.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 101.0 | BLANK |
| 101.0 | 125.0 | WH LS SOFT |
| 125.0 | 143.0 | BLUE LS HARD |
| 143.0 | 159.0 | GRAY LS HARD |
| 159.0 | 161.0 | BLUE LS HARD |

***Comments*** MC

# Record of Water Well

260

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217331** | .5 MI W AVOCA FISH HATCHERY ON EURICA RD | Sun, Apr 24, 1960 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | ELMER PATON | AVOCA, IN | |
| Building Contractor | | | |
| Drilling Contractor | ELMER ATFORD | MITCHELL, IN | |
| Equipment Operator | ELMER ATFORD | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 91.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* PUMPING *Test rate:* 11.0 gpm for hrs. *BailTest rate:* gpm for 0.5 hrs.
*Drawdown:* ft. *Static water level:* 18.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the SW 1/4 of the SW 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 600 *Ft N of SL:* 1000 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 650.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 538524.0 *UTM Northing:* 4306371.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 57.0 | CLAY & BOULDERS |
| 57.0 | 91.0 | LIME GRAY |

*Comments*

# Record of Water Well

261

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217336** | APPROX. STARTING AT THE JCT OF SR58 & GREEN LANE WELL LIES 1.2 MI S OF SR58 103 FT E OF THE CENTER OF GREEN LANE | Sat, Jul 23, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | KEITH S DAVIS | RR #2 SPRINGVILLE | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD | |
| Equipment Operator | ERNIE UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 103.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 95.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 10.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 63.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the SW 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* S&H *on:* Tue, Nov 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1400 *Ft E of WL:* 100 *Ft S of NL:*
*Ground elevation:* 670.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 537055.0 *UTM Northing:* 4306503.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 95.0 | MUD HOLES & LS & BOULDERS |
| 95.0 | 103.0 | WH LS SOFT |

*Comments* MC

262

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217337** | 5 MI N OF BEDFORD ON PEERLESS RD 1 MI NW OF MT PLEASANT CHURCH | |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | DON STULTZ | BEDFORD RR 4 IND. | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | R #4 BEDFORD IND. | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 10.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* 1.0 gpm for 8.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 20.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the SE 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2600 *Ft N of SL:* 1900 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 650.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 541112.0 *UTM Northing:* 4308247.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | CLAY |
| 10.0 | 105.0 | HARD LS |

***Comments***

263

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217341** | ON SR 54 IT IS ON THE L SIDE OF TOWN ON THE HILL | |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GEORGE SARGENT | SPRINGVILLE | |
| Building Contractor | | | |
| Drilling Contractor | HAROLD JACKSON | 1516 E TIPTON, SYCAMORE, IN | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 114.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 45.0 | *Material:* | *Diameter:* 4.5 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the NE 1/4 of the NE 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 200 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 700
*Ground elevation:* 575.0 *Depth to bedrock:* *Bedrock elevation:* 530.0 *Aquifier elevation:*
*UTM Easting:* 538656.0 *UTM Northing:* 4307408.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 45.0 | RED CLAY |
| 45.0 | 75.0 | WHITE LIME |
| 75.0 | 114.0 | BLUE LIME & SH |

***Comments*** MC 530

264

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217342** | NEEDMORE ON HIGHWAY 37 S OF NEEDMORE | Wed, Jun 26, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DELBERT STEWART | | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. RR 4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 174.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 22.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 70.0 ft.

*Grouting Information*: *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*: *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the SW 1/4 of Section 28 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2000 *Ft E of WL:* 2000 *Ft S of NL:*
*Ground elevation:* 650.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 541075.0 *UTM Northing:* 4308284.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 22.0 | CLAY |
| 22.0 | 112.0 | SOFT LS |
| 112.0 | 174.0 | HARD LS |

*Comments*

# Record of Water Well

265

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223245** | 20' W OF N PIKE RD 100' E OF SR 54 | Wed, Sep 20, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HARVEY G HOLMES | AVOCA, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD, IN | |
| Equipment Operator | ERNIE UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 79.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 24.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 6.0 gpm for 7.0 hrs.
*Drawdown:* ft. *Static water level:* 39.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the NE 1/4 of the NE 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 100 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 400
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 538675.0 *UTM Northing:* 4307517.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 6.0 | DIRT |
| 6.0 | 20.0 | WHELLER LS |
| 20.0 | 79.0 | WHITE LS |

*Comments*

# Record of Water Well

2606

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223250** | | Tue, Jul 20, 1954 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | WENDELL TURNER | | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR3 MITHCELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 95.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 17.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* | *Test rate:* gpm for hrs. | *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. | *Static water level:* 45.0 ft.

*Grouting Information*: *Material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Well Abandonment*: *Sealing material:* | *Depth:* from to
*Installation Method:* | *Number of bags used:*

*Administrative*

| | | | |
|---|---|---|---|
| *County:* LAWRENCE | | *Township:* 6N *Range:* 1W | |
| *Section:* NW 1/4 of the SE 1/4 of the NE 1/4 of Section 31 | | | *Topo map:* OOLITIC |
| *Field located by:* JRD | | *on:* Tue, Aug 08, 1978 | |
| *Courthouse location by:* | | *on:* | |
| *Location accepted w/o verification by:* | | *on:* | |
| *Subdivision name:* | | *Lot number:* | |
| *Ft W of EL:* 700 | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* 1400 |
| *Ground elevation:* 615.0 | *Depth to bedrock:* 15.0 | *Bedrock elevation:* 600.0 | *Aquifier elevation:* |
| *UTM Easting:* 538486.0 | | *UTM Northing:* 4307218.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 15.0 | OVERBURDEN CLAY ROCK |
| 15.0 | 17.0 | SOLID ROCK |
| 17.0 | 95.0 | LS |

*Comments*: MC600; WELL HAS 100 GAL RESERVE CAP.; OWNER VERIFED/15' S OF HOUSE

# Record of Water Well

267

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223255** | 25' W OF BIOLOGIST'S RESIDENCE | |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DNR AVOCA FISH HATCHERY | AVOCA, IN | |
| Building Contractor | | | |
| Drilling Contractor | | | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* | *Pump type:* |
| | *Depth:* 130.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

| | | | |
|---|---|---|---|
| *Well Capacity Test* | *Type of test:* | *Test rate:* 6.0 gpm for hrs. | *BailTest rate:* gpm for hrs. |
| | *Drawdown:* ft. | *Static water level:* 25.0 ft. | |

| | | |
|---|---|---|
| *Grouting Information* | *Material:* | *Depth:* from to |
| | *Installation Method:* | *Number of bags used:* |

| | | |
|---|---|---|
| *Well Abandonment* | *Sealing material:* | *Depth:* from to |
| | *Installation Method:* | *Number of bags used:* |

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W

*Section:* 1/4 of the 1/4 of the SW 1/4 of Section 32 *Topo map:* OOLITIC

| | | | |
|---|---|---|---|
| *Field located by:* | | *on:* | |
| *Courthouse location by:* | | *on:* | |
| *Location accepted w/o verification by:* | | *on:* | |
| *Subdivision name:* | | *Lot number:* | |
| *Ft W of EL:* | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* | *Depth to bedrock:* | *Bedrock elevation:* | *Aquifer elevation:* |
| *UTM Easting:* 539177.0 | | *UTM Northing:* 4306598.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | NO INFORMATION |

*Comments* CHEMICAL ANALYSIS

# Record of Water Well

268

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223260** | | Thu, May 31, 1951 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BARRETT | SOUTH AVOCA | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR3 MITHCELL | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 98.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 44.5 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.0 gpm for 0.5 hrs.
*Drawdown:* ft. *Static water level:* 32.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the SE 1/4 of the SE 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* JRD *on:* Tue, Aug 08, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 700 *Ft N of SL:* 850 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 640.0 *Depth to bedrock:* 44.0 *Bedrock elevation:* 596.0 *Aquifer elevation:*
*UTM Easting:* 538506.0 *UTM Northing:* 4306322.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 44.5 | OVERBURDERN CLAY BOULDERS |
| 44.5 | 98.0 | LS |

***Comments*** MC596; WELL HAS RESERVE CAP. OF 100 GAL.; PREVIOUS OWNER VERIFIED/SW OFHOUSE

269

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223265** | AP. 2 MI W OF AVOCA IND. | Tue, Jun 07, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | GAROLD BRENT (ASK E TURNER) | SPRINGVILLE IND. RR 6 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 121.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 66.7 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.5 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 71.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the NW 1/4 of the NE 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* NO *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1800 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1100
*Ground elevation:* 650.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 538145.0 *UTM Northing:* 4307273.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 65.0 | DIRT & LAYERS OF LS |
| 65.0 | 101.0 | BUFF LS SOFT |
| 101.0 | 121.0 | WH LS HARD |

*Comments* MC

270

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223270** | APP. 2 MI W OF AVOCA IND. ON US HIGHWAY 54 TO 1ST RD S TOWNSHIP RD APP. 1/2 MI S ON E SIDE OF RD | Wed, Nov 11, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DOYLE JONES | SPRINGVILLE RR 1 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 108.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 69.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.9 gpm for hrs.
*Drawdown:* ft. *Static water level:* 68.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NW 1/4 of the NW 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 100 *Ft S of NL:* 1200
*Ground elevation:* 670.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 538675.0 *UTM Northing:* 4307274.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 70.0 | LS BOULDERS & MUD HOLES |
| 70.0 | 79.0 | BLUE LS HARD |
| 79.0 | 85.0 | GRAY LS SOFT |
| 85.0 | 108.0 | BLUE LS HARD |

*Comments*

271

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223275** | AVOCA IND. APP. 2 BLOCKS N OF US POST OFFICE ON SR54 E SIDE OF RD | Wed, Sep 25, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CLOVIS MAY | AVOCA IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD IND. | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 128.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 6.3 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 20.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the SW 1/4 of the NW 1/4 of Section 32 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 700 *Ft S of NL:* 1830
*Ground elevation:* 560.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 538919.0 *UTM Northing:* 4307085.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DIRT |
| 3.0 | 12.0 | BLUE LS HARD |
| 12.0 | 37.0 | GRAY LS SOFT |
| 37.0 | 48.0 | BLUE LS SOFT |
| 48.0 | 61.0 | GRAY LS SOFT |
| 61.0 | 99.0 | BLUE LS SOFT |
| 99.0 | 128.0 | GRAY LS HARD |

*Comments*

272

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223280** | ADJOINING AVOCA STATE FISH HATCHERY ON EAST | Fri, Jul 29, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HOMER ROLLINS | AVOCA IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 119.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 10.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 0.5 gpm for 1.0 hrs.
*Drawdown:* ft. — *Static water level:* 14.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SW 1/4 of Section 32 — *Topo map:* OOLITIC
*Field located by:* S & H — *on:* Tue, Nov 01, 1960
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* 2500 — *Ft E of WL:* 1000 — *Ft S of NL:*
*Ground elevation:* 565.0 — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* 539017.0 — *UTM Northing:* 4306860.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DIRT |
| 3.0 | 8.0 | SHELLIE LS |
| 8.0 | 40.0 | BLUE LS |
| 40.0 | 100.0 | WH LS |
| 100.0 | 119.0 | BLUE LS HARD |

***Comments*** MC

273

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223285** | E SIDE OF AVOCA 1/4 MI FROM H WAY 54 IN AVOCA | Thu, Dec 01, 1966 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MAURICE GRAVES | AVOCA | |
| Building Contractor | | | |
| Drilling Contractor | RAY E. ALFORD | RR 2 MITCHELL | |
| Equipment Operator | RAY E. ALFORD | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 117.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.0 | *Material:* | *Diameter:* 6.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 7.0 gpm for hrs.
*Drawdown:* ft. — *Static water level:* ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the NW 1/4 of the NW 1/4 of Section 32 — *Topo map:* OOLITIC
*Field located by:* JRD — *on:* Tue, Aug 08, 1978
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* 1000 — *Ft S of NL:* 900
*Ground elevation:* 615.0 — *Depth to bedrock:* 8.0 — *Bedrock elevation:* 607.0 — *Aquifier elevation:*
*UTM Easting:* 538992.0 — *UTM Northing:* 4307359.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | SOIL CLAY |
| 8.0 | 28.0 | SHELLY LIME & SS |
| 28.0 | 87.0 | GRAY LIME MD |
| 87.0 | 117.0 | WH LIME MD |

***Comments*** MC607: OWNER VERIFIED/NE CORNER OF HOUSE

274

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223290** | AVOCA SR54 ACROSS FROM BRANCH EAST STATE FISH HATCHERY | Mon, Oct 05, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LEX FRANKLIN | AVOCA IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD IND. | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 89.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 9.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.2 gpm for 1.0 hrs.
*Drawdown:* 68.0 ft. *Static water level:* 81.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 32 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* NO *on:*
*Subdivision name:* *Lot number:*

| | | | |
|---|---|---|---|
| *Ft W of EL:* 3650 | *Ft N of SL:* 1600 | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* 560.0 | *Depth to bedrock:* | *Bedrock elevation:* | *Aquifier elevation:* |
| *UTM Easting:* 539231.0 | | *UTM Northing:* 4306622.0 | |

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | DIRT |
| 3.0 | 7.0 | BROKEN LS |
| 7.0 | 40.0 | GRAY LIME SOFT |
| 40.0 | 60.0 | BLUE LIME SOFT |
| 60.0 | 89.0 | BUFF SOFT |

***Comments*** MC580

# Record of Water Well

275

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223295** | ACROSS THE STREET FROM AVOCA BAPTIST CHURCH PARSONAGE | Wed, May 04, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RUSSEL TURNER | | |
| Building Contractor | | | |
| Drilling Contractor | WINFRED PHILLIPS | RR #5 BEDFORD IND. | |
| Equipment Operator | WINFRED PHILLIPS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 88.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 28.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 35.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NW 1/4 of Section 32 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Fri, Jul 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* NO *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1200 *Ft S of NL:* 2100
*Ground elevation:* 590.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 539078.0 *UTM Northing:* 4306994.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 28.0 | RED CLAY |
| 28.0 | 45.0 | BLUE LIME |
| 45.0 | 65.0 | BR LIME |
| 65.0 | 88.0 | SOFT WH LIME |

*Comments* MC; I COULD NOT LOWER WATER IN THIS WELL IWTH 2 GAL. BAILER

# Record of Water Well

276

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223300** | APP. .5 MI NE OF AVOCA POST OFFICE AT AVOCA IND. | Thu, Oct 21, 1965 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT & THOMAS BUNCH | AVOCA IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 103.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 75.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 90.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the NW 1/4 of Section 32 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1200 *Ft S of NL:* 600
*Ground elevation:* 640.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 539065.0 *UTM Northing:* 4307482.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 14.0 | DIRT |
| 14.0 | 70.0 | BOULDERS & MUD HOLES |
| 70.0 | 97.0 | GRAY LS HARD |
| 97.0 | 103.0 | BLUE LS HARD |

*Comments* MC630

# Record of Water Well

277

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223315** | IN AVOCA ON LOTS 55 & 56 OF BRIDWELL ADD, APPROX 1 BLOCK OFF STATE HWY 54 & 58 | Thu, Sep 06, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT OR LINDA CHARELS | ANOCA, IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR6, BEDFORD, IN | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 217.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.1 gpm for hrs.
*Drawdown:* ft. *Static water level:* 97.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 32 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2300 *Ft E of WL:* 1400 *Ft S of NL:*
*Ground elevation:* 580.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 539139.0 *UTM Northing:* 4306775.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 16.0 | DIRT |
| 16.0 | 52.0 | BLUE LS HARD |
| 52.0 | 97.0 | GRAY LS HARD |
| 97.0 | 115.0 | GRAY LS SOFT |
| 115.0 | 130.0 | BLUE LS HARD |
| 130.0 | 175.0 | GRAY LS HARD |
| 175.0 | 206.0 | BLUE LS SOFT |
| 206.0 | 217.0 | BLUE SH SOFT |

*Comments*

278

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223320** | 1 1/2 MI N OF OOLITIC ON NEW HIGHWAY 37 1/4 MI N OF AVOCA BLINKER LIGHT ON NEW HIGHWAY 37 ON E SIDE OF HIGHWAY 37 PART OF THE JAMES MILLER LAND | Wed, Dec 04, 1974 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CHARLES MILLER | BEDFORD IND. RR | |
| Building Contractor | | | |
| Drilling Contractor | RAY E. ALFORD | MITCHELL IND. RR 2 | |
| Equipment Operator | RAY E. ALFORD | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 34.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 32 *Topo map:* OOLITIC
*Field located by:* JRD *on:* Tue, Aug 08, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1800 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2400
*Ground elevation:* 660.0 *Depth to bedrock:* 42.0 *Bedrock elevation:* 618.0 *Aquifier elevation:*
*UTM Easting:* 539779.0 *UTM Northing:* 4306928.0

*Well Log.*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 42.0 | SOIL & CLAY |
| 42.0 | 53.0 | HARD GRAY LIME HARD |
| 53.0 | 64.0 | BR BUFF LIME SOFT |
| 64.0 | 170.0 | GRAY LIME MD LITTLE WATER |
| 170.0 | 174.0 | YEL SOAPSTONE LITTLE W |
| 174.0 | 200.0 | HARD WH LIME |

*Comments* MC618; NEIGHBOR VERIFIED

279

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **223325** | ACROSS FROM AVOCA FISH HATCHERY | Wed, May 13, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | EVA CRULS | AVOCA IND. | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 BOX 13 BEDFORD IND. | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 166.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 54.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 93.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SW 1/4 of Section 32 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2450 *Ft E of WL:* 1100 *Ft S of NL:*
*Ground elevation:* 565.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 539042.0 *UTM Northing:* 4306823.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 24.0 | DIRT |
| 24.0 | 53.0 | BOULDERS & MUD HOLES |
| 53.0 | 104.0 | GRAY LS HARD |
| 104.0 | 139.0 | BLUE LS SOFT |
| 139.0 | 166.0 | WH LS HARD |

***Comments***

280

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217287** | LOGAN 8 MI N OF BEDFORD ON MONON RR FORMERLY CALL GRAYSON | Wed, Aug 05, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CARL HARTMAN | BEDFORD IND. RR 3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. RR 4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* | *Pump type:* |
| | *Depth:* 220.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 9.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* 0.05 gpm for 8.0 hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SE 1/4 of Section 22 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2800 *Ft E of WL:* 3900 *Ft S of NL:*
*Ground elevation:* 580.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 543041.0 *UTM Northing:* 4310049.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 9.0 | CLAY |
| 9.0 | 45.0 | LS |
| 45.0 | 220.0 | SOAPSTONE |

***Comments***

281

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217292** | AT LOGAN OR GRAYSON 7 MI N OF BEDFORD ON RR 3 | Mon, Nov 04, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | IRA SHERRILL | BEDFORD IND. RR 3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD IND. RR 4 | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 190.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 13.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 40.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the SW 1/4 of the NE 1/4 of Section 22 *Topo map:* OOLITIC
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 2800 *Ft S of NL:* 2200
*Ground elevation:* 590.0 *Depth to bedrock:* *Bedrock elevation:* 580.0 *Aquifier elevation:*
*UTM Easting:* 542730.0 *UTM Northing:* 4310207.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 13.0 | CLAY |
| 13.0 | 190.0 | SOAPSTONE |

***Comments*** MC580

282

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217297** | 1 MI N OF NEEDMORE ON SR37 | Thu, Jul 14, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LARRY STEWART | BEDFORD IND. RR 3 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | BEDFORD, IND. RR 4 BOX 72 | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 175.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 27.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*: *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* gpm for 8.0 hrs.
*Drawdown:* ft. — *Static water level:* 70.0 ft.

*Grouting Information*: *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Well Abandonment*: *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

*Administrative*

| | | | |
|---|---|---|---|
| *County:* LAWRENCE | | *Township:* 6N *Range:* 1W | |
| *Section:* NE 1/4 of the SW 1/4 of the NW 1/4 of Section 21 | | | *Topo map:* OOLITIC |
| *Field located by:* S & H | | *on:* Tue, Nov 01, 1960 | |
| *Courthouse location by:* | | *on:* | |
| *Location accepted w/o verification by:* | | *on:* | |
| *Subdivision name:* | | *Lot number:* | |
| *Ft W of EL:* | *Ft N of SL:* | *Ft E of WL:* | *Ft S of NL:* |
| *Ground elevation:* 615.0 | *Depth to bedrock:* | *Bedrock elevation:* | *Aquifier elevation:* |
| *UTM Easting:* 540462.0 | | *UTM Northing:* 4310453.0 | |

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 26.0 | CLAY |
| 26.0 | 175.0 | LS HARD |

*Comments*: MC590

283

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217317** | 8 MI N OF BEDFORD RR 4 JUDAH LOGAN RD | Sat, Apr 11, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RALPH LUALLEN | BEDFORD IND. RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4 BOX 72 BEDFORD INDIANA | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 135.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 9.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.3 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 60.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NW 1/4 of the NE 1/4 of the SW 1/4 of Section 24 *Topo map:* BARTLETTSVILLE
*Field located by:* JCH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 1900 *Ft S of NL:* 2700
*Ground elevation:* 645.0 *Depth to bedrock:* 10.0 *Bedrock elevation:* 635.0 *Aquifier elevation:*
*UTM Easting:* 545704.0 *UTM Northing:* 4310119.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 8.0 | CLAY |
| 8.0 | 75.0 | LS |
| 75.0 | 135.0 | SOAPSTONE |

*Comments* MC635

284

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217322** | FRANK GOODMAN PLACE 7 MI N OF BEDFORD ON LOGAN RD | Fri, Jun 15, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | CLOYD PRINCE | BEDFORD RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4 BOX 72 BEDFORD INDIANA | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 90.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 3.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** *Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 10.0 hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

***Grouting Information*** *Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment*** *Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the NW 1/4 of the SW 1/4 of Section 24 *Topo map:* BARTLETTSVILLE
*Field located by:* U *on:* Mon, Jul 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 2100 *Ft E of WL:* 700 *Ft S of NL:*
*Ground elevation:* 690.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 545362.0 *UTM Northing:* 4309955.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 3.0 | CLAY |
| 3.0 | 80.0 | HARD LS |

***Comments*** MC685

285

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217327** | LOGAN COMMUNITY (OR GRAYSON) 8 MI N OF BEDFORD & E OF LITTLE SALT CREEK AT OLD HOUSE SITE | Sat, Aug 24, 1963 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | RALPH ALLEN | BEDFORD RR 4 | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4 BOX 72 BEDFORD INDIANA | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 12.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* SW 1/4 of the NE 1/4 of the SW 1/4 of Section 24 *Topo map:* BARTLETTSVILLE
*Field located by:* U *on:* Tue, Oct 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1800 *Ft E of WL:* 1500 *Ft S of NL:*
*Ground elevation:* 655.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 545582.0 *UTM Northing:* 4309918.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | CLAY |
| 12.0 | 100.0 | HARD LS |

***Comments*** MC645: NEIGHBOR

286

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217332** | ON THE PEERLESS & JUDAH RD ON R #3 BEDFORD INDIANA | Wed, Jul 08, 1959 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | DON BLACKWELL | R #3 BEDFORD IND. | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4 BOX 72 BEDFORD INDIANA | |
| Equipment Operator | FLOYD STULTZ | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 12.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.3 gpm for hrs.
*Drawdown:* ft. *Static water level:* 50.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* NE 1/4 of the SE 1/4 of the SW 1/4 of Section 22 *Topo map:* OOLITIC
*Field located by:* BARNES *on:* Mon, Aug 01, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* 1000 *Ft E of WL:* 2000 *Ft S of NL:*
*Ground elevation:* 630.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 542499.0 *UTM Northing:* 4309615.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | CLAY |
| 12.0 | 100.0 | HARD LS |

*Comments* MC620

# Record of Water Well

287

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217671** | 2MILES SOUTH OF HELTONVILLE AND ABOUT 1/4 MI W OF TODD LANE | Fri, May 04, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT FLEETWOOD | HELTONVILLE | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BEDFORD IN | |
| Equipment Operator | E. & C. UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 170.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 16.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* SE 1/4 of the SE 1/4 of the NE 1/4 of Section 33 *Topo map:* BARTLETTSVILLE
*Field located by:* UHL *on:* Sat, Jun 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 25 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2500
*Ground elevation:* 670.0 *Depth to bedrock:* 13.0 *Bedrock elevation:* 657.0 *Aquifier elevation:*
*UTM Easting:* 551623.0 *UTM Northing:* 4306912.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 13.0 | DIRT |
| 13.0 | 170.0 | BLUE SHALE |

*Comments* MC660; DRY HOLE

# Record of Water Well

288

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217701** | 4 MI WEST OF HELTONVILLE. 6 MI N.E. OF BEDFORD. ONE QUARTER NORTH OF PLEASANT RUN CHURCH | Fri, Oct 05, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | EARL M. STIPP | BEDFORD, IND R.R.3 | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | BEDFORD IND. RR6 | |
| Equipment Operator | EUGENE & CHARLES UMPHRESS | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 140.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 17.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* BAILING *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 100.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* NW 1/4 of the SW 1/4 of the NE 1/4 of Section 29 *Topo map:* BARTLETTSVILLE
*Field located by:* UHL *on:* Sat, Jun 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* 100 *Ft S of NL:* 1400
*Ground elevation:* 730.0 *Depth to bedrock:* 14.0 *Bedrock elevation:* 716.0 *Aquifer elevation:*
*UTM Easting:* 548406.0 *UTM Northing:* 4308874.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 14.0 | BROKEN LS & HOLES |
| 14.0 | 20.0 | BLUE LS - HARD |
| 20.0 | 29.0 | WHITE LS - HARD |
| 29.0 | 50.0 | BR LS - SOFT |
| 50.0 | 75.0 | WHITE LS - HARD |
| 75.0 | 86.0 | BLUE LS - HARD |
| 86.0 | 120.0 | WHITE LS - HARD |
| 120.0 | 126.0 | BLUE LS - HARD |
| 126.0 | 132.0 | WHITE LS |
| 132.0 | 140.0 | BLUE LS |

***Comments*** MC715

# Record of Water Well

289

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217706** | 8 MILES NORTH EAST OF BEDFORD 2-1/2 MILES SOUTHWEST OF HELTONVILLE | Thu, Aug 04, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HAROLD DENISTON | RR 4, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | PAUL SCOTT | RR 4, BLOOMINGTON | |
| Equipment Operator | PAUL SCOTT | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 110.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 12.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 75.0 gpm for 1.0 hrs.
*Drawdown:* ft. *Static water level:* 16.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* SW 1/4 of the NE 1/4 of the NE 1/4 of Section 28 *Topo map:* BARTLETTSVILLE
*Field located by:* N-3 *on:* Fri, Nov 04, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 900 *Ft N of SL:* 2150 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 745.0 *Depth to bedrock:* 12.0 *Bedrock elevation:* 733.0 *Aquifier elevation:*
*UTM Easting:* 551327.0 *UTM Northing:* 4308943.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | BLANK |
| 12.0 | 60.0 | GRAY LIME MEDIUM |
| 60.0 | 110.0 | BLUE SOAPSTONE SOFT |

***Comments*** MC735

# Record of Water Well

290

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217711** | 3 MILES FROM HELTONVILLE ON PLEASANT RUN ROAD WEST | Mon, Feb 12, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HERMAN DECKARD | HELTONVILLE IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6, BEDFORD IN | |
| Equipment Operator | ERNIE UMPHRESS & SONS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 100.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 16.5 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 4.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* NE 1/4 of the SW 1/4 of the NW 1/4 of Section 28 *Topo map:* BARTLETTSVILLE
*Field located by:* UHL *on:* Sat, Jun 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1500 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1600
*Ground elevation:* 765.0 *Depth to bedrock:* 15.0 *Bedrock elevation:* 750.0 *Aquifier elevation:*
*UTM Easting:* 551175.0 *UTM Northing:* 4308824.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | DIRT |
| 12.0 | 15.0 | LIMESTONE BOULDERS |
| 15.0 | 40.0 | LIMESTONE BLUE HARD |
| 40.0 | 43.0 | LIMESTONE WHITE SOFT |
| 43.0 | 54.0 | LIMESTONE BLUE HARD |
| 54.0 | 60.0 | LIMESTONE BROWN HARD |
| 60.0 | 76.0 | LIMESTONE BLUE HARD |
| 76.0 | 100.0 | SHALE BLUE SOFT |

*Comments* MC750

291

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217608** | 8 MILES NORTH OF BEDFORD BARTLETTSVILLE ROAD | Thu, Jul 28, 1960 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROBERT TURNER | RR 3, BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | PAUL SCOTT | RR 4, BLOOMINGTON IN | |
| Equipment Operator | PAUL SCOTT | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 95.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 11.0 | *Material:* | *Diameter:* 6.5 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 60.0 gpm for 0.5 hrs.
*Drawdown:* ft. *Static water level:* 15.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the NW 1/4 of Section 20 *Topo map:* BARTLETTSVILLE
*Field located by:* HS *on:* Fri, Nov 04, 1960
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 535.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 548398.0 *UTM Northing:* 4310285.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 10.0 | BLANK |
| 10.0 | 65.0 | BLUE SOAPSTONE SOFT |
| 65.0 | 95.0 | WHITE LIME MEDIUM |

***Comments*** MC

# Record of Water Well

292

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217613** | APP. 1-1/4 MI NE OF PLEASANT RUN CHURCH | Tue, Dec 11, 1962 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHN HEARTH | BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ERNIE UMPHRESS & SONS | RR 6 ,BEDFORD IN | |
| Equipment Operator | E. & C. UMPHRESS | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* STOCK | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 260.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 10.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.1 gpm for hrs.
*Drawdown:* ft. *Static water level:* 155.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* SW 1/4 of the SW 1/4 of the SE 1/4 of Section 20 *Topo map:* BARTLETTSVILLE
*Field located by:* UHB *on:* Sat, Jun 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2100 *Ft N of SL:* 150 *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* 770.0 *Depth to bedrock:* 8.0 *Bedrock elevation:* 762.0 *Aquifer elevation:*
*UTM Easting:* 549348.0 *UTM Northing:* 4309398.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | DIRT |
| 5.0 | 8.0 | BOULDERS & HOLES |
| 8.0 | 20.0 | BLUE LIMESTONE HARD |
| 20.0 | 36.0 | GRAY LIMESTONE SOFT |
| 36.0 | 54.0 | BLUE LIMESTONE HARD |
| 54.0 | 58.0 | BROWN LIMESTONE HARD |
| 58.0 | 63.0 | BLUE SHALE SOFT |
| 63.0 | 76.0 | BLUE LIMESTONE HARD |
| 76.0 | 91.0 | BROWN LIMESTONE HARD |
| 91.0 | 94.0 | MUCHY SHALE SOFT |
| 94.0 | 115.0 | GRAY LIMESTONE HARD |
| 115.0 | 137.0 | BLUE LIMESTONE SOFT |
| 137.0 | 260.0 | BLUE SHALE SOFT |

*Comments* MC760

# Record of Water Well

293

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217618** | BARTLESTTSVILLE & BEDFORD ROAD BAT HOLLOW LAKE | Sat, Feb 08, 1964 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ROY SCHERSCHEL | RR 3 BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | FLOYD STULTZ | RR 4, BEDFORD IN | |
| Equipment Operator | FLOYD STULTZ | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 200.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 5.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* -1.0 gpm for 8.0 hrs.
*Drawdown:* ft. *Static water level:* 150.0 ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* NW 1/4 of the SW 1/4 of the NE 1/4 of Section 19 *Topo map:* BARTLETTSVILLE
*Field located by:* JVH *on:* Mon, Aug 01, 1966
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2300 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1600
*Ground elevation:* 640.0 *Depth to bedrock:* 5.0 *Bedrock elevation:* 635.0 *Aquifier elevation:*
*UTM Easting:* 547659.0 *UTM Northing:* 4310429.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | CLAY |
| 5.0 | 95.0 | LIMESTONE |
| 95.0 | 200.0 | SOAPSTONE |

***Comments*** MC635:

294

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217623** | 1 MI SOUTH OF BARLTETT IN ON TOP OF HILL AT HAIR PIN CURVE 160 FT W OF TURN IN ROAD IN FRONT YD OF 3-BD. NEW HOME ABOUT 30' E OF N END OF HOME | Thu, Jun 15, 1961 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | LEBERT STARR | RR 3 BEDFORD IN | |
| Building Contractor | | | |
| Drilling Contractor | ALBERT LENTZ | BOX 83, SMITHVILLE IN | |
| Equipment Operator | B. ERIE 20W | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 260.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 6.0 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

***Grouting Information***

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 6N *Range:* 1E
*Section:* NW 1/4 of the SW 1/4 of the NE 1/4 of Section 18 *Topo map:* BARTLETTSVILLE
*Field located by:* UHL *on:* Sat, Jun 01, 1963
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 2300 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 1700
*Ground elevation:* 610.0 *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* 547633.0 *UTM Northing:* 4311958.0

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 0.0 | NO INFORMATION |

***Comments*** MC580

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217346** | AVOCA | Fri, Apr 02, 1954 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | HILLTOP PENTECOSTAL CHURCH | | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR3 MITHCELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 130.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 30.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* 1/4 of the 1/4 of the 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 538584.0 *UTM Northing:* 4306798.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 25.0 | OVERBURDEN CLAY ROCKS |
| 25.0 | 30.0 | SOLID ROCK |
| 30.0 | 130.0 | LS |

*Comments* WELL HAS RESERVE OF 60 GAL.; SOME SULPHUR WATER 89-90'

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217351** | NEAREST TOWN AVOCA | |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | DR. BENHAM | | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR3 MITHCELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 131.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 15.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 12.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* 36.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 6N *Range:* 1W
*Section:* 1/4 of the 1/4 of the 1/4 of Section 31 *Topo map:* OOLITIC
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* 538724.0 *UTM Northing:* 4307097.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 12.0 | OVERBURDEN CLAY ROCKS |
| 12.0 | 15.0 | SOLID ROCK |
| 15.0 | 131.0 | LS |

*Comments*

# Record of Water Well

Indiana Department of Natural Resources

*Reference Number*
**291792**

*Driving directions to well*
4 MI. S.E. BEDFORD

*Date completed*

*Owner-Contractor*

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | COUNTY PROPERTY | OLD POOR FARM | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* DOMESTIC | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 145.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*
*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 2.0 gpm for 6.0 hrs.
*Drawdown:* ft. *Static water level:* 24.0 ft.

*Grouting Information*
*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*
*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*
*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* 1/4 of the 1/4 of the 1/4 of Section 30 *Topo map:*
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* 122.0 *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 23.0 | CLAY & BOULDERS |
| 23.0 | 145.0 | LIME |

*Comments*

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **294237** | TAKE 50 E TOWARD BEDFORD GO N ON HWY30 AS SOON AS Y0U CROSS WHITE RIVER TURN BACK E (SANDPORT RD) GO TO ICE RD GO N APPROX 2 MI TURN ON (SEE COMMENTS) | Fri, May 26, 1995 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | BILL HENDERSON | 2904 TED JONES DR., APT. D, BEDFORD, IN 47421 | |
| Building Contractor | | | |
| Drilling Contractor | S&S DRILLING INC. | R1 BOX 507, MONTGOMERY, IN 47558 | |
| Equipment Operator | DEXTER SWARTZENTRUBER | License: 302 | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* ROTARY | *Pump type:* |
| | *Depth:* 300.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 30.0 | *Material:* PVC | *Diameter:* 6.0 |
| Screen | *Length:* 280.0 | *Material:* PVC | *Diameter:* 4.5 *Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* 1.5 gpm for hrs. *BailTest rate:* gpm for hrs.
*Drawdown:* ft. *Static water level:* 100.0 ft.

***Grouting Information***

*Material:* BNSL *Depth:* from 30.0 to 0.0
*Installation Method:* PUMP *Number of bags used:* 2.0

***Well Abandonment***

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 5N *Range:* 1E
*Section:* 1/4 of the 1/4 of the 1/4 of Section 29 *Topo map:* BEDFORD EAST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 30.0 | CLAY, MUD SEAMS, SAND |
| 30.0 | 122.0 | LIME & LIME BRKS |
| 122.0 | 300.0 | LIME SHALE BRK |

***Comments***

SEE MAP: DEAD END ROAD TO EAST, 1ST HOUSE ON NORTH SD OF RD

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220914** | | Wed, Oct 20, 1954 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | ADAMSON | EUREKA | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | R3 MITCHELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 161.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 62.0 | *Material:* | *Diameter:* 5.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.5 gpm for 0.5 hrs.
*Drawdown:* ft. *Static water level:* 70.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* 1/4 of the 1/4 of the 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 62.0 | OVERBURDEN,CLAY,BLDRS,LS |
| 62.0 | 161.0 | LS |

*Comments* WELL PUMPED DRY DURING TESPage 9788

# Record of Water Well

Indiana Department of Natural Resources

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **220909** | | Thu, Aug 19, 1954 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | MRS. PINKSTON | EUREKA | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | R2 MITCHELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* JET | *Pump type:* |
| | *Depth:* 164.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 49.5 | *Material:* | *Diameter:* 5.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 1.0 gpm for 0.5 hrs.
*Drawdown:* ft. *Static water level:* 76.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* 1/4 of the 1/4 of the 1/4 of Section 18 *Topo map:* BEDFORD WEST
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 49.5 | OVERBURDEN,CLAY,BLDRS,LS |
| 49.5 | 164.0 | LS |

*Comments* WELL PUMPED DRY DURING TEST

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **217890** | SR158 .5 MI S ON SR450. | Sat, Nov 25, 1967 |

| *Owner-Contractor* | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| Well Owner | JOHNSON | 312 INDIANA AVE, OOLITIC IN | |
| Building Contractor | | | |
| Drilling Contractor | MUMMA DRLG INC. | WASHINGTON & LYONS IN | |
| Equipment Operator | DEAN K. MUMMA | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* OTHER | *Pump type:* |
| | *Depth:* 186.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 6.62 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 5.5 gpm for hrs.
*Drawdown:* ft. *Static water level:* 109.0 ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 5N *Range:* 1W
*Section:* SE 1/4 of the SW 1/4 of the NE 1/4 of Section 21 *Topo map:* BEDFORD WEST
*Field located by:* JRD *on:* Wed, Aug 09, 1978
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* 1700 *Ft N of SL:* *Ft E of WL:* *Ft S of NL:* 2100
*Ground elevation:* 675.0 *Depth to bedrock:* 36.0 *Bedrock elevation:* 639.0 *Aquifier elevation:*
*UTM Easting:* 541414.0 *UTM Northing:* 4300572.0

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 36.0 | CLAY |
| 36.0 | 58.0 | LIME |
| 58.0 | 63.0 | MUD & BREAKS OF LIME |
| 63.0 | 158.0 | LIME |
| 158.0 | 180.0 | BREAKS OF LIME WATER |
| 180.0 | 186.0 | LIME |

*Comments* MC 639; OWNER VERIFIED 40' N OF HOUSE. 7.7 PH, 0.1 IRON, 20 GRAMS HARDNES;

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219643** | NEAREST TOWN MITCHELL | Fri, Apr 19, 1957 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | HOWARD WOODS | | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | RR #3 MITCHELL IN | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 125.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 22.0 | *Material:* | *Diameter:* 6.25 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 3.0 gpm for hrs.
*Drawdown:* ft. *Static water level:* ft.

*Grouting Information*

*Material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to
*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 4N *Range:* 1W
*Section:* 1/4 of the 1/4 of the 1/4 of Section 4 *Topo map:* MITCHELL
*Field located by:* *on:*
*Courthouse location by:* *on:*
*Location accepted w/o verification by:* *on:*
*Subdivision name:* *Lot number:*
*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*
*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*
*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 18.0 | OVRBRN CLAY BLDRS BRKN LS |
| 18.0 | 22.0 | SOLID ROCK |
| 22.0 | 125.0 | LS~ |
| 125.0 | 0.0 | SOAPSTONE |

*Comments* WELL HAD RESERVE CAP OF 300 GAL: MAY BE IN NAME OF GUS WOODS:

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219648** | BEDFORD | Sat, Jul 07, 1951 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | HARLEY CLARK | OLD HWY 37 | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | R #3 MITCHELL | |
| Equipment Operator | | License: | |

*Construction Details*

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 108.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

*Well Capacity Test*

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.25 gpm for hrs.

*Drawdown:* ft. *Static water level:* 42.0 ft.

*Grouting Information*

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Well Abandonment*

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

*Administrative*

*County:* LAWRENCE *Township:* 4N *Range:* 1W

*Section:* 1/4 of the 1/4 of the 1/4 of Section 3 *Topo map:* BEDFORD WEST

*Field located by:* *on:*

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifer elevation:*

*UTM Easting:* *UTM Northing:*

*Well Log*

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 5.0 | OVRBRDN CLAY ROCKS BRKN LS |
| 5.0 | 108.0 | LS* |

*Comments* APPROX LOC: WELL HAS 120 GAL RESERVE CAP. MAY BE APPLE ACRES FARM:

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219653** | | Sat, Jul 07, 1951 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | HARLEY CLARK | NEW SR 37 | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | R #3 MITCHELL | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 131.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 21.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test***

*Type of test:* *Test rate:* gpm for hrs. *BailTest rate:* 0.5 gpm for hrs.

*Drawdown:* ft. *Static water level:* 61.0 ft.

***Grouting Information***

*Material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Well Abandonment***

*Sealing material:* *Depth:* from to

*Installation Method:* *Number of bags used:*

***Administrative***

*County:* LAWRENCE *Township:* 4N *Range:* 1W

*Section:* 1/4 of the 1/4 of the 1/4 of Section 3 *Topo map:* BEDFORD WEST

*Field located by:* *on:*

*Courthouse location by:* *on:*

*Location accepted w/o verification by:* *on:*

*Subdivision name:* *Lot number:*

*Ft W of EL:* *Ft N of SL:* *Ft E of WL:* *Ft S of NL:*

*Ground elevation:* *Depth to bedrock:* *Bedrock elevation:* *Aquifier elevation:*

*UTM Easting:* *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 17.0 | OVRBRDN CLAY ROCKS BRKN LS |
| 17.0 | 21.0 | SOLID ROCK |
| 21.0 | 131.0 | LS* |

***Comments***

APPROX LOC: WELL HAS 100GAL RESERVE CAPPage 9702

# Record of Water Well

**Indiana Department of Natural Resources**

| *Reference Number* | *Driving directions to well* | *Date completed* |
|---|---|---|
| **219658** | | Mon, Sep 08, 1952 |

| | *Name* | *Address* | *Telephone* |
|---|---|---|---|
| *Owner-Contractor* | | | |
| Well Owner | OTHA SMITH | RR #2 MITCHELL ST RD 37 & 50 S | |
| Building Contractor | | | |
| Drilling Contractor | HOMER ALFORD | | |
| Equipment Operator | | License: | |

***Construction Details***

| | | | |
|---|---|---|---|
| Well | *Use:* HOME | *Drilling method:* CABLE TOOL | *Pump type:* |
| | *Depth:* 293.0 | *Pump setting depth:* | *Water quality:* |
| Casing | *Length:* 23.0 | *Material:* | *Diameter:* 5.63 |
| Screen | *Length:* | *Material:* | *Diameter: Slot size:* |

***Well Capacity Test*** — *Type of test:* — *Test rate:* gpm for hrs. — *BailTest rate:* 1.0 gpm for 0.5 hrs.
*Drawdown:* ft. — *Static water level:* 62.0 ft.

***Grouting Information*** — *Material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Well Abandonment*** — *Sealing material:* — *Depth:* from to
*Installation Method:* — *Number of bags used:*

***Administrative***

*County:* LAWRENCE — *Township:* 4N *Range:* 1W
*Section:* 1/4 of the 1/4 of the NE 1/4 of Section 3 — *Topo map:* BEDFORD WEST
*Field located by:* — *on:*
*Courthouse location by:* — *on:*
*Location accepted w/o verification by:* — *on:*
*Subdivision name:* — *Lot number:*
*Ft W of EL:* — *Ft N of SL:* — *Ft E of WL:* — *Ft S of NL:*
*Ground elevation:* — *Depth to bedrock:* — *Bedrock elevation:* — *Aquifier elevation:*
*UTM Easting:* — *UTM Northing:*

***Well Log***

| Top | Bottom | Formation |
|---|---|---|
| 0.0 | 23.0 | OVRBRDN CLAY BLDRS BRKN LS |
| 23.0 | 293.0 | LS |

***Comments*** APPROX LOC: WELL HAS RESERVE CAP OF 375 GAL. 9.66 ACRES AT HWY Y FIELDLOCATE:

DIVISION OF WATER
DEPARTMENT OF NATURAL RESOURCES, STATE OF INDIANA
STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3–6757

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: _____

Congressional township: 5 N Range: 1 W Number of section: 14

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: Bedford

NOW GM CENTRAL FOUNDRY ?

Name of owner: Bedford Foundry & Machine Co. Address: _____

Name of Well Drilling Contractor: _____

Address: _____

Name of Drilling Equipment Operator: _____

## INFORMATION ON THE WELL

Completed depth of well: 130 ft. Date well was completed: 11-53

Diameter of outside casing or drive pipe: 6 Length: 20

Diameter of inside casing or liner: _____ Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☐ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☐ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☐ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) _____ ft.

Bailer Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate 5 (est) g.p.m. Drawdown _____ ft.

Signature Roberts

Date USGS

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| limestone | 20 | 130 |

| | PPM | EPM |
|---|---|---|
| Silica | 12 | |
| Iron | .17 | .009 |
| Calcium | 114 | 5.689 |
| Magnesium | 27 | 2.220 |
| Sodium | 32 | 1.391 |
| Potassium | 1.2 | .031 |
| Bicarbonate | 334 | 5.474 |
| Sulfate | 134 | 2.790 |
| Chloride | 27 | .761 |
| Fluoride | .1 | .005 |
| Nitrate | 15 | .242 |
| pH | 7.7 | |
| Colar | 1. | |
| Dissolved Solids | 527 | |
| Resideu 180°C | 531 | |
| Hardness | | |
| Calcium, Magnesium | 396 | |
| Noncarbonate | 122 | |

REMARKS:

58° Water Temp

COUNTY: Fillmore TWP. 5N RGE. 1W ¼ NW ¼ NE ¼ SEC. 12

Topo Map: Burnt Ranch 22'

Well log classified By — Date —

Courthouse located By ____ Date ____

Field located By ____ Date ____

Acc. w/o verification By ____ Date ____

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

____ Ft W of EL. Ground elevation ____

____ Ft N of SL. Depth to bedrock ____

____ Ft E of WL. Bedrock elevation ____

____ Ft S of NL. Aquifer elevation ____

Chem

Machine, Standard

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water

4-Bin Thermal Ct Jr
2 Wilford.
Mapor Bellair.

Oolitic Quad
Reference ID
(47SFR31233)

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

# WATER WELL RECORD

1

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: 5 N. Range: 1 W Number of section: 3
(Fill in as completely as possible) LOT #30

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: East Oolitic - 1 mile East of Oolitic

Name of owner: W. Omer Hubbard Address: Bedford Rd. RR 2

Name of Well Drilling Contractor: ERNIE HUMPHRESS & SONS

Address: BEDFORD IND. RR 6

Name of Drilling Equipment Operator: Eugene & Charles HUMPHRESS

## INFORMATION ON THE WELL

Completed depth of well: 100 ft. Date well was completed: 7/26/62

Diameter of outside casing or drive pipe: 6" Length: 20' 6"

Diameter of inside casing or liner: 5 5/8" Length:

Diameter of Screen: Length: Slot size:

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 40 ft.

Bailer Test: Hours tested Rate 3 g.p.m. Drawdown 60 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested Rate g.p.m. Drawdown ft.

Signature Eugene Humphress

Date 7/26/62

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 5' |
| Blue Limestone - Hard | 5 | 13 |
| OPEN Hole | 13 | 14 |
| Blue Limestone - Hard | 14 | 23 |
| Gray " - Soft | 23 | 51 |
| Blue Shale - Soft | 51 | 62 |
| Blue Limestone - Soft | 62 | 79 |
| Blue Shale - Soft | 79 | 105' |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: Lawrence TWP. 5N RGE. 1W NW¼ SE¼ NW¼ SEC. 3

Topo. Map: Oolitic 7½ Loc. accepted w/o verification Yes ___ No ___

El. of grnd. surface at well: 550 Courthouse Loc. By ___ Date ___

Depth to bedrock: ___ Field Located By K Date 7-63

Well Log processed by: ___ Placed in Master Well Log File Date ___

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS 9, INDIANA

Quad.




# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: LOT-10+11 Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: APP. ONE MILE NORTH OF BEDFORD, IND. ONE BLOCK WEST OF PEERLESS ROAD, KNOWN AS WALNUT HEIGHTS (otr)

Name of owner: PHILLIS CHILDERS Address: BEDFORD, IND.

Name of Well Drilling Contractor: ERNIE UMPHRESS & SONS

Address: BEDFORD IND. RR6

Name of Drilling Equipment Operator: EUGENE & CHARLES UMPHRESS

## INFORMATION ON THE WELL

Completed depth of well: 200 ft. Date well was completed: 11/30/62

Diameter of outside casing or drive pipe: 6" Length: 9in known

Diameter of inside casing or liner: 5 5/8" Length: Drilled Depth

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 135 ft.

Bailer Test: Hours tested _____ Rate 3 g.p.m. Drawdown 65 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Eugene Umphress

Date 11/30/62

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Blue Limestone - Hard | 100' | 108' |
| Gray " - Soft | 108' | 130' |
| Blue Shale - Soft | 130' | 200' |

REMARKS: Old well drilled deeper from 100' to 200'

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

COUNTY: [illegible] TWP. 5N RGE. 1W ¼ ¼ ¼ SEC. Sec 2

Topo Map: [illegible]

Well log classified By [illegible] Date
Courthouse located By ____ Date ____
Field located By ____ Date ____
Acc. w/o verification By ____ Date 7-63

____ Ft W of EL. Ground elevation ____
____ Ft N of SL. Depth to bedrock ____
____ Ft E of WL. Bedrock elevation ____
____ Ft S of NL. Aquifer elevation ____

NW SW SE SE Sec 3

INSTRUCTIONS


This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation.

Stallettsville Quad

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA




# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawnee

Congressional township: _____ Range: _____ Number of section: 2

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: Bracken Ridge Road one mile north Bedford City Limits

Name of owner: Jessie Stigall Address: Bedford RR 4

Name of Well Drilling Contractor: Paul Scott

Address: RR 4 Bloomington Ind

Name of Drilling Equipment Operator: Paul Scott

## INFORMATION ON THE WELL

Completed depth of well: 140 ft. Date well was completed: 7. 21. 60

Diameter of outside casing or drive pipe: 6 in Length: 67 ft.

Diameter of inside casing or liner: 5 5/8 in. Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) _____ ft.

Bailer Test: Hours tested _____ Rate Full g.p.m. Drawdown 0 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Paul Scott

Date 7, 30, 60.

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Rustic Buff Lime meidian | 6 | 40 |
| Blue Lime Hard | 40 | 130 |
| Blue Lime Soft | 130 | 140 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

COUNTY: LAWRENCE TWP. 5N RGE. 1W NE¼ SW¼ SW¼ SEC. 2

Topo. Map: BARTLETTSVILLE 7½ Loc. accepted w/o verification Yes ___ No ___

El. of grnd. surface at well: 670 Courthouse Loc. By ___ Date ___

Depth to bedrock: ___ Field Located By H. S Date 11/4/60

Well Log processed by: PC Placed in Master Well Log File Date ___

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

Quad.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

FEB 1960 RECEIVED

# WATER WELL RECORD

6

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: Two miles north Bedford on Ind. Breckenridge road near Pine School House.
Bahr's Hiland Blk. D, Lot 1
North N St

Name of owner: Wmand Elkins Address: RR 4 Bedford Ind.

Name of Well Drilling Contractor: Ernie Umphreys & Sons

Address: RR 6 Box 13 Bedford Ind

Name of Drilling Equipment Operator: Ernie Umphreys & Sons

## INFORMATION ON THE WELL

Was 107 Drilled Hiffmand

Completed depth of well: 150 ft. Date well was completed: Jan 26 1960

Diameter of outside casing or drive pipe: _____ Length: not known

Diameter of inside casing or liner: 5 5/8 Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: ~~Drilled~~ ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: ~~For home~~ ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 50 ft.

Bailer Test: Hours tested 1 Rate 3 g.p.m. Drawdown 100 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested None Rate _____ g.p.m. Drawdown 100 ft.

Signature Ernie Umphreys & sons

Date Jan 26 1960

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| White limestone Hard | 109 | 150 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: Lawrence TWP. 5N RGE. 1W ¼ SW ¼ SW ¼ SEC. 2

Topo. Map: Bartlettsville

El. of grnd. surface at well: 700 Loc. accepted w/o verification Yes — No X

Depth to bedrock: — Courthouse Loc. By —

Well Log processed by: Bowers Field Located By Bowers Date 8/66

Placed in Master Well Log File Date 7/66

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

Lawrence Quad

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS 9, INDIANA

RECEIVED OCT 1963 Dept. of Conservation Division of Water Resources

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: LAWRENCE Civil Township: SHAWSWICK

Congressional township: 5 Range: 1 WEST Number of section: 1

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: 1 mile north of Ind. Hiway 58 on Mt. Pleasant Road R.R.4. Bedford Indiana

Name of owner: Guy S. Weaver Address: RR4. Bedford Indiana

Name of Well Drilling Contractor: Ernie Umphress & Sons

Address: Bedford, Ind. RR6

Name of Drilling Equipment Operator: Eugene & Charles Umphress

## INFORMATION ON THE WELL

Completed depth of well: 250 ft. Date well was completed: 9/10/63

Diameter of outside casing or drive pipe: 6" Length: 23'

Diameter of inside casing or liner: 5 5/8" Length: 23'

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 170 ft.

Bailer Test: Hours tested _____ Rate 5 g.p.m. Drawdown 80 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Eugene Umphress

Date 9/10/63

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 4' |
| BROKEN Limestone | 4 | 17 |
| Blue " - Hard | 17 | 39 |
| Gray " - Hard | 39 | 55 |
| Blue Shale - SOFT | 55 | 250' |

REMARKS:

COUNTY: [illegible] TWP. S-9 RGE. 1 E ¼ ¼ ¼ ¼ SEC. 1

Topo Map: Bluffton

Well log classified By Zuhl Date 9/63

Courthouse located By [illegible] Date [illegible]

Field located By [illegible] Date [illegible]

Acc. w/o verification By [illegible] Date [illegible]

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

[illegible] Ft W of EL. Ground elevation 630'

2500 Ft N of SL. Depth to bedrock [illegible]

2600 Ft E of WL. Bedrock elevation [illegible]

[illegible] Ft S of NL. Aquifer elevation [illegible]

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3-6757

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: 5 N Range: 1 E Number of section: 5

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: APP. 3 Miles East of Bedford, Ind. ON U. S. Highway #58

Name of owner: Noel Gene Mitchell Address: Bedford, Ind. RR3

Name of Well Drilling Contractor: Ernie Umphress & Sons

Address: Bedford, Ind. RR6

Name of Drilling Equipment Operator: Eugene & Charles Umphress

## INFORMATION ON THE WELL

Completed depth of well: 200 ft. Date well was completed: 1/5/66

Diameter of outside casing or drive pipe: 6" Length: 21.6"

Diameter of inside casing or liner: 5-5/5" Length: 21.6"

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 90 ft.

Bailer Test: Hours tested _____ Rate 12 g.p.m. Drawdown 110 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Eugene Umphress

Date 1/8/66

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 6' |
| Boulders & Mud Holes | 6 | 17 |
| Gray Limestone - Hard | 17 | 27 |
| Blue " - " | 27 | 61 |
| Gray " - Soft | 61 | 82 |
| Blue Shale - " | 82 | 85- |
| Blue Limestone - " | 85- | 103 |
| Blue Shale - " | 103 | 200' |
| | | |
| | | |
| | |

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS 9, INDIANA

# WATER WELL RECORD




## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: 3 S Range: 1 E Number of section: 8

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: Three miles south-east of Bedford on State road fifty Eight

stand for new house; Trailer now

Name of owner: Lawrence Ray Address: RR #3 Bedford Ind

Name of Well Drilling Contractor: Eugene Humphress & Sons

Address: Bedford Ind. RR6

Name of Drilling Equipment Operator: Eugene & Charles Humphress

## INFORMATION ON THE WELL

Completed depth of well: 100 ft. Date well was completed: 11/27/62

Diameter of outside casing or drive pipe: 6" Length: 31' 6"

Diameter of inside casing or liner: 5 3/5" Length: 31' 6"

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 45 ft.

Bailer Test: Hours tested _____ Rate 36 g.p.~~m.~~ Drawdown 55 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Eugene Humphress

Date 11/27/62

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 4' |
| Blue Limestone - Hard | 4 | 32' |
| Mud Hole | 32 | 32'6" |
| Blue Limestone - Hard | 32'6" | 44' |
| Gray " - Soft | 44' | 51' |
| Blue " - Hard | 51' | 70' |
| Blue Shale - Soft | 70' | 100' |
| | | |
| | | |
| | |

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

# WATER WELL RECORD

10

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Pleasant View

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: Northeast of Bedford between the Mt. Pleasant Road & Pleasant View Road.

Name of owner: Louis Hicks Address: R.R. 3

Name of Well Drilling Contractor: Floyd Stultz

Address: Bedford Ind. R.R. 4

Name of Drilling Equipment Operator: Floyd Stultz

## INFORMATION ON THE WELL

Completed depth of well: 125 ft. Date well was completed: Sept. 15, 1962

Diameter of outside casing or drive pipe: 6 in. Length: 19 ft.

Diameter of inside casing or liner: 5 5/8 Length: 19 ft.

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☐ For industry ☐ For public supply ☐ Stock ☑

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 30 ft.

Bailer Test: Hours tested 8 Rate 20 g.p.m. Drawdown _____ ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Floyd Stultz

Date Sept. 15, 1962

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| 19 ft. of clay | | |
| 106 ft. of limestone | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

COUNTY: LAWRENCE TWP. 5N RGE. 1E SE¼ SW¼ NE¼ SEC. 6

Topo. Map: Bartlett Loc. accepted w/o verification Yes ___ No ___

El. of grnd. surface at well: 775 Courthouse Loc. By ___ Date ___

Depth to bedrock: ___ Field Located By HS Date 11-5

Well Log processed by: PB Placed in Master Well Log File Date 11/15/72

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3-6757

# WATER WELL RECORD

10

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: 5 North Range: 1 East Number of section: 7

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: App. 3 Miles East of Bedford, Ind on U.S. Highway No. 58 North Side of Road

Name of owner: Robert Watson Address: Bedford, Ind.

Name of Well Drilling Contractor: Ernie Umphress & Sons

Address: Bedford, Ind. RR 6

Name of Drilling Equipment Operator: Eugene & Charles Umphress

## INFORMATION ON THE WELL

Completed depth of well: 200 ft. Date well was completed: 8/26/65

Diameter of outside casing or drive pipe: 6" Length: 13'

Diameter of inside casing or liner: 5-5/8" Length: 13'

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 40 ft.

Bailer Test: Hours tested _____ Rate 1/2 g.p.m. Drawdown 160 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Eugene Umphress

Signature Robert Watson

Date 8/26/65

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 7' |
| LIMESTONE Boulders | 7 | 14 |
| gRay LIMESTONE - HARD | 14 | 31 |
| BRow " - SOFT | 31 | 50 |
| gRay " - HARD | 50 | 89 |
| Blue " - " | 89 | 125 |
| Blue Shale - SOFT | 125 | 200' |

REMARKS:

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

COUNTY: [illegible] TWP. 5N RGE. 1E SE ¼ NW ¼ NE ¼ SEC. 7

Topo Map: [illegible]

Well log classified By _____ Date _____
Courthouse located By _____ Date _____
Field located By [illegible] Date 8-26
Acc. w/o verification By _____ Date _____

400 Ft W of EL. Ground elevation 630
_____ Ft N of SL. Depth to bedrock _____
_____ Ft E of WL. Bedrock elevation _____
_____ Ft S of NL. Aquifer elevation _____


INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS 9, INDIANA




# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: LAWRENCE Civil Township: SHIELDSBURG

Congressional township: 5 Range: 1E Number of section: 7

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: 3 MILES EAST OF BEDFORD ON STATE ROAD #58

Name of owner: TERRY NEAL Address: 1321 5TH STREET, BEDFORD

Name of Well Drilling Contractor: ERNIE UMPHRESS SONS

Address: Bedford Ind. RR6

Name of Drilling Equipment Operator: Eugene & Charles UMPHRESS

## INFORMATION ON THE WELL

Completed depth of well: 200 ft. Date well was completed: 7/17/63

Diameter of outside casing or drive pipe: 6" Length: 16'

Diameter of inside casing or liner: 5 5/8" Length: 16'

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 50 ft.

Bailer Test: Hours tested _____ Rate 1 g.p.m. Drawdown 150 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Eugene Umphress

Date 7/17/63

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 8' |
| Limestone Boulders - Hard | 8 | 12 |
| White Limestone - Soft | 12 | 34 |
| Blue " - Hard | 34 | 78 |
| Gray " - Hard | 78 | 83 |
| Blue " - Hard | 83 | 107 |
| Blue Shale - Soft | 107 | 200' |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: [illegible] TWP. 5-N RGE. 1-E NE ¼ NW ¼ NW ¼ SEC. 17

Topo Map: [illegible]

Well log classified By [illegible] Date [illegible]
Courthouse located By [illegible] Date [illegible]
Field located By [illegible] Date [illegible]
Acc. w/o verification By [illegible] Date [illegible]

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

200 Ft W of EL. Ground elevation 653
Ft N of SL. Depth to bedrock
Ft E of WL. Bedrock elevation
600 Ft S of NL. Aquifer elevation

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

13

RECEIVED
JUL 19 1959

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: [illegible] Civil Township: [illegible]

Congressional township: 5 Range: 1 East Number of section: 7

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: Located near State Rd 58 East of Bedford about 1½ Miles East of City Limits & Big Barkhouse.

Name of owner: [illegible] Address: [illegible]

Name of Well Drilling Contractor: [illegible]

Address: [illegible]

Name of Drilling Equipment Operator: [illegible]

## INFORMATION ON THE WELL

Completed depth of well: 150' ft. Date well was completed: July 14 1959

Diameter of outside casing or drive pipe: 6" Length: 16' 6"

Diameter of inside casing or liner: 5" Length:

Diameter of Screen: Length: Slot size:

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☒

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 46½ ft.

Bailer Test: Hours tested 1 Rate 24 g.p.h. Drawdown 109 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested none Rate ____ g.p.m. Drawdown ____ ft.

Signature Ernie Ambrose & Sons

Date July 16 1959

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

# WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Dirt | 0 | 6 |
| Hard Shelly lime white | 6 | 8 |
| White lime soft | 8 | 115 |
| Blue lime Firm | 115 | 137 |
| Blue Shale soft | 137 | 155 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: Lake TWP. 34N RGE. 7E SW ¼ NE ¼ NE ¼ SEC. 7

Topo. Map: East Chicago

El. of grnd. surface at well: 680 Loc. accepted w/o verification Yes ___ No X

Depth to bedrock: ___ Courthouse Loc. By ___ Date ___

Well Log processed by: Bowser Field Located By Bowser Date 8/67

Placed in Master Well Log File Date 8/67

(Well Driller does not fill out)

## INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

J. 193.

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawsville

Congressional township: 5 North Range: 1 (one) Number of section: 18

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: Southeast quarter of Section 18 Lawrence 5 north, ~~Range~~ 1 Rang 1 cet the Northwest corn of said quarter section, South of Leesville gra road 18 Rods and 17 Links. 2½ miles East of Bedford Ind.

Name of owner: Floyd Silvers Address: R R. 6.

Name of Well Drilling Contractor: [illegible]

Address: [illegible]

Name of Drilling Equipment Operator: [illegible]

## INFORMATION ON THE WELL

Completed depth of well: 100 ft. Date well was completed: [illegible]

Diameter of outside casing or drive pipe: 6 Length: 8

Diameter of inside casing or liner: 5" Length:

Diameter of Screen: Length: Slot size:

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 42 ft.

Bailer Test: Hours tested 1 Rate 12 g.p.m. Drawdown 58 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested none Rate ____ g.p.m. Drawdown 58 ft.

Signature [illegible]

Date [illegible]

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

# WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Dirt | 0 | 4 |
| White limestone Hard | 4 | 40 |
| Blue | 40 | 65 |
| White | 65 | 83 |
| Blue shale | 83 | 100 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: LAWRENCE TWP. 5N RGE. 1E SE¼ SW¼ SE¼ SEC. 18

Topo. Map: BEDFORD E 7½ Loc. accepted w/o verification Yes ___ No ___

El. of grnd. surface at well: 660 Courthouse Loc. By ___ Date ___

Depth to bedrock: ___ Field Located By ___ Date ___

Well Log processed by: DFS Placed in Master Well Log File Date ___

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)


## INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS 9, INDIANA




# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: LAWRENCE Civil Township: Shawswick

Congressional township: 5 NORTH Range: 1 EAST Number of section: 18

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: APP. 1 Mile East of Bedford Ind.

Name of owner: Glenn D. Woody Address: R.R.#6 Bedford, Indiana.

Name of Well Drilling Contractor: Ervin Umphress & Sons

Address: Bedford, Ind.

Name of Drilling Equipment Operator: Eugene & Charles Umphress

## INFORMATION ON THE WELL

Completed depth of well: 200 ft. Date well was completed: 8/6/63

Diameter of outside casing or drive pipe: 6" Length: 6'

Diameter of inside casing or liner: 5 3/8" Length: 6'

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 100 ft.

Bailer Test: Hours tested _____ Rate 1/2 g.p.m. Drawdown 100 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Glenn Woody

Date 8/6/63

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

# WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 2½' |
| Blue Limestone - Hard | 2½ | 23 |
| Gray " - " | 23 | 51 |
| White " - " | 51 | 70 |
| Blue " - " | 70 | 103 |
| Blue Shale - SOFT | 103 | 200' |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: _____ TWP. 5-N RGE. 1-E NW ¼ NE ¼ SE ¼ SEC. 1

Topo Map: _____

Well log classified By _____ Date _____

Courthouse located By _____ Date _____

Field located By OGS Date 9-1962

Acc. w/o verification By _____ Date _____

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

_____ Ft W of EL. Ground elevation 760

_____ Ft N of SL. Depth to bedrock _____

_____ Ft E of WL. Bedrock elevation _____

_____ Ft S of NL. Aquifer elevation _____


## INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA




# WATER WELL RECORD

10

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Co. Civil Township: Shawswick

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: 2 mi. northeast of Bedford Ind. on U.S. 50

Name of owner: Donald Fish Address: Bedford Ind. RR4

Name of Well Drilling Contractor: Floyd Stultz

Address: Bedford Ind. RR4

Name of Drilling Equipment Operator: Floyd Stultz

## INFORMATION ON THE WELL

Completed depth of well: 70 ft. Date well was completed: 10 December, 1959

Diameter of outside casing or drive pipe: 6 in. Length: 14 ft.

Diameter of inside casing or liner: 5 in Length: 14 ft.

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☐ For industry ☐ For public supply ☐ Stock ☒

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) _____ ft.

Bailer Test: Hours tested 8 Rate 20 g.p.m. Drawdown _____ ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature: Floyd Stultz

Date: Dec. 28, 1959

**FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET**

# WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| 11 ft. Clay | | |
| 75 ft. Limestone | | |

REMARKS:

COUNTY: Jennings TWP. 5N RGE. 1W NW¼ NW¼ SE¼ SEC. 1

Topo. Map: Bartlettsville Loc. accepted w/o verification Yes — No —

El. of grnd. surface at well: Not Given Courthouse Loc. By ____ Date ____

Depth to bedrock: ____ Field Located By Owner Date 8/60

Well Log processed by: H. C. Kost Placed in Master Well Log File Date ____

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)


## INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA




# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: 5 Range: 1 - W Number of section: 21
(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: West of Bedford 1 mi
1½ mi South on Williams Road east side

Name of owner: Gordon Lee Hamilton Address: Bedford RR

Name of Well Drilling Contractor: Ray E Alford

Address: Mitchell RR 1

Name of Drilling Equipment Operator: Samuel Crowe

## INFORMATION ON THE WELL

Completed depth of well: 150 Ft. Date well was completed: Sept 25 - 65

Diameter of outside casing or drive pipe: 6 5/8 Length: 39½

Diameter of inside casing or liner: 6¼ Length: 39½

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 76 Ft.

Bailer Test: Hours tested _____ Rate 1 g.p.m. Drawdown 6 Ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ Ft.

Signature Ray E Alford

Date Sept 25 - 65

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Clay | 0 | 50 |
| Soft Lime | 50 | 60 |
| Lime | 60 | 140 |
| Med Lime | 140 | 155 |
| Hard " | 155 | 179 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: Lawrence TWP. 5N RGE. 1W ¼ SW ¼ NE ¼ SEC. 21

Topo Map: Bedford West 22

Well log classified By [illegible] Date ____

Courthouse located By ____ Date ____

Field located By [illegible] Date 2-[illegible]

Acc. w/o verification By ____ Date ____

2450 Ft W of EL. Ground elevation 615

____ Ft N of SL. Depth to bedrock 50

____ Ft E of WL. Bedrock elevation 615

2502 Ft S of NL. Aquifer elevation ____

(Well driller does not fill out)

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

DEC 1963
RECEIVED
Dept. of Conservation
Division of

18

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

ty in which well was drilled: Lawrence Civil Township: Shawswick

ressional township: Range: Number of section:

(Fill in as completely as possible)

ribe in your own words the well location with respect to nearby towns, roads, streets

listinctive landmarks: From Bedford Going West on 16 ST Turn left on 450. Go Approx ½ Mi Turn Left at 2nd curve.

me of owner: Gene Beck Address:

me of Well Drilling Contractor: Louie O. Smith

dress: RR 1 Bedford

ame of Drilling Equipment Operator: Same

## INFORMATION ON THE WELL

ompleted depth of well: 170 ft. Date well was completed: Dec. 9, 1963

Diameter of outside casing or drive pipe: 6¼ Length: 48

Diameter of inside casing or liner: Length:

Diameter of Screen: Length: Slot size:

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other Stock ☐

Use of Well: For home ☒ For industry ☐ For public supply ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 95 ft.

Bailer Test: Hours tested 2 Rate 5 g.p.m. Drawdown 163 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested Rate g.p.m. Drawdown ft.

Signature Louie O. Smith

Date Dec. 14, 1963

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| clay | 0 | 16 |
| Broken Lime | 16 | 38 |
| Lime | 38 | 75 |
| Hard Lime | 75 | 81 |
| Soft Lime | 81 | 135 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: Lawrence TWP. 5N RGE. 13W ¼ SW ¼ NE ¼ SEC. 21

Topo Map: Bedford West

Well log classified By ZLL Date 7/20

Courthouse located By ___ Date ___

Field located By VLL Date 8-17-71

Acc. w/o verification By ___ Date ___

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

2200 Ft W of EL. Ground elevation 680'

___ Ft N of SL. Depth to bedrock 16

Ft E of WL. Bedrock elevation 614

1618 Ft S of NL. Aquifer elevation ___

OPTIONAL

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water

DIVISION OF WATER
DEPARTMENT OF NATURAL RESOURCES, STATE OF INDIANA
STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3-6757

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawnick

Congressional township: _____ Range: _____ Number of section: _____

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: (Fill in as completely as possible)
From Bedford ~~town~~ going about 2 mi
Turn left on 450 go about ½ mi to Bef Lots.
well be 4th house on Right

Name of owner: Glen Craig Address: Bedford

Name of Well Drilling Contractor: Sam O Smith

Address: RR 1 Bedford

Name of Drilling Equipment Operator: Sam

## INFORMATION ON THE WELL

Completed depth of well: 175 ft. Date well was completed: May 13, 1965

Diameter of outside casing or drive pipe: 6¼ Length: 52'

Diameter of inside casing or liner: _____ Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 125 ft.

Bailer Test: Hours tested 2 Rate 2 g.p.m. Drawdown 120 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested ____ Rate ____ g.p.m. Drawdown ____ ft.

Signature Sam O. Smith

Date May 18, 1968

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Clay | 0 | 20 |
| Brown clay | 20 | 22 |
| shell | 22 | 30 |
| hard lime | 30 | 47 |
| soft | 47 | 52 |
| hard lime | 52 | 85 |
| med lime | 85 | 165 |
| hard lime | 165 | 175 |

REMARKS:

COUNTY: [illegible] TWP. 51 RGE. 15 SE ¼ SW ¼ NE ¼ SEC. 21

Topo Map: [illegible]

Well log classified By [illegible] Date ____

Courthouse located By ____ Date ____

Field located By [illegible] Date [illegible]

Acc. w/o verification By ____ Date ____

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

1665 Ft W of EL. Ground elevation 670+

____ Ft N of SL. Depth to bedrock 175

2155 Ft E of WL. Bedrock elevation 645

____ Ft S of NL. Aquifer elevation ____

MC

Bck

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water

FC

WATER WELL LOG

| ORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| | 0 | 36 |
| Clay | 36 | 58 |
| Lime | 58 | 63 |
| Mud & Breaks of Lime | 63 | 158 |
| Lime | 158 | 180 |
| Breaks of Lime Water | 180 | 186 |
| Lime | | |
| | | |
| | | |
| | | |
| 7.7 PH. | | |
| 0.1 Iron | | |
| 20 grams hardest | | |
| | | |
| | | |
| Well is 35 ft. from house | | |
| The well was Switched | | |
| Set pump 175 ft. | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: Lawrence TWP. 5N RGE. 1W SE ¼ SW ¼ NE ¼ SEC. 21

Topo Map: Bedford West ½

Well log classified By [illegible] Date 2/62

Courthouse located By [illegible] Date 8-9-76

Field located By [illegible] Date

Acc. w/o verification By [illegible] Date

FOR ADMINISTRATIVE USE ONLY
(Well driller does not fill out)

1700 Ft W of EL. Ground elevation 675'

Ft N of SL. Depth to bedrock 36

Ft E of WL. Bedrock elevation 639

2100 Ft S of NL. Aquifer elevation

Owner Varified 40 ft. North of House

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water

DIVISION OF WATER
DEPARTMENT OF NATURAL RESOURCES, STATE OF INDIANA
STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3-6757

# WATER WELL RECORD

NO T or R

## INFORMATION ON WELL LOCATION

County in which well was drilled: LAWRENCE Civil Township: _____

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: S.R. 158 1/2 Mile South on S.R. 450

?

maybe Section 21
SW 1/4

Name of owner: ~~Lenny D. McGee~~ Johnson Address: 312 Indiana Ave. Oolitic, Ind

Name of Well Drilling Contractor: MUMMA DRILLING, INC.

Address: Washington & Lyons, Indiana

Name of Drilling Equipment Operator: Dean K. Mumma

## INFORMATION ON THE WELL

Completed depth of well: 186 ft. Date well was completed: 11-25-67

Diameter of outside casing or drive pipe: 6 5/8 Length: 65 ft.

Diameter of inside casing or liner: _____ Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☐ Air Rotary ☒ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 100 ft.

Bailer Test: Hours tested _____ Rate 5½ g.p.m. Drawdown 185 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Rufus J. Mumma, Secretary

Date 12-4-67

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

DIVISION OF WATER
DEPARTMENT OF NATURAL RESOURCES, STATE OF INDIANA
STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3-6757

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: From Bedford Going West on 16th Turn Left on 450 Go Approx. 1/4 Mi. 1st Road Left (Bexidion)

Name of owner: Warren Wilman Address: R#1 Bedford.

Name of Well Drilling Contractor: Louie Smith

Address: R#1 Bedford

Name of Drilling Equipment Operator: Same

## INFORMATION ON THE WELL

Completed depth of well: 135 ft. Date well was completed: June 19, 1970

Diameter of outside casing or drive pipe: 6 1/4 Length: 42

Diameter of inside casing or liner: _____ Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 75 ft.

Bailer Test: Hours tested 2 Rate 15 g.p.m. Drawdown 120 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Louie D. Smith

Date June 19, 1970

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| ATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| red soil | 0 | 20 |
| Brown clay | 20 | 25 |
| Shale | 25 | 27 |
| Hard lime | 27 | 29 |
| Lime | 30 | 40 |
| Brown | 40 | 41 |
| Hard lime | 41 | 60 |
| Hard lime white | 60 | 125 |
| Hard lime | 125 | 130 |
| Lime stone | 130 | 170 |
| | | |
| | | |
| | |

DIVISION OF WATER
DEPARTMENT OF NATURAL RESOURCES, STATE OF INDIANA
STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3-6757

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: _____

Congressional township: Lawrence Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: From Bedford going west Turn left on 450 go appro 1/2 mile Stone house on left. (Thomas Chestnut place)

Name of owner: Thomas Chestnut Address: R# 1 Bedford

Name of Well Drilling Contractor: Jamie Smith

Address: R#1 Bedford

Name of Drilling Equipment Operator: Same

## INFORMATION ON THE WELL

Completed depth of well: 179 ft. Date well was completed: Dec 15, 1968

Diameter of outside casing or drive pipe: _____ Length: _____

Diameter of inside casing or liner: 6 1/4 Length: 60

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 130 ft.

Bailer Test: Hours tested 2 Rate 1 1/2 g.p.m. Drawdown 177 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Jamie E. Smith

Date Dec 23, 1968

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

# WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Sand & clay free Boulders | 0 | 39 |
| Gray Limestone | 39 | 166 |
| White Limestone | 166 | 180 |

REMARKS:

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

COUNTY: Lawrence TWP. 5N RGE. 1W NW¼ SW¼ NE¼ SEC. 21

Topo. Map: Bedford West Loc. accepted w/o verification Yes No

El. of grnd. surface at well: 650 Courthouse Loc. By Date

Depth to bedrock: 40 Field Located By Date 8-16

Well log processed by: DR 6/10 Placed in Master Well Log File Date

1700 FWL
2500 FEL

## INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER
DEPARTMENT OF NATURAL RESOURCES, STATE OF INDIANA
STATE OFFICE BUILDING
INDIANAPOLIS, INDIANA 46209
MElrose 3-6757

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: From Bedford going west Turn left on SR 450 go about 1/2 mi turn left at Bejea Shomaita 1st house on left

Name of owner: Roy Baker Address: R 1 Bedford

Name of Well Drilling Contractor: Louis A. Smith

Address: R#1 Bedford

Name of Drilling Equipment Operator: Same

## INFORMATION ON THE WELL

Completed depth of well: 145' ft. Date well was completed: Nov 17 1967

Diameter of outside casing or drive pipe: 6 1/4 Length: 45'1

Diameter of inside casing or liner: _____ Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) _____ ft.

Bailer Test: Hours tested 1 Rate 8 g.p.m. Drawdown 95' ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown 135' ft.

Signature Louis A. Smith

Date Mar. 20, 1967

**FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET**

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

COUNTY: [illegible] TWP. 5N RGE. 1W NE¼ SW¼ SW¼ SEC. 21

Topo. Map: Rockport 4 Quad Loc. accepted w/o verification Yes ___ No ___

El. of grnd. surface at well: ___ Courthouse Loc. By ___ Date ___

Depth to bedrock: ___ Field Located By DWH Date 8-Feb

Well Log processed by: Judy 4/64 Placed in Master Well Log File Date ___

| WATER WELL LOG<br>ATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| clay | 0 | 35 |
| White Lime | 35 | 41 |
| Shell | 41 | 41 |
| Lime | 41 | 120 |
| Soft Shell | 123 | 125 |
| Hard Lime | 125 | 175 |

REMARKS:

## INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

# WATER WELL RECORD

(23)

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: From Bedford going West Thru Lefton 450 To 1st House on Left. Road is 312

Name of owner: Wayne Tirey Address: R#1 Bedford

Name of Well Drilling Contractor: Louie O. Smith

Address: R#1 Bedford

Name of Drilling Equipment Operator: - Same -

## INFORMATION ON THE WELL

Completed depth of well: 150 ft. Date well was completed: Nov. 6, 1961

Diameter of outside casing or drive pipe: 6 1/4 (1 1/2 cement) Length: 32'

Diameter of inside casing or liner: _____ Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 100 ft. (Gravity)

Bailer Test: Hours tested 1 Rate 1 g.p.m. Drawdown _____ ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Louie O. Smith

Date Dec. 30 1961

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| LOGS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| | 0 | 40 |
| Clay | 40 | 90 |
| Shale | 90 | 120 |
| Lime | 120 | 155 |
| Soft | 155 | 175 |
| Lime | | |

REMARKS:

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

COUNTY: Lawrence TWP. 5N RGE. 2W NE¼ SW¼ SW¼ SEC. 21

Topo. Map: Bedford SW Loc. accepted w/o verification Yes — No —

El. of grnd. surface at well: 600 Courthouse Loc. By _____ Date _____

Depth to bedrock: 40 Field Located By _____ Date 8-66

Well Log processed by: DR 5-67 Placed in Master Well Log File Date _____

200 N 75 E

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

RECEIVED
DEC 1959
Dept. of Conservation
Division of
Water Resources

# WATER WELL RECORD

Lawrence Co

## INFORMATION ON WELL LOCATION

County in which well was drilled: ~~Pleasant Run~~ Civil Township: ~~Pleasant~~

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: 1 3mi. northeast of Bedford Ind. on Mt. Pleasant Road.

Name of owner: Elmer Fisk Address: Bedford Ind RR4

Name of Well Drilling Contractor: Floyd Stultz

Address: Bedford Ind RR4

Name of Drilling Equipment Operator: Floyd Stultz

## INFORMATION ON THE WELL

Completed depth of well: 86 ft. Date well was completed: Dec. 22nd-1959

Diameter of outside casing or drive pipe: 6 inches Length: 11 ft.

Diameter of inside casing or liner: 5 5/8 Length: 11 ft.

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☐ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☐ For industry ☐ For public supply ☐ Stock ☒

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) _____ ft.

Bailer Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature: Floyd Stultz

Date Dec. 28, 1959

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| 14 ft. clay | | |
| 56 ft. limestone | | |
| | | |
| | | |
|

Oolitic Quad

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: _____ Range: LOT 30 Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: East Oolitic

Name of owner: Larry Chenault Address: Bedford Ind. RR 2

Name of Well Drilling Contractor: Ernie Umphress & Sons

Address: Bedford Ind. RR 6

Name of Drilling Equipment Operator: Eugene & Charles Umphress

## INFORMATION ON THE WELL

Completed depth of well: 200 ft. Date well was completed: 9/20/62

Diameter of outside casing or drive pipe: 6" Length: 22 ft.

Diameter of inside casing or liner: 5 5/8" Length: _____

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 120 ft. up,

Bailer Test: Hours tested _____ Rate 3 g.p.m. Drawdown 90 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Some people get salt water. & filter water.

Signature [illegible]

Date 9/20/62

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 12' |
| Mud Holes + Boulders | 12' | 19 |
| Blue Limestone - Hard | 19 | 34 |
| " " - Soft | 34 | 60 |
| Blue Shale - Soft | 60 | 200' |

REMARKS:

COUNTY: Lawrence TWP. 5N RGE. 1W SW¼ SE¼ NW¼ SEC. 13

Topo. Map: Bolivia Loc. accepted w/o verification Yes ___ No ___

El. of grnd. surface at well: 540 Courthouse Loc. By ___ Date ___

Depth to bedrock: ___ Field Located By K Date 7-23

Well Log processed by: KHR 10/30/62 Placed in Master Well Log File Date ___

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

1500 E. & W.L.; 1900 S. & N.L.

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
311 WEST WASHINGTON STREET
INDIANAPOLIS, INDIANA

(96)

# WATER WELL RECORD

new. hard
2 tone. white
brown

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

~~Congressional township~~ Range: ~~Number of Section~~ Lot: 19

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: (Fill in as completely as possible) located in East Oolitic on lot 19

Name of owner: James W. + Eva A. Anderson Address: RR 2 Bedford Ind.

Name of Well Drilling Contractor: ERVIE [illegible] SONS

Address: Bedford Ind. RR 2 Box 13

Name of Drilling Equipment Operator: [illegible]

## INFORMATION ON THE WELL

Completed depth of well: 165 ft. Date well was completed: 8/4/62

Diameter of outside casing or drive pipe: 6" Length: 35'

Diameter of inside casing or liner: 5" Length:

Diameter of Screen: Length: Slot size:

Type of Well: Drilled ☒ Gravel Pack ☐ Driven ☐ Other

Use of Well: For home ☒ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☒ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 117 ft.

Bailer Test: Hours tested ____ Rate 4 g.p.m. Drawdown 40 ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested ____ Rate ____ g.p.m. Drawdown ____ ft.

Signature [illegible]

Date 8/14/62

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| DIRT | 0 | 32' |
| White Limestone - SOFT | 32 | 43' |
| Blue " - HARD | 43 | 85' |
| Black Shale - SOFT | 85 | 165' |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| REMARKS: | | |
| | | |
| | | |

COUNTY: Lawrence TWP. 5N RGE. 1W NW¼ SW¼ NW¼ SEC. 3

Topo. Map: Oolitic 7½' Loc. accepted w/o verification Yes ___ No ___

El. of grnd. surface at well: 565 Courthouse Loc. By ___ Date ___

Depth to bedrock: ___ Field Located By ___ Date ___

Well Log processed by: Pete Placed in Master Well Log File Date ___

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

500 E, 3 mi. S. & ¼ mi. W.

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation, 311 West Washington Street, Indianapolis, Indiana.

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS 9, INDIANA

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shawswick

Congressional township: _____ Range: _____ Number of section: _____

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: (Fill in as completely as possible) East Oolitic

Farmers R.D. #54

Name of owner: Felix Chenault Address: Bedford Ind. RR3

Name of Well Drilling Contractor: Floyd Stultz

Address: Bedford Ind. RR4

Name of Drilling Equipment Operator: Floyd Stultz

## INFORMATION ON THE WELL

Completed depth of well: 150 ft. Date well was completed: Sept 21 18 1964

Diameter of outside casing or drive pipe: 6 in. Length: 12 ft.

Diameter of inside casing or liner: 5 5/8 Length: 12 "

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 50 ft.

Bailer Test: Hours tested 8 Rate 1 g.p.m. Drawdown _____ ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Floyd Stultz

Date Oct. 4 1964

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| MATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| | 0 | 12 |
| Clay | 12 | 50 |
| Limestone | 50 | 150 |
| Soapstone | | |

REMARKS:

FOR ADMINISTRATIVE USE ONLY
(Well Driller does not fill out)

COUNTY: Lawrence TWP. 5N RGE. 1W ¼ ¼ ¼ SEC. 3

Topo Map: Dolphin 7½ Loc. accepted w/o verification Yes ___ No ___

Well log classified By Kelp Date 10/9/64 Ground elevation ___ Ft W of EL
Courthouse located By ___ Date ___ Depth to bedrock ___ Ft N of SL
Field located By ___ Date ___ Bedrock elevation ___ Ft E of WL
Placed in master well log file Date ___ Aquifer elevation ___ Ft S of NL

INSTRUCTIONS

This Water Well Record form is designed to record the most essential data concerning a water well. We request that you be as accurate as possible in recording this information as it may be of great assistance in the planning and development of new water supplies.

An accurate location of the well is equally as important as an accurate well log. Please include all information possible in the space provided for well location.

As specified in Chapter 6 of the Acts of 1959, a copy of this report must be submitted within thirty days after the completion of a well to the Division of Water Resources, Indiana Department of Conservation.

3

DIVISION OF WATER RESOURCES
INDIANA DEPARTMENT OF CONSERVATION
609 STATE OFFICE BUILDING
INDIANAPOLIS 9, INDIANA

Laurence Quad

OCT 1964

# WATER WELL RECORD

## INFORMATION ON WELL LOCATION

County in which well was drilled: Lawrence Civil Township: Shrewsbury

Congressional township: _____ Range: _____ Number of section: _____

(Fill in as completely as possible)

Describe in your own words the well location with respect to nearby towns, roads, streets or distinctive landmarks: On state Road 58. 1 mile east of Bedford. RR 3

Name of owner: Mrs. Joseph A. Myers Address: Bedford RR 3

Name of Well Drilling Contractor: Floyd Stultz

Address: Bedford Ind. RR 1

Name of Drilling Equipment Operator: Floyd Stultz

## INFORMATION ON THE WELL

Completed depth of well: 144 ft. Date well was completed: Oct. 5, 1964

Diameter of outside casing or drive pipe: 6 in. Length: 40

Diameter of inside casing or liner: 5 5/8 Length: 40

Diameter of Screen: _____ Length: _____ Slot size: _____

Type of Well: Drilled ☑ Gravel Pack ☐ Driven ☐ Other _____

Use of Well: For home ☑ For industry ☐ For public supply ☐ Stock ☐

Method of Drilling: Cable Tools ☑ Rotary ☐ Rev. Rotary ☐ Jet ☐ Driven ☐

Static water level in completed well (Distance from ground to water level) 60 ft.

Bailer Test: Hours tested 8 Rate 40 g.p.h. Drawdown _____ ft. (Difference between static level and water level at end of test)

Pumping Test: Hours tested _____ Rate _____ g.p.m. Drawdown _____ ft.

Signature Floyd Stultz

Date Oct. 5, 1964

FOR WELL LOG SPACE USE REVERSE SIDE OF THIS SHEET

WATER WELL LOG

| FORMATIONS (Color, type of material, hardness, etc.) | From | To |
|---|---|---|
| Rock + clay | 0 | 40 |
| Limestone | 40 | 144 |
| | | |
| | | |
| | |

# APPENDIX C.2

# 2000 FISH CONSUMPTION ADVISORY

# Angling Indiana - 2000 FISH CONSUMPTION ADVISORY

Group 1 = Unrestricted consumption (at-risk population - limit consumption to 1 meal/week)*
Group 2 = Limit consumption to 1 meal/week (at-risk population - limit to 1 meal/month)*
Group 3 = Limit consumption to 1 meal/month **(at-risk population - DO NOT EAT)***
Group 4 = Limit consumption to 1 meal/2 months **(at-risk population - DO NOT EAT)***
**Group 5 = DO NOT EAT**

*At-risk populations include children under 15, pregnant or nursing women, and those women planning to have children within 6 years

| **County Name** River, Stream, Lake, or Reservoir Name | Fish Species | Fish Length (inches) | Contaminant ■ = PCBs ○ = Mercury | Group (1-5) |
|---|---|---|---|---|
| **Lawrence County** | | | | |
| **All Indiana Rivers and Streams** (unless otherwise specified) | **Carp** | 15-20<br>20-25<br>25+ | ■○<br>■○<br>■○ | 3<br>4<br>5 |
| **East Fork of White River** | **Carp** | 22+ | ■○ | 5 |
| | **Channel Catfish** | 15-21<br>21+ | ■○<br>■○ | 4<br>5 |
| | **Freshwater Drum** | 12-15<br>15+ | ■<br>■ | 4<br>5 |
| | Bigmouth Buffalo | 18+ | ○ | 4 |
| | Flathead Catfish | 10-16<br>16+ | ■<br>■ | 3<br>4 |
| | **Largemouth Bass** | 11-14<br>14+ | ■<br>■ | 4<br>5 |
| | **River Carpsucker** | 13+ | ■ | 5 |
| | Sauger | 14+ | ■○ | 3 |
| | **Shorthead Redhorse** | 14-16<br>16+ | ■<br>■ | 4<br>5 |

| | | | | |
|---|---|---|---|---|
| | **Smallmouth Buffalo** | 15+ | ■ | 5 |
| | Spotted Bass | 10+ | ■○ | 2 |
| | Spotted Sucker | 17+ | ■ | 3 |
| | Striped Bass | 22+ | ■ | 4 |
| **Pleasant Run Creek** | **ALL SPECIES** | **ALL** | ■ | 5 |

Table of Contents

# 2000 INDIANA FISH ADVISORY
# STREAMS AND RIVERS

○ = Mercury ■ = PCBs

Group 2 = 1 meal/week Group 3 = 1 meal/month
Group 4 = 1 meal/2 months Group 5 = DO NOT EAT
(Women and children see advisory groups)

| Location | Species | Fish Size (inches) | Contaminant | Group |
|---|---|---|---|---|
| **All Indiana Rivers and Streams** | | | | |
| ***All Counties*** (unless otherwise specified) | **Carp** | 15-20 | ■○ | 3 |
| | | 20-25 | ■○ | 4 |
| | | **25+** | ■○ | **5** |
| **Big Blue River** | | | | |
| *Henry County* | Creek Chubs | 6-7 | ■ | 3 |
| | | 7+ | ■ | 4 |
| | Rock Bass | 4-7 | ■ | 3 |
| | | 7+ | ■ | 4 |
| | White Suckers | 8-10 | ■ | 3 |
| | | 10+ | ■ | 4 |
| *Rush County* | Creek Chubs | 6+ | ■ | 3 |
| *Shelby County* | Black Redhorse | 11+ | ■ | 3 |
| | Golden Redhorse | 18+ | ■ | 4 |

| | | | | |
|---|---|---|---|---|
| | Northern Hogsucker | 9-10<br>10+ | ■<br>■ | 3<br>4 |
| | Rock Bass | 4-7 | ■ | 3 |
| *Johnson County* | Longear Sunfish | 5+ | ■ | 3 |
| | Northern Hogsucker | 8-10<br>10+ | ■<br>■ | 3<br>4 |
| | Rock Bass | 7+ | ■ | 3 |
| | Smallmouth Bass | 5-8<br>8+ | ■<br>■ | 3<br>4 |

**Big Pine Creek**

| | | | | |
|---|---|---|---|---|
| *Warren County* | Black Redhorse | 13-16<br>16+ | ○<br>○ | 2<br>3 |
| | Channel Catfish | 12-17 | ■ | 2 |
| | Smallmouth Bass | 10-11<br>11+ | ■<br>■ | 2<br>3 |

**Big Raccoon Creek**

| | | | | |
|---|---|---|---|---|
| *Parke County* | Carp | 19-22<br>22+ | ○<br>○ | 2<br>3 |
| | Black Redhorse | 11-17<br>17+ | ○<br>○ | 2<br>3 |
| | Channel Catfish | 17-22<br>22+ | ■<br>■ | 3<br>4 |
| | Spotted Bass | 10-14<br>14+ | ○<br>○ | 2<br>3 |

**Big Walnut Creek**

| | | | | |
|---|---|---|---|---|
| *Putnam County* | Black Redhorse | 11-14 | ○ | 2 |
| | | 14+ | ○ | 3 |
| | River Carpsucker | 9-14 | ○ | 2 |
| | | 14+ | ○ | 3 |
| | Spotted Bass | 9-12 | ○ | 2 |
| | | 12+ | ○ | 3 |

**Blue River**

| | | | | |
|---|---|---|---|---|
| *Harrison County* | Carp | 28-29 | ○ | 2 |
| | | 29+ | ○ | 3 |
| | Channel Catfish | 15+ | ■ | 3 |
| | Rock Bass | 5-7 | ■ | 2 |
| | | 7+ | ■ | 3 |
| | Shorthead Redhorse | 14-17 | ■ | 3 |
| | | 17+ | ■ | 4 |

**Brandywine Creek**

| | | | | |
|---|---|---|---|---|
| *Hancock County* | Northern Hogsucker | 8-11 | ○ | 2 |
| | | 11+ | ○ | 3 |

**Buck Creek**

| | | | | |
|---|---|---|---|---|
| *Delaware County* | Longear Sunfish | 5-6 | ■ | 3 |
| | | 6+ | ■ | 4 |
| | Rock Bass | 6-9 | ■ | 3 |
| | | 9+ | ■ | 4 |
| | Smallmouth Bass | 8-11 | ■○ | 3 |
| | | 11+ | ■○ | 4 |

**Clear Creek**

| | | | | |
|---|---|---|---|---|
| *Monroe County* | **ALL SPECIES** | **ALL** | ■ | **5** |

**Deer Creek**

| | | | | |
|---|---|---|---|---|
| *Carroll County* | Black Redhorse | 13-19 | ○ | 2 |
| | | 19+ | ○ | 3 |
| | Carp | Up to 19 | ■ | 2 |
| | | 19+ | ■ | 3 |
| | Carpsucker | 15-17 | ○ | 2 |
| | | 17+ | ○ | 3 |
| | Smallmouth Bass | 10 | ■ | 2 |
| | | 10+ | ■ | 3 |

**East Fork of White Lick Creek**

| | | | | |
|---|---|---|---|---|
| *Hendricks County* | Creek Chub | 6-9 | ■ | 2 |
| | | 9+ | ■ | 3 |
| | Northern Hogsucker | 8-11 | ■ | 2 |
| | | 11+ | ■ | 3 |
| | Yellow Bullhead | 8-10 | ■ | 2 |
| | | 10+ | ■ | 3 |

**East Fork of the White River**

| | | | | |
|---|---|---|---|---|
| *Bartholomew County* | Golden Redhorse | 8-13 | ■ | 2 |
| | | 13+ | ■ | 3 |
| | Silver Redhorse | 16-18 | ■ | 3 |
| | | 18+ | ■ | 4 |

| | | | | |
|---|---|---|---|---|
| *Jackson County* | Freshwater Drum | 17-18 | ○ | 2 |
| | | 18+ | ○ | 3 |
| | Golden Redhorse | 14-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | Silver Redhorse | 20-22 | ■ | 2 |
| | | 22+ | ■ | 3 |
| | Smallmouth Buffalo | 19-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Bigmouth Buffalo | 18+ | ■○ | 3 |
| *Lawrence County* | **Carp** | **22+** | ■○ | **5** |
| | **Channel Catfish** | 15-21 | ■○ | 4 |
| | | **21+** | ■○ | **5** |
| | **Freshwater Drum** | 12-15 | ■ | 4 |
| | | **15+** | ■ | **5** |
| | Bigmouth Buffalo | 18+ | ○ | 4 |
| | Flathead Catfish | 10-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | **Largemouth Bass** | 11-14 | ■ | 4 |
| | | **14+** | ■ | **5** |
| | **River Carpsucker** | **13+** | ■ | **5** |
| | Sauger | 14+ | ■○ | 3 |
| | **Shorthead Redhorse** | 14-16 | ■ | 4 |
| | | **16+** | ■ | **5** |
| | **Smallmouth Buffalo** | **15+** | ■ | **5** |

| | | | | |
|---|---|---|---|---|
| | Spotted Bass | 10+ | ■○ | 2 |
| | Spotted Sucker | 17+ | ■ | 3 |
| | Striped Bass | 22+ | ■ | 4 |
| *Martin County* | Channel Catfish | 12-14<br>14+ | ■<br>■ | 3<br>4 |
| | Freshwater Drum | 10-12<br>12+ | ■<br>■ | 3<br>4 |
| | Longear Sunfish | 6+ | ■ | 3 |
| | **Shorthead Redhorse** | 14-16<br>**16+** | ■<br>■ | 4<br>**5** |
| | Smallmouth Buffalo | 19+ | ■ | 3 |

**East Fork of Whitewater River**

| | | | | |
|---|---|---|---|---|
| *Wayne County* | Channel Catfish | 12-18<br>18+ | ■<br>■ | 3<br>4 |
| | **Smallmouth Bass** | 8-11<br>**11+** | ■<br>■ | 4<br>**5** |
| *Union County* | Creek Chub | 4-5<br>5+ | ○<br>○ | 2<br>3 |

**Eel River** (West Fork White River Basin)

| | | | | |
|---|---|---|---|---|
| *Greene County* | Bigmouth Buffalo | 18-20<br>20+ | ○<br>○ | 2<br>3 |
| | Channel Catfish | 18+ | ■○ | 2 |

| | | | | |
|---|---|---|---|---|
| | Freshwater Drum | 14-16 | ○ | 2 |
| | | 16+ | ○ | 3 |
| | Sauger | 18+ | ■ | 3 |

**Eel River** (Upper Wabash River Basin)

| | | | | |
|---|---|---|---|---|
| *Whitley County* | Bluegill | 4-6 | ■ | 3 |
| | | 6+ | ■ | 4 |
| | Carp | 11-20 | ■○ | 2 |
| | | 20+ | ■○ | 3 |
| | Northern Hogsucker | 7-10 | ■ | 3 |
| | | 10+ | ■ | 4 |
| | Rock Bass | 7-8 | ○ | 2 |
| | | 8+ | ○ | 3 |
| | White Sucker | 8-12 | ■ | 2 |
| | | 12+ | ■ | 3 |
| *Wabash County* | Northern Hogsucker | 8+ | ■ | 3 |
| *Miami County* | Northern Hogsucker | 9-12 | ○ | 2 |
| | | 12+ | ○ | 3 |
| | Rock Bass | 6-7 | ○ | 2 |
| | | 7+ | ○ | 3 |
| | Smallmouth Bass | 10+ | ■ | 3 |
| *Cass County* | Northern Hogsucker | 8-11 | ○ | 2 |
| | | 11+ | ○ | 3 |
| | Rock Bass | 7-9 | ○ | 2 |
| | | 9+ | ○ | 3 |

**Elkhart River**

| | | | | |
|---|---|---|---|---|
| *Elkhart County* | Rock Bass | 7-9 | ■○ | 3 |
| | | 9+ | ■○ | 4 |
| | Smallmouth Bass | 5-6 | ■ | 3 |
| | White Sucker | 8-13 | ■ | 3 |
| | | 13+ | ■ | 4 |
| **Elliot Ditch** | | | | |
| *Tippecanoe County* | **ALL SPECIES** | **ALL** | ■ | **5** |
| **Fall Creek** | | | | |
| *Madison County* | Black Redhorse | 13-17 | ○ | 2 |
| | | 17+ | ○ | 3 |
| | Carp | 19-22 | ■○ | 3 |
| | | 22+ | ■○ | 4 |
| | Channel Catfish | Up to 22 | ■ | 3 |
| | | 22+ | ■ | 4 |
| | Rock Bass | 5-7 | ■ | 2 |
| | | 7+ | ■ | 3 |
| | Smallmouth Bass | 6-14 | ○ | 2 |
| | | 15-17 | ○ | 3 |
| | | 17+ | ○ | 4 |
| | White Sucker | 12-16 | ○ | 2 |
| | | 16+ | ○ | 3 |
| *Hamilton County* | Carp | 16-23 | ■ | 2 |
| | | 23+ | ■ | 3 |
| | Largemouth Bass | 12-16 | ○ | 2 |
| | | 16+ | ○ | 3 |

**Flatrock River**

| | | | | |
|---|---|---|---|---|
| *Rush County* | Northern Hogsucker | 8-13<br>13+ | ○<br>○ | 2<br>3 |
| | Longear Sunfish | 4-6<br>6+ | ○<br>○ | 2<br>3 |
| | Rock Bass | 5-8<br>8+ | ○<br>○ | 2<br>3 |
| *Shelby County* | Rock Bass | 5-8<br>8+ | ■○<br>■○ | 2<br>3 |

**Grassy Creek**

| | | | | |
|---|---|---|---|---|
| *Kosciusko County* | Largemouth Bass | Up to 14<br>14+ | ○<br>○ | 2<br>3 |

**Great Miami River**

| | | | | |
|---|---|---|---|---|
| *Dearborn County* | **Carp** | 16-20<br>**20+** | ■<br>■ | 4<br>**5** |
| | **Channel Catfish** | **15+** | ■ | **5** |
| | Largemouth Bass | 15-18<br>18+ | ■○<br>■○ | 2<br>3 |
| | White Crappie | 8-11<br>11+ | ■<br>■ | 3<br>4 |

**Greens Fork**

| | | | | |
|---|---|---|---|---|
| *Wayne County* | Creek Chub | 7+ | ○ | 2 |

**Honey Creek**

| | | | | |
|---|---|---|---|---|
| *White County* | Largemouth Bass | Up to 20<br>20+ | ■○<br>■○ | 2<br>3 |

**Iroquois River**

| | | | | |
|---|---|---|---|---|
| *Jasper County* | Carp | 28+ | ■ | 3 |
| *Newton County* | Carp | 28+ | ■ | 3 |

**Juday Creek**

| | | | | |
|---|---|---|---|---|
| *St. Joseph County* | White Sucker | 12-17 | ■ | 2 |
| | | 17+ | ■ | 3 |

**Kankakee River**

| | | | | |
|---|---|---|---|---|
| *LaPorte County* | Bigmouth Buffalo | 16-22 | ○ | 2 |
| | | 22+ | ○ | 3 |
| | Channel Catfish | 17+ | ■ | 3 |
| | Northern Pike | 15+ | ■ | 2 |
| | Quillback | 15-16 | ■ | 3 |
| | Shorthead Redhorse | 13-17 | ■○ | 3 |
| | | 17+ | ■○ | 4 |
| *Lake County* | Bigmouth Buffalo | 18-24 | ■○ | 2 |
| | | 24+ | ■○ | 3 |
| | Carp | 20-22 | ■ | 2 |
| | | 22+ | ■ | 3 |
| | Northern Pike | 31+ | ■ | 2 |
| | Quillback | 13-15 | ■ | 2 |
| | | 15+ | ■ | 3 |
| | Shorthead Redhorse | 14-16 | ■ | 2 |
| | | 16-19 | ■ | 3 |
| | | 19+ | ■ | 4 |

| | | | | |
|---|---|---|---|---|
| | Silver | 18-20 | ■ | 2 |
| | Redhorse | 20+ | ■ | 3 |
| | **Smallmouth** | 18-22 | ■○ | 2 |
| | **Buffalo** | 22-28 | ■○ | 3 |
| | | 28-32 | ■○ | 4 |
| | | **32+** | ■○ | **5** |

**Killbuck Creek**

| | | | | |
|---|---|---|---|---|
| *Madison County* | Largemouth Bass | 16+ | ○ | 3 |
| | Longear | 5-6 | ■ | 3 |
| | Sunfish | 6+ | ■ | 4 |

**Kokomo Creek**

| | | | | |
|---|---|---|---|---|
| *Howard County* | **ALL SPECIES** | **ALL** | ■ | **5** |

**Little Blue River**

| | | | | |
|---|---|---|---|---|
| *Shelby County* | Northern | 8-11 | ■ | 2 |
| | Hogsucker | 11+ | ■ | 3 |

**Little Mississinewa River**

| | | | | |
|---|---|---|---|---|
| *Randolph County* | **ALL SPECIES** | **ALL** | ■ | **5** |

**Little Sugar Creek/Walnut Fork**** (Middle Wabash Basin)

| | | | | |
|---|---|---|---|---|
| *Montgomery County* | **ALL SPECIES** | **ALL** | ■○ | **5** |

*** Fish tissue samples have not been taken from Walnut Fork. However, fish tissue samples taken from Little Sugar Creek (Montgomery Co.) and Sugar Creek (Montgomery Co., I-74 to SR-32) are at No Consumption advisory levels. These two bodies of water are connected by Walnut Fork in Montgomery Co., approximately one river mile in length. Based on these data, a No Consumption advisory will be placed on Walnut Fork to protect human health. Future sampling of Walnut Fork is planned for more comprehensive results.*

**Little Sugar Creek** (East Fork White River Basin)

| | | | | |
|---|---|---|---|---|
| *Hancock County* | Creek Chub | ALL | ■○ | 3 |

**Maumee River**

| | | | | |
|---|---|---|---|---|
| *Allen County* | Channel Catfish | 14-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | Largemouth Bass | 9+ | ■ | 3 |
| | River Redhorse | 12-14 | ■○ | 3 |
| | | 14+ | ■○ | 4 |
| | Rock Bass | 7-8 | ■ | 3 |
| | | 8+ | ■ | 4 |
| | Sauger | 15-24 | ■○ | 2 |
| | | 24+ | ■○ | 3 |
| | Shorthead Redhorse | 14-16 | ■○ | 3 |
| | | 16+ | ■○ | 4 |

**Mississinewa River**

| | | | | |
|---|---|---|---|---|
| *Randolph County* | **Carp** | **17+** | ■ | **5** |
| | **Channel Catfish** | **15+** | ■ | **5** |

| | | | | |
|---|---|---|---|---|
| | **Green Sunfish** | **3+** | ■ | **5** |
| | Longear Sunfish | 3-5 | ■ | 3 |
| | | 5+ | ■ | 4 |
| | White Crappie | 8-10 | ■ | 3 |
| | | 10+ | ■ | 4 |
| *Delaware County* | Bluegill | 6+ | ■ | 2 |
| | Green Sunfish | 4-6 | ■ | 2 |
| | | 6+ | ■ | 3 |
| | Rock Bass | 6-7 | ■○ | 2 |
| | | 7+ | ■○ | 3 |
| *Grant County* | Channel Catfish | 11-13 | ■○ | 2 |
| | | 13+ | ■○ | 3 |
| | Largemouth Bass | 8-11 | ■ | 2 |
| | | 11+ | ■ | 3 |
| | White Crappie | 8-11 | ○ | 2 |
| | | 11+ | ○ | 3 |
| | Carp | 14-19 | ■ | 3 |
| *Miami County* | Carp | 19-20 | ■ | 2 |

**Muddy Fork of Sand Creek**

| | | | | |
|---|---|---|---|---|
| *Decatur County* | Black Redhorse | 12-15 | ○ | 2 |
| | | 15+ | ○ | 3 |
| | Largemouth Bass | 6-11 | ■ | 3 |
| | | 11+ | ■ | 4 |

| | | | | |
|---|---|---|---|---|
| | Northern Hogsucker | 6-10<br>10+ | ■<br>■ | 3<br>4 |
| | White Sucker | 10-13<br>13+ | ○<br>○ | 2<br>3 |

**Muscatatuck River**

| | | | | |
|---|---|---|---|---|
| *Washington County* | Bigmouth Buffalo | 17-26<br>26+ | ■○<br>■○ | 2<br>3 |
| | Smallmouth Buffalo | 22-23<br>23+ | ■○<br>■○ | 2<br>3 |

**Otter Creek**

| | | | | |
|---|---|---|---|---|
| *Vigo County* | Black Redhorse | 10-14<br>14+ | ■<br>■ | 2<br>3 |
| | Golden Redhorse | 14+ | ■○ | 2 |
| | Spotted Bass | 8-13<br>13+ | ○<br>○ | 3<br>4 |

**Patoka River**

| | | | | |
|---|---|---|---|---|
| *Dubois County* | Bigmouth Buffalo | 16-21<br>21+ | ○<br>○ | 2<br>3 |
| | Carp | 15-20<br>20+ | ■<br>■ | 2<br>3 |
| | Freshwater Drum | 13-17<br>17+ | ○<br>○ | 2<br>3 |

| | | | | |
|---|---|---|---|---|
| *Pike County* | Bigmouth Buffalo | 16-21<br>21+ | ○<br>○ | 2<br>3 |
| | Freshwater Drum | 21-22<br>22+ | ■○<br>■○ | 2<br>3 |
| *Gibson County* | Black Buffalo | 24-25<br>25+ | ■○<br>■○ | 2<br>3 |
| | Channel Catfish | 16-18<br>18+ | ■<br>■ | 2<br>3 |
| | Flathead Catfish | 12-18<br>18+ | ■○<br>■○ | 2<br>3 |
| | Freshwater Drum | 14-16<br>16+ | ○<br>○ | 2<br>3 |

**Pigeon Creek** (St. Joseph River Basin)

| | | | | |
|---|---|---|---|---|
| *Steuben County* | Carp | 21-25<br>25+ | ■<br>■ | 3<br>4 |
| | White Sucker | 11-14<br>14+ | ○<br>○ | 2<br>3 |

**Pigeon Creek** (Ohio River Basin)

| | | | | |
|---|---|---|---|---|
| *Vanderburgh County* | **Channel Catfish** | 15-18<br>**18+** | ■<br>■ | 4<br>**5** |
| | Largemouth Bass | 13+ | ■ | 2 |
| | White Crappie | 12+ | ■ | 2 |

**Pipe Creek**

| | | | | |
|---|---|---|---|---|
| *Madison County* | Longear Sunfish | 4+ | ■ | 2 |
| | White Sucker | 10-15 | ■○ | 2 |
| | | 15+ | ■○ | 3 |
| **Pleasant Run Creek** | | | | |
| *Lawrence County* | **ALL SPECIES** | **ALL** | ■ | **5** |
| **Richland Creek** | | | | |
| *Monroe County* | Creek Chub | 6-7 | ■ | 3 |
| | | 7+ | ■ | 4 |
| | Rock Bass | 4-8 | ■○ | 2 |
| | | 8+ | ■○ | 3 |
| | White Sucker | 8-11 | ■○ | 3 |
| | | 11+ | ■○ | 4 |
| *Owen County* | Creek Chub | 5-9 | ■○ | 3 |
| | | 9+ | ■○ | 4 |
| | Longear Sunfish | 4-6 | ■○ | 2 |
| | | 6+ | ■○ | 3 |
| | Rock Bass | 6-7 | ■○ | 2 |
| | | 7+ | ■○ | 3 |
| **Salt Creek** | | | | |
| *Monroe County* ** (tailwaters of Monroe Reservoir | Bluegill | 7+ | ■ | 2 |
| | **Freshwater Drum** | **16+** | ■ | **5** |

| | | | | |
|---|---|---|---|---|
| Dam to Clear Creek) | Striped Bass | 12+ | ■ | 3 |
| | Walleye | 15-21 | ■ | 3 |
| | | 21+ | ■ | 4 |
| | White Crappie | 7+ | ■ | 2 |
| | Yellow Bass | 8+ | ■ | 2 |
| *Monroe County* (confluence of Clear Creek to Lawrence Co.) | **ALL SPECIES** | **ALL** | ■○ | **5** |
| *Lawrence County* | **ALL SPECIES** | **ALL** | ■○ | **5** |

*** This listing is based on limited data. It should be noted that fish migrate. Fish not sampled from these waters may migrate from the confluence of Clear Creek and Salt Creek, 1.3 miles south. Those water bodies have No Consumption advisories. Future sampling of the Salt Creek tailwaters below the Monroe Reservoir Dam is planned for more comprehensive results.*

**Sand Creek**

| | | | | |
|---|---|---|---|---|
| *Decatur County* | Black Redhorse | 14+ | ○ | 2 |
| | Northern Hogsucker | 10-12 | ■ | 3 |
| | | 12+ | ■ | 4 |
| | Spotted Sucker | 13-14 | ○ | 2 |
| | | 14+ | ○ | 3 |
| | White Sucker | 8-11 | ○ | 2 |
| | | 11+ | ○ | 3 |

| | | | | |
|---|---|---|---|---|
| | Yellow Bullhead | 10-12<br>12+ | ■<br>■ | 3<br>4 |
| *Jennings County* | Rock Bass | 6-9<br>9+ | ○<br>○ | 2<br>3 |
| | Spotted Bass | 8-12<br>12+ | ○<br>○ | 2<br>3 |
| | Yellow Bullhead | 8-11<br>11+ | ○<br>○ | 2<br>3 |
| **Silver Creek** | | | | |
| *Union County* | Creek Chub | 6-7<br>7+ | ○<br>○ | 2<br>3 |
| *Floyd County* | Carp | 21-25<br>25+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 17-20<br>20+ | ■<br>■ | 3<br>4 |
| | Freshwater Drum | 15-18<br>18+ | ■○<br>■○ | 2<br>3 |
| | Smallmouth Bass | 15+ | ■ | 2 |
| **Stoney Creek** | | | | |
| *Hamilton County* | **ALL SPECIES** | **ALL** | ■ | **5** |
| **Stouts Creek** | | | | |
| *Monroe County* | Creek Chubs | 4-8<br>8+ | ■○<br>■○ | 2<br>3 |

**St. Joseph River** (Maumee River Basin)

| | | | | |
|---|---|---|---|---|
| *Allen County* | Black Crappie | 9-11 | ■ | 3 |
| | | 11+ | ■ | 4 |
| | Black Redhorse | 13-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | **Channel Catfish** | 20-24 | ■○ | 3 |
| | | 25-26 | ■○ | 4 |
| | | **26+** | ■○ | **5** |
| | Golden Redhorse | 12-13 | ■ | 3 |
| | | 13+ | ■ | 4 |
| | Rock Bass | 7-9 | ■ | 3 |
| | | 9+ | ■ | 4 |

**St. Joseph River** (St. Joseph River Basin)

| | | | | |
|---|---|---|---|---|
| *Elkhart County* | Black Redhorse | 13-17 | ○ | 2 |
| | | 17+ | ○ | 3 |
| | **Channel Catfish** | 20-24 | ■ | **3** |
| | | 25-26 | ■ | **4** |
| | | **26+** | ■ | **5** |
| | Golden Redhorse | 13-25 | ■ | 3 |
| | | 25+ | ■ | 4 |
| | Largemouth Bass | 11-12 | ○ | 2 |
| | | 12+ | ○ | 3 |
| | Rock Bass | 7-9 | ■ | 3 |
| | | 9+ | ■ | 4 |
| | Shorthead Redhorse | 14-17 | ■○ | 3 |
| | | 17+ | ■○ | 4 |

| | | | | |
|---|---|---|---|---|
| | Smallmouth Bass | 9-13 | ○ | 2 |
| | | 13+ | ○ | 3 |
| | Walleye | 16-17 | ○ | 3 |
| | | 17+ | ○ | 4 |
| *St. Joseph County* | Black Redhorse | 14-17 | ■○ | 3 |
| | | 17+ | ■○ | 4 |
| | **Carp** | **20+** | ■○ | **5** |
| | Channel Catfish | 22+ | ■○ | 4 |
| | Golden Redhorse | 13-22 | ■ | 3 |
| | | 22+ | ■ | 4 |
| | **Largemouth Bass** | 15-16 | ■○ | 3 |
| | | 16-18 | ■○ | 4 |
| | | **18+** | ■○ | **5** |
| | Shorthead Redhorse | 15-19 | ■○ | 3 |
| | | 19+ | ■○ | 4 |
| | Smallmouth Bass | 7-9 | ■○ | 2 |
| | | 9+ | ■○ | 3 |
| | Steelhead | 25-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Quillback | 18+ | ■ | 3 |
| | White Sucker | 14-16 | ■ | 3 |
| | | 16+ | ■ | 4 |

**St. Mary's River**

| | | | | |
|---|---|---|---|---|
| *Allen County* | Bigmouth Buffalo | 20-25<br>25+ | ■○<br>■○ | 3<br>4 |
| | Black Redhorse | 12-15<br>15+ | ■○<br>■○ | 2<br>3 |
| | Channel Catfish | 13-15<br>15+ | ■<br>■ | 3<br>4 |
| | Largemouth Bass | Up to 15<br>15+ | ■○<br>■○ | 3<br>4 |
| | Quillback | 9-14<br>14+ | ■○<br>■○ | 2<br>3 |
| | Silver Redhorse | 17+ | ■○ | 3 |
| | White Suckers | 8-11<br>11+ | ■○<br>■○ | 2<br>3 |

**Sugar Creek** (East Fork White River Basin)

| | | | | |
|---|---|---|---|---|
| *Hancock County* | Black Redhorse | 11-13<br>13+ | ○<br>○ | 2<br>3 |
| *Johnson County* | Carp | 27+ | ■ | 3 |
| | Flathead Catfish | 17+ | ■ | 3 |
| | Spotted Bass | 13+ | ○ | 2 |

**Sugar Creek** (Middle Wabash River Basin)

*Montgomery County*

| | | | | |
|---|---|---|---|---|
| (Crawfordsville I74 - SR32) | **ALL SPECIES** | **ALL** | ■ | **5** |
| (Shades State Park) | **Black Redhorse** | 14-16<br>**16+** | ■<br>■ | **4**<br>**5** |
| | Rock Bass | 7+ | ■ | 3 |
| | Smallmouth Bass | 7-11<br>11-15<br>15+ | ■<br>■<br>■ | 2<br>3<br>4 |
| Parke County | Black Redhorse | 12-16<br>16+ | ■<br>■ | 3<br>4 |
| | Smallmouth Bass | 8-11<br>11+ | ■<br>■ | 2<br>3 |
| | Channel Catfish | 12-13<br>13+ | ■<br>■ | 3<br>4 |
| **Tippecanoe River** | | | | |
| *Kosciusko County* | Bluegill | 6+ | ○ | 2 |
| | Redhorse | 17-18<br>18+ | ■<br>■ | 3<br>4 |
| | River Redhorse | 17+ | ○ | 3 |
| | Rock Bass | 5+ | ○ | 2 |
| *Marshall County* | Rock Bass | 9-10<br>10+ | ○<br>○ | 2<br>3 |

| | | | | |
|---|---|---|---|---|
| *Fulton County* | Channel Catfish | 12-23<br>23+ | ■○<br>■○ | 2<br>3 |
| | Northern Hogsucker | 7-12<br>12+ | ○<br>○ | 2<br>3 |
| | Spotted Suckers | 13+ | ○ | 2 |
| | Golden Redhorse | 15-16<br>16+ | ■○<br>■○ | 2<br>3 |
| | Carp | 30-31 | ■○ | 2 |
| *Pulaski County* | Black Redhorse | 16-17<br>17+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 11-12<br>12+ | ■○<br>■○ | 2<br>3 |
| | Longear Sunfish | 3-5<br>5+ | ○<br>○ | 2<br>3 |
| | Northern Hogsucker | 13-15<br>15+ | ○<br>○ | 2<br>3 |
| *Carroll County* | Carp | 21-22 | ■ | 2 |
| **Trail Creek** | | | | |
| *LaPorte County* | **Carp** | **23-25** | ■ | **5** |
| **Wabash River** | | | | |
| *Adams County* | Carp | 17-19 | ■ | 2 |

| | | | | |
|---|---|---|---|---|
| *Wells County* | Channel Catfish | 13-19 | ■○ | 3 |
| | | 19+ | ■○ | 4 |
| | Golden Redhorse | 18+ | ○ | 2 |
| | Rock Bass | 7-10 | ○ | 2 |
| | | 10+ | ○ | 3 |
| | **Sauger** | 13-19 | ■ | 4 |
| | | **19+** | ■ | **5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| | White Crappie | 5-7 | ○ | 2 |
| | | 7+ | ○ | 3 |
| | Yellow Perch | 6-7 | ○ | 2 |
| | | 7+ | ○ | 3 |
| *Huntington County* | Blue Sucker | 21-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Channel Catfish | 13-16 | ■○ | 3 |
| | | 16+ | ■○ | 4 |
| | Freshwater Drum | 12-18 | ■ | 3 |
| | | 18+ | ■ | 4 |
| | Largemouth Bass | 12-14 | ○ | 3 |
| | | 14+ | ○ | 4 |
| | Carp | 18-21 | ■○ | 2 |
| | **Sauger** | 13-19 | ■ | 4 |
| | | **19+** | ■ | **5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |

| | | | | |
|---|---|---|---|---|
| *Wabash County* | Black Redhorse | 16-19<br>19+ | ○<br>○ | 2<br>3 |
| | Blue Sucker | 21-26<br>26+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 13-19<br>19+ | ○<br>○ | 2<br>3 |
| | Freshwater Drum | 12-18<br>18+ | ■<br>■ | 3<br>4 |
| | Quillback | 12-16<br>16+ | ○<br>○ | 2<br>3 |
| | **Sauger** | 13-19<br>**19+** | ■<br>■ | 4<br>**5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| | White Bass | 11-21<br>21+ | ■○<br>■○ | 3<br>4 |
| *Miami County* | Blue Sucker | 21-26<br>26+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 13-19<br>19+ | ■○<br>■○ | 2<br>3 |
| | Freshwater Drum | 12-18<br>18+ | ■<br>■ | 3<br>4 |
| | Quillback | 13-17<br>17+ | ○<br>○ | 2<br>3 |
| | **Sauger** | 13-19<br>**19+** | ■<br>■ | 4<br>**5** |

| | | | | |
|---|---|---|---|---|
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| *Cass County* | Black Redhorse | 16-19 | ○ | 2 |
| | | 19+ | ○ | 3 |
| | Blue Sucker | 21-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Channel Catfish | 13-19 | ■○ | 2 |
| | | 19+ | ■○ | 3 |
| | Freshwater Drum | 12-18 | ■ | 3 |
| | | 18+ | ■ | 4 |
| | Quillback | 13-19 | ○ | 2 |
| | | 19+ | ○ | 3 |
| | Sauger | 13-19 | ■○ | 2 |
| | | 19+ | ■○ | 3 |
| | Smallmouth Bass | 12-16 | ○ | 2 |
| | | 16+ | ○ | 3 |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| | Walleye | 16+ | ○ | 2 |
| *Carroll County* | Blue Sucker | 21-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Channel Catfish | 13-19 | ■○ | 2 |
| | | 19+ | ■○ | 3 |
| | Freshwater Drum | 12-18 | ■ | 3 |
| | | 18+ | ■ | 4 |
| | River Redhorse | 23-26 | ○ | 2 |
| | | 26+ | ○ | 3 |

| | | | | |
|---|---|---|---|---|
| | **Sauger** | 13-19 | ■ | 4 |
| | | **19+** | ■ | **5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| *Tippecanoe County* | Bigmouth Buffalo | 17-20 | ■ | 2 |
| | | 20+ | ■ | 3 |
| | Blue Sucker | 21-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | **Channel Catfish** | **16+** | ■○ | **5** |
| | Flathead Catfish | 15-24 | ■○ | 2 |
| | | 24+ | ■○ | 3 |
| | Freshwater Drum | 12-18 | ■○ | 3 |
| | | 18+ | ■○ | 4 |
| | Golden Redhorse | 20+ | ■ | 3 |
| | Largemouth Bass | 9-14 | ○ | 2 |
| | | 14+ | ○ | 3 |
| | **Quillback** | 13-19 | ■ | 4 |
| | | **19+** | ■ | **5** |
| | River Redhorse | 16-19 | ■○ | 2 |
| | | 19+ | ■○ | 3 |
| | **Sauger** | 13-19 | ■○ | 4 |
| | | **19+** | ■○ | **5** |
| | Paddlefish | 34+ | ■ | 3 |

| | | | | |
|---|---|---|---|---|
| | Smallmouth Bass | 9-12<br>12+ | ■<br>■ | 3<br>4 |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| | White Bass | 6-11<br>11+ | ○<br>○ | 2<br>3 |
| *Fountain County* | Blue Sucker | 21-26<br>26+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 13-19<br>19+ | ■<br>■ | 3<br>4 |
| | Freshwater Drum | 12-18<br>18+ | ■<br>■ | 3<br>4 |
| | **Sauger** | 13-19<br>**19+** | ■<br>■ | 4<br>**5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| *Vermillion County* | Bigmouth Buffalo | 18+ | ■ | 3 |
| *Vigo County* | Bigmouth Buffalo | 21-24<br>24+ | ■<br>■ | 3<br>4 |
| | Blue Sucker | 21-26<br>26+ | ■○<br>■○ | 3<br>4 |
| | Carpsucker | 10+ | ■○ | 2 |
| | Channel Catfish | 13-19<br>19+ | ■○<br>■○ | 3<br>4 |

| | | | | |
|---|---|---|---|---|
| | Flathead Catfish | 10-20<br>20+ | ■○<br>■○ | 2<br>3 |
| | Freshwater Drum | 12-18<br>18+ | ■<br>■ | 3<br>4 |
| | **Sauger** | 13-19<br>**19+** | ■<br>■ | 4<br>**5** |
| | Shovelnose Sturgeon | 30+ | ■ | 3 |
| | **Smallmouth Buffalo** | **25+** | ■○ | **5** |
| | White Bass | 13+ | ■○ | 3 |
| | Wiper | 10-12<br>12+ | ■<br>■ | 3<br>4 |
| *Sullivan County* | Blue Sucker | 21-26<br>26+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 13-19<br>19+ | ■○<br>■○ | 3<br>4 |
| | Flathead Catfish | 16-31<br>31+ | ■○<br>■○ | 3<br>4 |
| | Freshwater Drum | 12-18<br>18+ | ■<br>■ | 2<br>3 |
| | **Sauger** | 13-19<br>**19+** | ■<br>■ | 4<br>**5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |

| | | | | |
|---|---|---|---|---|
| *Knox County* | Blue Sucker | 21-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Channel Catfish | 13-19 | ■ | 2 |
| | | 19+ | ■ | 3 |
| | Freshwater Drum | 12-18 | ■○ | 3 |
| | | 18+ | ■○ | 4 |
| | **Sauger** | 13-19 | ■ | 4 |
| | | **19+** | ■ | **5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| *Gibson County* | Blue Sucker | 21-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Channel Catfish | 13-19 | ■○ | 2 |
| | | 19+ | ■○ | 3 |
| | Freshwater Drum | 12-18 | ■○ | 2 |
| | | 18+ | ■○ | 3 |
| | **Sauger** | 13-19 | ■ | 4 |
| | | **19+** | ■ | **5** |
| | Smallmouth Buffalo | 25+ | ■ | 5 |
| *Posey County* | Blue Sucker | 21-26 | ■ | 3 |
| | | 26+ | ■ | 4 |
| | Channel Catfish | 13-19 | ■ | 2 |
| | | 19+ | ■ | 3 |
| | Flathead Catfish | 11-19 | ■○ | 2 |
| | | 19+ | ■○ | 3 |

| | | | | |
|---|---|---|---|---|
| | **Sauger** | 13-19 | ■ | 4 |
| | | **19+** | ■ | **5** |
| | **Smallmouth Buffalo** | **25+** | ■ | **5** |
| | White Bass | 11-21 | ■○ | 3 |
| | | 21+ | ■○ | 4 |
| | Wiper | 13+ | ■ | 3 |
| **Wea Creek** | | | | |
| *Tippecanoe County* | **ALL SPECIES** | **ALL** | ■ | **5** |
| **West Fork of the White River** | | | | |
| *Randolph County* | Bluegill | 6+ | ○ | 2 |
| | Carp | 15-21 | ■ | 2 |
| | | 21-25 | ■ | 3 |
| | | 25+ | ■ | 4 |
| | Carpsucker | 13-18 | ■ | 3 |
| | | 18+ | ■ | 4 |
| | Channel Catfish | 14-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | Creek Chub | 7-8 | ■○ | 2 |
| | | 8+ | ■○ | 3 |
| | Largemouth Bass | 8+ | ■ | 2 |
| | Longear Sunfish | 3-5 | ■ | 2 |
| | | 5+ | ■ | 3 |

| | | | | |
|---|---|---|---|---|
| | Spotted Sucker | 11-13<br>13+ | ■<br>■ | 3<br>4 |
| | White Sucker | 4-7<br>7+ | ○<br>○ | 2<br>3 |
| *Delaware County* | Black Bullhead | Up to 9<br>9+ | ■<br>■ | 2<br>3 |
| | Carpsucker | 13-18<br>18+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 14-16<br>16+ | ■<br>■ | 3<br>4 |
| | Largemouth Bass | 9-15<br>15+ | ■○<br>■○ | 3<br>4 |
| | Smallmouth Bass | 13-15<br>15+ | ■○<br>■○ | 2<br>3 |
| | Spotted Sucker | 11-13<br>13+ | ■<br>■ | 3<br>4 |
| *Madison County* | Green Sunfish | 4-6<br>6+ | ■<br>■ | 2<br>3 |
| | Longear Sunfish | 5+ | ■ | 2 |
| | Rock Bass | 6+ | ■ | 2 |
| | Spotted Suckers | 11+ | ■ | 3 |

| | | | | |
|---|---|---|---|---|
| *Hamilton County* | **Carp** | 17-20 | ■ | 4 |
| | | **20+** | ■ | **5** |
| | Carpsucker | 13-18 | ○ | 3 |
| | | 18+ | ○ | 4 |
| | Largemouth Bass | 11-17 | ■○ | 3 |
| | | 17+ | ■○ | 4 |
| | Longear Sunfish | 4-9 | ■ | 3 |
| | | 9+ | ■ | 4 |
| *Marion County* | Bluegill | 7+ | ■ | 2 |
| | **Carp** | **19+** | ■ | **5** |
| | **Channel Catfish** | 14-18 | ■ | 3 |
| | | 18-24 | ■ | 4 |
| | | **24+** | ■ | **5** |
| | Flathead Catfish | 13-15 | ■○ | 3 |
| | | 15+ | ■○ | 4 |
| | Largemouth Bass | 11-13 | ■ | 2 |
| | | 13+ | ■ | 3 |
| | **Quillback** | 13-18 | ■ | 4 |
| | | **18+** | ■ | **5** |
| | Spotted Sucker | 11-13 | ■○ | 3 |
| | | 13+ | ■○ | 4 |
| *Morgan County* | Black Redhorse | 15-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | Carp | 16-27 | ■ | 3 |
| | | 27+ | ■ | 4 |

| | | | | |
|---|---|---|---|---|
| | Channel Catfish | 14-16<br>16+ | ■○<br>■○ | 3<br>4 |
| | Flathead Catfish | 11-17<br>17+ | ○<br>○ | 2<br>3 |
| | Gizzard Shad | 10+ | ■ | 2 |
| | Largemouth Bass | 12+ | ■ | 3 |
| | Quillback | 13-18<br>18+ | ■<br>■ | 3<br>4 |
| | River Carpsucker | 12-15<br>15+ | ■<br>■ | 3<br>4 |
| | Smallmouth Bass | 13-15<br>15+ | ■<br>■ | 3<br>4 |
| | Spotted Sucker | 11-13<br>13+ | ■<br>■ | 3<br>4 |
| *Owen County* | Bigmouth Buffalo | 16-24<br>24+ | ■○<br>■○ | 2<br>3 |
| | Carpsucker | 13-18<br>18+ | ■<br>■ | 3<br>4 |
| | Channel Catfish | 14-16<br>16+ | ■<br>■ | 3<br>4 |
| | Spotted Sucker | 11-13<br>13+ | ■<br>■ | 3<br>4 |
| | White Bass | 14-15<br>15+ | ■○<br>■○ | 3<br>4 |

| | | | | |
|---|---|---|---|---|
| *Greene County* | Bigmouth Buffalo | Up to 20 | ■ | 2 |
| | | 20+ | ■ | 3 |
| | Carpsucker | 13-18 | ■ | 2 |
| | | 18+ | ■ | 3 |
| | Channel Catfish | 14-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | Spotted Sucker | 11-13 | ■ | 3 |
| | | 13+ | ■ | 4 |
| *Daviess County* | Bigmouth Buffalo | 17-19 | ■○ | 2 |
| | Carpsucker | 13-18 | ■ | 3 |
| | | 18+ | ■ | 4 |
| | Channel Catfish | 14-16 | ■ | 3 |
| | | 16+ | ■ | 4 |
| | Flathead Catfish | 11-14 | ■○ | 2 |
| | | 14+ | ■○ | 3 |
| | Spotted Sucker | 11-13 | ■ | 3 |
| | | 13+ | ■ | 4 |
| | White Bass | 11-14 | ■○ | 3 |
| | | 14+ | ■○ | 4 |
| *Pike County* | Bigmouth Buffalo | 21-25 | ■○ | 2 |
| | | 25+ | ■○ | 3 |
| | Carpsucker | 13-18 | ■ | 3 |
| | | 18+ | ■ | 4 |
| | Channel Catfish | 14-17 | ■ | 3 |
| | | 17+ | ■ | 4 |

| | | | | |
|---|---|---|---|---|
| | Flathead Catfish | 9-16<br>16+ | ■<br>■ | 2<br>3 |
| | Freshwater Drum | 12-14<br>14+ | ■○<br>■○ | 2<br>3 |
| | Quillback | 14-15<br>15+ | ○<br>○ | 3<br>4 |
| | River Carpsucker | 15-17<br>17+ | ■<br>■ | 3<br>4 |
| | Smallmouth Bass | 7-12<br>12+ | ○<br>○ | 2<br>3 |
| | Spotted Bass | 9+ | ■ | 3 |
| | Spotted Sucker | 11-13<br>13+ | ■<br>■ | 3<br>4 |
| *Gibson County* | Carpsucker | 6-18<br>18+ | ■○<br>■○ | 3<br>4 |
| | Channel Catfish | 14-17<br>17+ | ■<br>■ | 3<br>4 |
| | Freshwater Drum | 12-14<br>14+ | ■<br>■ | 2<br>3 |
| | Largemouth Bass | 11-17<br>17+ | ○<br>○ | 2<br>3 |
| | Quillback | Up to 11<br>11+ | ■<br>■ | 2<br>3 |
| | River Carpsucker | 16-18<br>18+ | ■○<br>■○ | 3<br>4 |

| | | | | |
|---|---|---|---|---|
| | Spotted | 11-13 | ■ | 3 |
| | Sucker | 13+ | ■ | 4 |

**West Fork of the Whitewater River**

| | | | | |
|---|---|---|---|---|
| *Wayne* | Creek Chub | 5-7 | ○ | 2 |
| *County* | | 7+ | ○ | 3 |
| *Fayette* | Black | 11-14 | ■○ | 2 |
| *County* | Redhorse | 14+ | ■○ | 3 |
| | Largemouth | 15-17 | ○ | 3 |
| | Bass | 17+ | ○ | 4 |
| | Quillback | 15+ | ○ | 3 |
| | Smallmouth | 7-9 | ■○ | 2 |
| | Bass | 9+ | ■○ | 3 |

**White Lick Creek**

| | | | | |
|---|---|---|---|---|
| *Hendricks* | Channel | 21-22 | ■○ | 2 |
| *County* | Catfish | 22+ | ■○ | 3 |
| | Smallmouth | 8-14 | ■○ | 2 |
| | Bass | 14+ | ■○ | 3 |
| *Morgan* | Channel | 20+ | ■○ | 2 |
| *County* | Catfish | | | |
| | Smallmouth | 8-12 | ■ | 2 |
| | Bass | 12+ | ■ | 3 |

**Whitewater River**

| | | | | |
|---|---|---|---|---|
| *Dearborn County* | Black Redhorse | 14-16<br>16+ | ■○<br>■○ | 2<br>3 |
| | Channel Catfish | 15-23<br>23+ | ■○<br>■○ | 3<br>4 |
| | Freshwater Drum | 14-15<br>15+ | ■○<br>■○ | 2<br>3 |
| **Wildcat Creek** | | | | |
| *Howard County* (Downstream of the Waterworks Dam in Kokomo) | **ALL SPECIES** | **ALL** | ■ | **5** |
| *Carroll County* | **ALL SPECIES** | **ALL** | ■ | **5** |
| *Tippecanoe County* | **Freshwater Drum** | 10-12<br>**12+** | ■<br>■ | 4<br>**5** |
| | Golden Redhorse | 12-14<br>14+ | ■<br>■ | 3<br>4 |
| | Quillback | 12-13<br>13+ | ■<br>■ | 3<br>4 |
| | White Bass | 7-8<br>8+ | ■<br>■ | 2<br>3 |
| | Channel Catfish | 10-16<br>16+ | ■<br>■ | 3<br>4 |
| | Spotted Bass | 8+ | ■ | 3 |
| **Young's Creek** | | | | |

| | | | | |
|---|---|---|---|---|
| *Johnson County* | Northern Hogsucker | 7-10<br>10+ | ■<br>■ | 2<br>3 |

Table of Contents

Indiana

Agency Listing | Privacy Policy
Terms of Use | Contact Network

SEARCH INDIANA GO!

# APPENDIX C.3

# WETLANDS INVENTORY MAP

# APPENDIX C.4

# FLOOD INSURANCE RATE MAP

*MAY 25, 2001*

# APPENDIX C.5

# ENDANGERED SPECIES LIST

# Distribution of Federally Threatened (T), Endangered (E), and Proposed (P) Species in Indiana (1999)

For more information about threatened and endangered species in Indiana, contact the U.S. Fish & Wildlife Service office at 620 South Walker Street, Bloomington, Indiana 47403-2121 (812/334-4261)

| Species | Status | Counties | Habitat |
|---|---|---|---|
| **Mammals** | | | |
| Gray bat (*Myotis grisescens*) | Endangered | Clark, Crawford, Floyd, Harrison | Caves |
| Indiana bat (*Myotis sodalis*) | Endangered | Statewide<br><br>CRITICAL HABITAT: Big Wyandotte Cave (Crawford County), Ray's Cave (Greene County) | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| **Birds** | | | |
| Bald eagle (*Haliaeetus leucocephalus*) | Threatened | Statewide | Wintering |
| Bald eagle (*Haliaeetus leucocephalus*) | Threatened | Brown, DuBois, Greene, Martin, Monroe, Morgan, Orange, Owen, Parke | Recent: Nesting & Wintering |
| Peregrine falcon (*Falco peregrinus*) | Endangered | Lake | Breeding |
| Peregrine falcon (*Falco peregrinus*) | Endangered | Allen and Marion | Hacking Site |
| Least Tern (*Sterna antillarum*) | Endangered | Gibson | Breeding |
| **Reptiles** | | | |
| Copperbelly water snake (*Nerodia erythrogaster neglecta*) | Threatened | Kosciusko, St. Joseph, Steuben | Wooded and permanently wet areas such as oxbows, sloughs, brushy ditches and floodplain woods |
| **Mussels** | | | |
| Clubshell (*Pleurobema clava*) | Endangered | Carroll, Dekalb, Fulton, Kosciusko, Marshall, Pulaski, Tippecanoe, White | Rivers |

| Species | Status | Counties | Habitat |
|---|---|---|---|
| Cracking pearlymussel *(Hemistena lata)* | Endangered | Knox (possibly extirpated) | Rivers |
| Fanshell (*Cyprogenia stegaria*) | Endangered | Carroll, Martin, Sullivan, Tippecanoe, Wabash, White | Rivers |
| Fat pocketbook (*Potamilus capax*) | Endangered | Gibson, Knox, and Posey | Rivers |
| Northern rifflesheil (*Epioblasma torulosa rangiana*) | Endangered | Dekalb, Pulaski | Rivers |
| Orange-footed pearlymussel (*Plethobasus cooperianus*) | Endangered | Gibson (possibly extirpated) | Rivers |
| Pink mucket pearlymussel *(Lampsilis orbiculata)* (=*P. abrupta*) | Endangered | Posey | Rivers |
| Ring pink (*Obovaria retusa)* | Endangered | Fountain, Gibson, Harrison, Knox, Lawrence, Posey, Sullivan, Tippecanoe, Vermilion, Vigo, Warren; possibly extirpated from those counties | Rivers |
| Rough pigtoe (*Pleurobema plenum*) | Endangered | Martin | Rivers |
| Tubercled-blossom pearlymussel *(Epioblasma torulosa torulosa)* | Endangered | Carroll, Fountain, Gibson, Fulton, Jackson, Knox, Posey, Pulaski, Sullivan, Tippecanoe, Vermilion, Vigo, Warren; possibly extirpated from those counties | Rivers |
| White cat's paw pearlymussel (*Epioblasma obliquata perobliqua*) | Endangered | Dekalb | Rivers |
| White warty-back pearlymussel *(Plethobasis cicatricosus*) | Endangered | Posey, Tippecanoe, Vermilion, Vigo; possibly extirpated from those counties | Rivers |
| **Insects** | | | |
| Mitchell's satyr *(Neonympha mitchellii*) | Endangered | LaGrange, LaPorte | Fens |

| Species | Status | Counties | Habitat |
|---|---|---|---|
| Karner blue butterfly (*Lycaeides melissa samuelis*) | Endangered | Lake, Porter | Pine barrens and oak savannas on sandy soils and containing wild lupines *(Lupinus perennis)*, the only known food plant of larvae. |
| **Plants** | | | |
| Mead's milkweed | Threatened | Lake | Prairies |
| Pitcher's thistle (*Cirsium pitcheri*) | Threatened | Lake, Porter | Lakeshores; stabilized dunes and blowout areas |
| Running buffalo clover (*Trifolium stoloniferum*) | Endangered | Dearborn, Ohio, Ripley, Switzerland | Disturbed bottomland meadows |

## Distribution of Federally Threatened (T), Endangered (E), and Proposed (P) Species in Indiana (1999)

For more information about threatened and endangered species in Indiana, contact the U.S. Fish & Wildlife Service office at 620 South Walker Street, Bloomington, Indiana 47403-2121 (812/334-4261)

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Allen | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Bartholomew | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Blackford | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Boone | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Brown | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Carroll | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| | Fanshell pearly mussel (*Cyprogenia stegaria*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Cass | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Clark | Gray bat (*Myotis grisescens*) | E | Caves |
| | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Clay | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Clinton | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Crawford | Gray bat (*Myotis grisescens*) | E | Caves |
| | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| De Kalb | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| | Northern riffleshell (*Epioblasma torulosa rangiana*) | E | Rivers |
| | White cat's paw pearlymussel (*Epioblasma obliquata perobliqua*) | E | Rivers |
| Dearborn | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Running buffalo clover (*Trifolium stoloniferum*) | E | Disturbed bottomland meadows |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Delaware | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Dubois | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Elkhart | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Floyd | Gray bat (*Myotis grisescens*) | E | Caves |
| | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Fountain | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Fulton | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Gibson | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Least Tern; interior population (*Sterna antillarum athalassos*) | E | |
| | Fat pocketbook (*Potamilus capax*) | E | Rivers |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Greene | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Hamilton | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Hancock | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Harrison | Gray bat (*Myotis grisescens*) | E | Caves |
| | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Hendricks | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Henry | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Howard | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Huntington | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Jackson | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Jasper | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Jay | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Jefferson | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Jennings | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Johnson | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Knox | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Fat pocketbook (*Potamilus capax*) | E | Rivers |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Kosciusko | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Copperbelly water snake (*Nerodia erythrogaster neglecta*) | T | Wooded and permanently wet areas such as oxbows, sloughs, brushy ditches and floodplain woods |
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| La Porte | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Mitchell's satyr butterfly (*Neonympha mitchellii mitchellii*) | E | Fens |
| Lagrange | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Mitchell's satyr butterfly (*Neonympha mitchellii mitchellii*) | E | Fens |
| Lake | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Karner blue butterfly (*Lycaeides melissa samuelis*) | E | Pine barrens and oak savannas on sandy soils and containing wild lupines *(Lupinus perennis)*, the only known food plant of larvae. |
| | Pitcher's thistle (*Cirsium pitcheri*) | T | Lakeshores; stabilized dunes and blowout areas |
| | Mead's milkweed (*Asclepias meadii*) | T | Prairies |
| Lawrence | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Madison | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Marion | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Marshall | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| Martin | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Fanshell pearly mussel (*Cyprogenia stegaria*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| Miami | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Monroe | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Montgomery | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Morgan | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Noble | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Ohio | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Running buffalo clover (*Trifolium stoloniferum*) | E | Disturbed bottomland meadows |
| Orange | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Owen | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Parke | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Pike | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Porter | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Karner blue butterfly (*Lycaeides melissa samuelis*) | E | Pine barrens and oak savannas on sandy soils and containing wild lupines *(Lupinus perennis)*, the only known food plant of larvae. |
| | Pitcher's thistle (*Cirsium pitcheri*) | T | Lakeshores; stabilized dunes and blowout areas |
| Posey | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Fat pocketbook (*Potamilus capax*) | E | Rivers |
| | Pink mucket (*Lampsilis abrupta*) | E | Rivers |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Pulaski | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| | Northern riffleshell (*Epioblasma torulosa rangiana*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Putnam | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Randolph | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | Y | Wintering |
| Ripley | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| | Running buffalo clover (*Trifolium stoloniferum*) | E | Disturbed bottomland meadow |
| Rush | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Shelby | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| St. Joseph | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Copperbelly water snake (*Nerodia erythrogaster neglecta*) | T | Wooded and permanently wet areas such as oxbows, sloughs, brushy ditches and floodplain woods |
| Starke | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| Steuben | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Copperbelly water snake (*Nerodia erythrogaster neglecta*) | T | Wooded and permanently wet areas such as oxbows, sloughs, brushy ditches and floodplain woods |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Sullivan | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Fanshell pearly mussel (*Cyprogenia stegaria*) | E | Rivers |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Switzerland | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Running buffalo clover (*Trifolium stoloniferum*) | E | Disturbed bottomland meadow |
| Tippecanoe | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| | Fanshell pearlymussel (*Cyprogenia stegaria*) | E | Rivers |
| | Ring pink (*Obovaria retusa*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Vermillion | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Vigo | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | E | Rivers |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Wabash | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Fanshell pearlymussel (*Cyprogenia stegaria*) | E | Rivers |

| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| Warren | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |
| | Ring Pink (*Obovaria retusa*) | E | Rivers |
| | Rough pigtoe (*Pleurobema plenum*) | E | Rivers |
| | Tubercled-blossom pearlymussel (*Epioblasma torulosa torulosa*) | E; possibly extirpated | Rivers |
| Washington | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Rivers |
| Wayne | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Rivers |
| Wells | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Rivers |
| White | Indiana bat (*Myotis sodalis*) | E | Hibernaria = Caves and mines; Maternity and foraging habitat = small stream corridors with well developed riparian woods; upland forests |
| | Bald eagle (*Haliaeetus leucocephalus*) | T | Wintering |


| COUNTY | SPECIES | STATUS | HABITAT |
|---|---|---|---|
| | Clubshell (*Pleurobema clava*) | E | Rivers |
| | Fanshell pearlymussel (*Cyprogenia stegaria*) | E | Rivers |

E = Endangered
T = Threatened

*MAY 25, 2001*

# APPENDIX D.1

# CITY OF BEDFORD ZONING DISTRICTS




HNTB
ARCHITECTS ENGINEERS PLANNERS
INDIANAPOLIS, INDIANA

Unknown Units: View1

# City of Bedford

July 14, 2000

*MAY 25, 2001*

# APPENDIX D.2

# REPORT OF THE SOIL AND FOUNDATION INVESTIGATION FOR THE PROPOSED WATER POLLUTION CLARIFICATION SYSTEM

CENTRAL FOUNDRY DIVISION
GENERAL MOTORS CORPORATION
BEDFORD PLANT
BEDFORD, INDIANA 47421

# REPORT OF THE SOIL AND FOUNDATION INVESTIGATION FOR THE PROPOSED WATER POLLUTION CLARIFICATION SYSTEM, BEDFORD, INDIANA

PREPARED BY
PITTSBURGH TESTING LABORATORY
November, 1972 IND 2239

PITTSBURGH TESTING LABORATORY
ESTABLISHED 1881
INSPECTING ENGINEERS AND CHEMISTS
2828 N. WEBSTER AVENUE
INDIANAPOLIS, INDIANA 46219

AS A MUTUAL PROTECTION TO CLIENTS, THE PUBLIC AND OURSELVES, ALL REPORTS ARE SUBMITTED AS THE CONFIDENTIAL PROPERTY OF CLIENTS, AND AUTHORIZATION FOR PUBLICATION OF STATEMENTS, CONCLUSIONS OR EXTRACTS FROM OR REGARDING OUR REPORTS IS RESERVED PENDING OUR WRITTEN APPROVAL.

Nov. 21, 1972 IND 2239

Central Foundry Division
General Motors Corporation
Bedford Plant
Bedford, Indiana 47421

Sub: Soil and Foundation Investigation
Proposed Water Pollution Clarification
System, Bedford, Indiana

Gentlemen:

In accordance with your authorization, we have completed a soil and foundation investigation at the subject site and are pleased to submit the following report on the results of the investigation:

## PURPOSE AND SCOPE

The purpose of this report is to present the results of our findings along with our interpretation of these, and recommendations to aid design and construction of foundations for the proposed Water Pollution Clarification System. These recommendations were developed on the basis of the specific information obtained at the boring locations during this investigation. The general stratification of the subsurface conditions other and poorer than those encountered may exist between boring locations and require some adjustments during construction.

## PROJECT CHARACTERISTICS

The project site is located adjacent to and south of the main GMC Central Foundry Facility in the City of Bedford, Indiana. This clarification System will consist of a Control Room with attached Hydraulic Storage Pit, a north and a south Clarithickener, and a Reactor Clarifier. Some of the more important information about these units follows:

## Control Room With Attached Hydraulic Storage Pit

The Control Room is a one-story building covering an area 22 feet by 29 feet. Its finished floor elevation will reportedly be 696.00. Standard brick and block construction will be used. A basement is proposed with poured concrete walls. Maximum loads are expected to be relatively light.

A Hydraulic Storage Pit is to be located adjacent to the north wall of Control Room. It will cover an area 11 feet by 22 feet. The Pit bottom will reportedly be at elevation 681.00.

## North and South Clarithickeners

Two clarithickeners are proposed for this facility. They will be 45 feet in diameter and 19'-6 3/4" deep. Their top elevation will be 696.5 and their bottom elevation will be 676.94.

## Reactor Clarifier

The Reactor Clarifier will be 44 feet in diameter and will be 16'- 8" deep. Its top elevation will be 693.5 and its bottom elevation is proposed at 673.83.

Three ponds currently exist at the site. The water elevations are 690.9, 689.2 and 686.8 in ponds Nos. 1, 2 and 3 respectively. The proposed facilities will be located at least partially in the area of pond No. 1, and in some cases completely. It is our understanding that a parking area is proposed in the area of pond No.2.

## Field Investigation

Four (4) borings were put down at the subject site at locations shown on the Location of Boring drawing contained in the Appendix to this report. The borings were generally drilled to depths ranging between about 7.5 and 22 feet below existing ground.

Borings were advanced by using a truck-mounted rotary drilling rig equipped to secure both disturbed and undisturbed soil samples. To determine the relative density of cohesionless soils, the consistency of cohesive soils, and to secure samples for visual identification of the soil types encountered, standard penetration tests were made in accordance with A.S.T.M. D-1586, at about 2.5 to 5.0 foot intervals of depth in each boring. Typical samples of the soils encountered were sealed in glass jars and sent to the laboratory.

Standard penetration tests are made by driving a standard 1-3/8" I.D. split barrel penetration spoon one-foot into undisturbed soil by

means of a 140 lb. drop weight free falling a distance of thirty inches.

A graphical representation of the logs of borings is given in the Appendix for reference. These sheets include:

1. The results of the standard penetration tests (N values).

2. Visual classifications of soils encountered at different depths.

3. Ground water level information where it was encountered.

FOUNDATION SUBSOIL CONDITIONS

The soil borings indicate that the foundation subsoil conditions at the site are somewhat variable. Surficial deposits in the area of borings 1 and 2 consist primarily of miscellaneous soil fill material. This material was extremely variable in both composition and condition. It generally extended to depths ranging between 7.5 and 20 feet below existing ground.

Below the miscellaneous fill at borings 1 and 2, and starting at the surface at borings 3 and 4 are various layers of medium stiff to very stiff clay or silty clay. These soils extended to the bottom of the borings. Auger refusal was encountered at depths of 22, 7.5 and 8 feet below existing ground at the location of borings 2, 3 and 4, respectively.

Free ground water level observations were made upon completion of the drilling. These observations indicate the water table was encountered at depths ranging between 5 and 10 feet below existing ground.

LABORATORY INVESTIGATION

All of the samples obtained in the field were brought to the laboratory for examination and testing. The field classifications were checked and modified if it was considered necessary.

Several unconfined compression tests were performed to assess the shear strength of the foundation soils. To obtain information about the soil index properties, natural moisture content and dry density determinations were performed. The results obtained from the various tests were tabulated and placed in the Appendix for reference.

ENGINEERING ANALYSES

Soil bearing capacity was computed as a function of depth below the lowest adjacent grade. The footings were considered to be at a minimum depth of 3 feet below final grade. The bearing capacity safety factor was on the order of 3 and was in some areas well above this limit. This safety factor was included in the recommended soil pressures.

The soil pressures recommended for use on this project were based on bearing capacity considerations and settlement evaluations of the foundation soils encountered. The settlements were estimated on the basis of the results of the field tests. The recommended soil pressure were adjusted so as to limit the estimated total settlements to about one (1) inch.

The evaluation was made on the basis of the least favorable soil conditions combined with the most severe loading conditions. It is therefore anticipated that the settlements in general will be less than the above limit, unless otherwise stated. Differential movements are expected to be on the order of three quarters of an inch maximum which is about 75 percent of the expected settlement. Most structures can readily tolerate such movements, however, it would be advisable to review the design of the proposed structure for this project considering the above mentioned settlement limits.

CONCLUSIONS AND RECOMMENDATIONS
GENERAL

1. The bottom of all excavations should be inspected at the time of construction by a representative of Pittsburgh Testing Laboratory to assure that all undesirable material has been removed, and the desired bearing material has been reached. The entire area should be proof-rolled with a heavy roller, in an attempt to locate soft surface areas. All soft soils, miscellaneous fill and organic soils should be removed and replaced with suitable fill material.

2. The materials used as backfill should be inspected by a soils engineer or his representative and approved prior to being used. A sufficient number of field density tests should be performed to assure that the specified compaction requirements are being fulfilled.

3. All soil placed under footings should be compacted to at least 100 percent of the maximum dry density as determined by A.S.T.M. Designation D-1557.

4. All soil placed around or above footings should be compacted to at least 93% of the maximum dry density as determined by A.S.T.M. Designation D-1557.

5. Rigid moisture control of soils should be maintained during construction of controlled backfills. The soils should be compacted at or near the optimum moisture content as determined by A.S.T.M. Designation D-1557.

6. If a compacted fill is used under footings at the site, it is recommended that the engineered compacted fill be constructed from a granular non-plastic, well-graded material. The fill should be compacted in layers not to exceed six to eight inches in compacted thickness. Pit run or bank run granular soils, road base material and other similar soils are usually good materials for this type of compacted fill.

The width of the compacted fill under the footings should be equal to the width of the footing plus a dimension equal to two times the thickness dimension of the engineered compacted fill under the bottom of the footing.

7. Extreme care should be taken not to allow weakening of the foundation soils because of prolonged atmospheric exposure, disturbance or an increase in water content of the foundation soils. Should a delay in concrete placement be anticipated, footing excavations should be finished about 6 inches high and subsequently cut to grade immediately before placement.

8. It is recommended that the floor slabs be supported on at least 12 inches of base course of relatively clean granular material such as sand, sand and gravel or crushed stone. This granular base course will help distribute concentrated loads and equalize moisture conditions beneath the slabs.

9. The floor slab should be floating, that is not structurally connected to the walls or foundations. This is to minimize the possibility of undue cracking of the floor slab because of differential movement between the slab and the foundation. Such movements may be excessive for rigid connections between the foundations and a ground supported slab.

10. All continuous (wall type) footings should be a minimum of 18 inches in width for bearing capacity considerations.

11. Adequate drainage should be provided at the site. All final grades, pavements and parking areas should be sloped away from the structure.

Specific

1. Due to the extremely variable nature and condition of the surficial fill material encountered at borings 1 and 2, it would be advisable to completely remove this material within the structure and any other paved areas, and replace it with an engineered compacted fill. Before backfilling, the area should be proof-rolled with a heavy roller and any soft areas disclosed by this operation should also be removed.

2. If proposed structures or paved areas are to be placed over existing ponds, the ponds should be drained, soft sediments should be removed down to stable soils, and backfilling should be accomplished with an engineered compacted fill. Proof rolling would be advisable in these areas also. These operations should be supervised by a representative of Pittsburgh Testing Laboratory.

3. If the above recommendations are followed, a net allowable bearing pressure of 2,000 psf can be used. When using net pressures, the weight of the footing and backfill over the footing need not be considered.

4. If the footings are designed as recommended above, the resulting settlements should be within tolerable limits.

5. Due to the depth of some proposed excavations, it is anticipated that dewatering problems will be encountered.

6. It is likely that bedrock will be encountered before reaching the anticipated bottom depth at the location of the south clari-thickener and the Reactor Clarifier. The bedrock may also be encountered in some of the other deeper excavation locations, but additional borings would be needed to verify this.

7. The structures located below the water table will have to be designed to resist the uplift forces resulting from the high water table in the area.

We appreciate this assignment and trust the above information will provide the data required for design purposes. If we can be of any further assistance, please advise.

Respectfully submitted,
PITTSBURGH TESTING LABORATORY

N. Ray Neel, Manager
Indianapolis District

cc: 3 Client
NRN/jp

## Appendix


1. Map of Boring Locations
2. Chart of Soil Classification
3. Log of Borings
4. Chart of Unconfined Compressive Strength of Soils

NOV 2 1972

Central Foundry Division
Bedford, Indiana

Pittsburgh Testing Laboratory
Nov. 22, 1972 IND 2239

## Boring Location Map




Form 1321

# PITTSBURGH TESTING LABORATORY
## LOG OF BORINGS

Client: Central Foundry Division
Project: Water Clarification System

Date: Nov. 21, 1972
Order No. IND 2239




Form 1321

# PITTSBURGH TESTING LABORATORY
## LOG OF BORINGS

Client: Central Foundry Division
Project: Water Clarification System

Date: Nov. 21, 1972
Order No. IND 2239



Central Foundry Division
General Motors Corporation
Bedford Plant
Bedford, Indiana 47421

Pittsburgh Testing Laboratory
IND 2239 Nov. 22, 1972

## Unconfined Compressive Strength of Soils

| Sample # | Boring No. | Depth in Ft. | % Moisture | Wet Density lbs. Cu. Ft | Dry Density lbs. Cu. ft. | Load Tons Ft. 2 |
|---|---|---|---|---|---|---|
| 1 | 1 | 7½-9 | 30.7 | 109.3 | 83.6 | 1.47 |
| 2 | 2 | 5-6½ | 29.3 | 104.5 | 80.8 | 1.82 |
| 1 | 2 | 15-16½ | 25.1 | 135.5 | 108.3 | 0.69 |

# SOIL CLASSIFICATION SYSTEM

| MAJOR DIVISIONS | | | GROUP SYMBOLS | TYPICAL NAMES |
|---|---|---|---|---|
| COARSE GRAINED SOILS (More than 50% of material is LARGER than No. 200 sieve size) | GRAVELS (More than 50% of coarse fraction is LARGER than the No. 4 sieve size) | CLEAN GRAVELS (Little or no fines) | GW | Well graded gravels, gravel - sand mixtures, little or no fines. |
| | | | GP | Poorly graded gravels or gravel - sand mixtures, little or no fines. |
| | | GRAVELS WITH FINES (Appreciable amt. of fines) | GM | Silty gravels, gravel - sand - silt mixtures. |
| | | | GC | Clayey gravels, gravel - sand - clay mixtures. |
| | SANDS (More than 50% of coarse fraction is SMALLER than the No. 4 sieve size) | CLEAN SANDS (Little or no fines) | SW | Well graded sands, gravelly sands, little or no fines. |
| | | | SP | Poorly graded sands or gravelly sands, little or no fines. |
| | | SANDS WITH FINES (Appreciable amt. of fines) | SM | Silty sands, sand-silt mixtures. |
| | | | SC | Clayey sands, sand-clay mixtures. |
| FINE GRAINED SOILS (More than 50% of material is SMALLER than No. 200 sieve size) | SILTS AND CLAYS (Liquid limit LESS than 50) | | ML | Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity. |
| | | | CL | Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays. |
| | | | OL | Organic silts and organic silty clays of low plasticity. |
| | SILTS AND CLAYS (Liquid limit GREATER than 50) | | MH | Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts. |
| | | | CH | Inorganic clays of high plasticity, fat clays. |
| | | | OH | Organic clays of medium to high plasticity, organic silts. |
| HIGHLY ORGANIC SOILS | | | Pt | Peat and other highly organic soils. |

**BOUNDARY CLASSIFICATIONS:** Soils possessing characteristics of two groups are designated by combinations of group symbols.

## PARTICLE SIZE LIMITS

| SILT OR CLAY | SAND | | | GRAVEL | | COBBLES | BOULDERS |
|---|---|---|---|---|---|---|---|
| | FINE | MEDIUM | COARSE | FINE | COARSE | | |

No. 200 No. 40 No. 10 No. 4 ¾ in. 3 in. (12 in.)

U.S STANDARD SIEVE SIZE

## RELATIVE DENSITY (sand-silt)

Very Loose – Less than 4 blows per foot
Loose – 4 to 10 blows/ft.
Medium – 10 to 30 blows/ft.
Dense – 30 to 50 blows/ft.
Very Dense – More than 50 blows/ft.

## CONSISTENCY (clay)

Very Soft – Less than 2 blows per foot
Soft – 2 to 4 blows/ft.
Medium – 4 to 8 blows/ft.
Stiff – 8 to 15 blows/ft.
Very Stiff – 15 to 30 blows/ft.
Hard – More than 30 blows/ft.


## KEY TO BORING LOGS




Number of blows of a 140-lb. weight falling 30 in. in req'd. to drive st'd. spoon one foot.




Thin-wall Shelby tube undisturbed sampler used




Free ground water level




Percent core recovery from rock core-drilling operations



Sample not recovered



Fill



Limestone



Sandstone



Igneous Rock




Shale

# APPENDIX D.3

# SURFACE WATER INTAKES

# Bedford City Utilities




Surface Water Intake

500 Foot Radius


1000 Foot Radius

500 0 500 1000 Feet

N

IDEM

# Mitchell Water Department



THERE ARE NO ATTACHMENTS FOR APPENDIX E